

**VOLUME II**  
**REVISED**  
**REMEDIAL INVESTIGATION REPORT**  
**JASCO CHEMICAL CORPORATION**  
**MOUNTAIN VIEW, CALIFORNIA**

**APPENDIX A - REFERENCES**

**APPENDIX B - BOREHOLE LITHOLOGIC LOGS**

**APPENDIX C - MONITOR WELL CONSTRUCTION DIAGRAMS**

**APPENDIX D - LABORATORY INVESTIGATION OF  
ENGINEERING PROPERTIES OF SOIL**

**APPENDIX E - AQUIFER TESTING REPORT**

**Prepared by:**  
**OHM Remediation Services Corp.**  
**Sacramento, California**

**On behalf of:**  
**Jasco Chemical Corporation**  
**Mountain View, California**

**February 1, 1991**

**REVISED  
RI REPORT**

**JASCO  
CHEMICAL  
CORP.**

**MOUNTAIN  
VIEW,  
CA**

**VOLUME  
II**

**February 1  
1991**

**VOLUME II**  
**REVISED**  
**REMEDIAL INVESTIGATION REPORT**  
**JASCO CHEMICAL CORPORATION**  
**MOUNTAIN VIEW, CALIFORNIA**

**APPENDIX A - REFERENCES**

**APPENDIX B - BOREHOLE LITHOLOGIC LOGS**

**APPENDIX C - MONITOR WELL CONSTRUCTION DIAGRAMS**

**APPENDIX D - LABORATORY INVESTIGATION OF  
ENGINEERING PROPERTIES OF SOIL**

**APPENDIX E - AQUIFER TESTING REPORT**

**Prepared by:**  
**OHM Remediation Services Corp.**  
**Sacramento, California**

**On behalf of:**  
**Jasco Chemical Corporation**  
**Mountain View, California**

**February 1, 1991**

**APPENDIX A**  
**REFERENCES**

## REFERENCES

- Driscoll, Fletcher G., "Groundwater and Wells," Johnson Division, St. Paul, Minnesota, 1986
- Harding Lawson Associates, April 30, 1987. "Remedial Investigation Report - Working Document, Chapter 4, Remedial Investigation/Feasibility Study, Middlefield-Ellis-Whisman Area, Mountain View, California." Draft report prepared for EPA, Region IX on behalf of Fairchild Semiconductor Corporation, Intel Corporation, Raytheon Corporation, April 30, 1987
- Harding Lawson Associates, "Evaluation of Current Site Conditions, Jasco Chemical Corporation, 1710 Villa Street, Mountain View, California," January 25, 1989
- Harding Lawson Associates, "Interim Remedial Measures, October through November, 1988, Jasco Chemical Corporation, Mountain View, California," February 15, 1989
- Harding Lawson Associates, "Summary of Work to Date, Jasco Chemical Corporation, Mountain View, California," February 16, 1989
- Javandel, I and Tsang, C., "Capture Zone Type Curves: A Tool for Aquifer Cleanup," Groundwater, Vol. 24, No.5, September-October, 1986
- Keeley, J and Tsang, C., "Velocity Plots and Capture Zones of Pumping Centers for Groundwater Investigations," Groundwater, Vol. 21, No. 6, November-December, 1983
- Levine-Fricke, "Results of Hydrogeologic Investigation North of Highway 101, Mountain View, California" Report prepared for Spectra Physics, Inc., March 13, 1986
- O.H. Materials Corporation, "Revised Workplan for Remedial Investigation/Feasibility Study, Jasco Chemical Corporation, Mountain View, California," August 31, 1989
- O.H. Materials Corporation, "Sampling and Analysis Plan (SAP), Jasco Chemical Corporation, Mountain View, California," February 1990
- Questa Engineering Corporation, "Preliminary Groundwater Investigation," June 1984
- Questa Engineering Corporation, "Jasco Monitoring Well V-2," October, 1986
- Questa Engineering Corporation, "Installation of Well V-3, Permeability Studies, Soil and Groundwater Sampling and Analysis," December 5, 1986

Tracer Research Corporation, "Tracer Leak Testing Proposal for 8 Underground Storage Tanks at the Jasco Chemical Facility, Mountain View, California," April 1989

USEPA, "Optimizing Pumping Strategies for Contaminant Studies and Remedial Action," EPA Report No. EPA-600/J-84-086, 1986

USGS, "Flatland Deposits of the San Francisco Bay Region, California - Their Geology and Engineering Properties and Their Importance to Comprehensive Planning" Geological Survey Professional Paper 943, 1979.

Wahler Associates, "Preliminary Report, Shallow Soil Gas Investigation," March 4, 1987

Wahler Associates, "Phase I Groundwater Investigation Workplan," March 4, 1987

Wahler Associates, "Chemical Testing Results, Collection Sump," April 27, 1987

Wahler Associates, "Phase I Hydrogeologic Investigation," June 1987

Wahler Associates, "Site Inspection Report," June 1987

Wahler Associates, "On-Site source Identification Investigation," June 1987

Wahler Associates, "Well Location Maps," July 30, 1987

Wahler Associates, "Collection and Disposal of Surface Runoff," September 16, 1987

Wahler Associates, "On-Site Runoff Management," November 2, 1987

Wahler Associates, "Phase II Hydrogeologic Investigation," November 1987

Wahler Associates, "Aquifer Testing Report," December 21, 1987

Wahler Associates, "Quality Assurance/Quality Control Project Plan," December 1987

Wahler Associates, "Sampling Plan," December 1987

Wahler Associates, "Site Health and Safety Plan," December 1987

Wahler Associates, "Proposal for Potential Conduit Investigation," December 1987

Wahler Associates, "Installation of Diesel Tank Monitoring Well," December 30, 1987

Wahler Associates, "Excavation and Removal of Diesel Tank,"  
February 8, 1988

Wahler Associates, "Interim Runoff Management Plan," February 29,  
1988

Wahler Associates, "Phase IIa Hydrogeologic Investigation," March  
1988

Wahler Associates, "Potential Conduits Investigation Preliminary  
Report," March 1988

Wahler Associates, "Potential Conduits Investigation," May 1988

Wahler Associates, "Surface Water and Soil Sampling  
Investigation," May 6, 1988

Wahler Associates, "Destruction of Dry Wells," June 9, 1988

Wahler Associates, "Evaluation of Interim Remedial Alternatives,  
Volumes 1 and 2," June 1988

In addition, monthly status reports documenting progress in  
the investigation and remediation of the site have been prepared  
by Jasco Chemical Corporation's environmental consultants and  
submitted to the California Regional Water Quality Control Board  
since March of 1987. Quarterly groundwater monitoring reports have  
also been submitted to RWQCB since this time.

**APPENDIX B**  
**BOREHOLE LITHOLOGIC LOGS**

## BORING LOG: V-1

LOCATION: 1710 Villa Street, Mountain View, California

ELEVATION: 62 feet (approximately) U.S.G.S. Datum

DATE &amp; TIME DRILLED: May 24, 1984 (1500 to 1740 Hours)

WATER LEVEL: Free water encountered at 29 feet; at completion of drilling  
water level 24 feet below the ground surface.

<u>DEPTH IN FEET</u>	<u>BLOWS/FOOT</u>	<u>DESCRIPTION</u>
0	- 0.2	AC paving and base material
0.2	- 11	Grayish brown (5YR 3/2) silty clay (CL) medium stiff, damp. Some gravel at 8 feet.
11	- 12.5	Moderate brown (5YR 3/4) silty clay (CL) medium stiff, moist.
12.5	- 15	Medium gray (N 5) sandstone fragments (SP) angular, up to 1/2 inch dia.
15	- 20	Dark yellowish brown (10YR 4/2) silty clay (CL), stiff, moist.
15.5	----- 50 -----	Undisturbed soil sample. Grades gravelly and wet at 17 feet
20	- 25	Grayish olive (10Y 4/2) silty clay (CL) containing well preserved gastropods shells up to 0.3 inches long, stiff, damp.
20.5	----- 37 -----	Undisturbed soil sample.
25	- 35	Dark grayish green (5G 4/2) silty to sandy clay (CL to ML) with some peat and rock fragments, stiff, wet.
25.5	----- 40 -----	Undisturbed soil sample.
30.5	----- 22 -----	Undisturbed soil sample. Increase in rock fragments, up to 1 inch in dia., fragments appear to be composed of serpentine, soft, saturated.
35	- 50	Olive gray (5Y 3/2) silty to sandy clay (CL to ML) with occasional rock fragment, stiff, damp.
50.5	----- 50 blows for 3" -----	Disturbed soil sample. Fine-grained sandy to silty gravel (SW), angular to subangular, up to 1/2 inch in dia. (average size 0.02"), loose, saturated.
BOTTOM OF BORING		

# **Questa Engineering Corporation**

Civil, Environmental & Agricultural Engineers

DRILL HOLE NUMBER VILLA #2


DATE DRILLED 8/22/86

**WELL HEAD ELEVATION**

**DRILLING METHOD 8" HOLLOW STEM AUGER**

WELL O.D. 2"

## CLASSIFICATION and Remarks



logged by PNC

LOG of Drill Hole Number VILLA #2

Fig. 3

checked by

at JASCO PAINT CO. Proj No. 8669 1 of 2


Questa Engineering Corporation  
Civil, Environmental & Agricultural Engineers

DRILL HOLE NUMBER VILLA #2

DATE DRILLED 8/22/86

Moisture Content (%)	Dry Density	Blows / ft.	Groundwater Level	DEPTH (ft.)	Sample Interval	Graphic Log
----------------------	-------------	-------------	-------------------	-------------	-----------------	-------------

CLASSIFICATION and Remarks



logged by PNC

checked by \_\_\_\_\_

LOG of Drill Hole Number VILLA #2


at JASCO PAINT CO. Proj No. 8669 2 of 2

DRILL HOLE NUMBER V-3

DATE DRILLED 11-3-1986

DRILLING METHOD 10" HOLLOW  
STEM AUGER  
WELL O.D. 5" DIA.

CLASSIFICATION and Remarks



logged by PNC

checked by \_\_\_\_\_

LOG of Drill Hole Number V-3

at VIASCO

Proj No. 8669 1 of 2

Figure 3

DRILL HOLE NUMBER V-3


DATE DRILLED 11-3-1986

WELL HEAD ELEVATION \_\_\_\_\_

DRILLING METHOD 10" HOLLOW STEM AUGER

WELL O.D. 5" DIA.

CLASSIFICATION and Remarks



(CL) SITY CLAY, Blue-Green, Smooth.  
Thin Sandy lenses.  
— Few Wood Chips & Rootlets  
Faint Odor.

(SP) SAND & Fine GRAVEL with SITY  
CLAY LENSES. Odor.  
— Clay Lens  
Coarse SAND & Fine GRAVEL  
LENSES OF Fine Sand.

(CL) CLAY, Blue Grey.  
STIFF.

logged by AVC

LOG of Drill Hole Number V-3

checked by \_\_\_\_\_

at JASCO

Proj No. 8669 2 of 2

BORING LOCATION JASCO Chemical Corp. 8' SE of U-2						GROUND EL.	
DEPTH/ELEV. WATER 25' 7/1/87 FOR DEVELOP DRILL CONTRACTOR HEW DRILLING						TOTAL DEPTH 40'	
DRILL RIG CME-75	BORING DIA. 10"	DATE DRILLED 7-2-87			LOGGED BY RGB		
SOIL CLASS.	DESCRIPTION	DEPTH	SAMPLE NO.	PR RQD	REC.	MODE	REMARKS
GP	FILL. 0-3.0' SANDY GRAVEL, light gray dirt loose	0			HA		Begin 1340
CL	ALLUVIUM 3.0-5.0' CLAY, dark gray, damp, 5% coarse sand, highly PLASTIC, very soft, slight odor	2	B-1	2 3	1.2 1.5	DR	2-3.5' Standard penetration TEST (SPT) 140 lb hammer 30" drop
CL	5.0-10.0' SANDY CLAY, blue-gray, damp soil, 5% coarse sand, 15% fine sand, slight sewerage odor	4			HA		5-6.5 SPT
CL	10.0-14.4' CLAY, brownish black, 5% gravel, high plasticity, stiff, moist, slight sewerage odor. 12-13' dark gray	6	B-2	4 6 7	1.2 1.5	DR	10-11.5 SPT. SPT sample lost, 2nd SPT core rusted with oil
GP	13' increase in moist clay	8			HA		
CL	14.4-15.5' SANDY GRAVEL greenish black, up to 1" clasts, medium dense, moist	10	B-3	4 6	0.8 1.5	DR/ IP	14-15.5' rel. modified driven. Sample Saved for EPA 0010 analysis. G-1425 both bentonite samples taken with contractor's sand layer seen in sample
CL	15.5-23.0' SANDY CLAY greenish black, 10% sand very moist. soft, highly plastic	12			HA		
		14	S-4 B-4	8 10 7	1.2 1.5	DR	
		16			HA		
		18			HA		
		20					MINERAL OCCURRENCES

Wahler  
Associates

JASCO CHEMICAL CORP.

EXPLORATION BORING LOG  
PROJECT NO. JCG-1041A  
SHEET NO. 1 of 2

BORING NO.  
V-4

BORING LOCATION							GROUND EL.
DEPTH/ELEV. WATER		DRILL CONTRACTOR					TOTAL DEPTH
DRILL RIG		BORING DIA.	DATE DRILLED			LOGGED BY	
SOIL CLASS.	DESCRIPTION	DEPTH	SAMPLE NO.	PR RQD	REC.	MODE	REMARKS
CL	20-25.8 medium plastic, very stiff, moist, sewer  DATA ON THIS LOG ARE AN APPROXIMATION OF THE GEOLOGIC AND SURFACE CONDITIONS BECAUSE THE INFORMATION WAS OBTAINED FROM INDIRECT, DISCONTINUOUS, AND POSSIBLY DISTURBED SAMPLING NECESSITATED BY USE OF SMALL-DIAMETER Holes. ROTARY AND WASH BORING HOLES HAVE OTHER COMPLICATIONS IN THIS REGARD BECAUSE OF THE NEED TO USE DRILLING FLUID AND/OR Casing IN ADVANCING HOLES.  THIS LOG INDICATES CONDITIONS IN THIS HOLE ONLY AT THE DATE INDICATED AND MAY NOT REPRESENT CONDITIONS AT OTHER LOCATIONS AND ON OTHER DATES. ACTUAL WATER LEVELS SHOWN ARE SUBJECT TO VARIATION.  THIS HOLE WAS LOGGED IN SUCH A WAY AS TO PROVIDE DATA PRIMARILY FOR DESIGN PURPOSES AND NOT NECESSARILY FOR THE PURPOSES OF SPECIFIC CONTRACTORS.  THE STRATIFICATION LINES OR DEPTH INTERVALS REPRESENT THE APPROXIMATE BOUNDARIES BETWEEN MATERIAL TYPES, AND THE TRANSITIONS MAY BE GRADUAL.  SOIL CLASSIFICATIONS SHOWN ON LOGS ARE FIELD CLASSIFICATIONS BASED ON THE UNIFIED SOILS CLASSIFICATION SYSTEM.	20	S-5/ B-5	10 12 12	1.4 1.5	DR	20-21.5 gl modified driven 1440 TWO SAMPLES TAKEN, ONE FOR GPR 8010, ONE FOR VERTICAL FORM TESTING
SC-CL	25.8-26.2 CLAYEY SAND greenish black, 50-70% coarse sand, 30-50% clay	22					
CL	26	B-6	4 6 5	1.5	DR	24	INCREASE IN MOISTURE
GP	28.0-34.8 SANDY GRAVEL greenish black, 20-60% sand 40-60% gravel	28				HA	25-26.5 SPT SIGHT WATER RISES TO 25'
	32	B-7	6 18 22	1.5 1.5	DR	30	28' - driller says beginning of gravel - water encountered.
	34	B-8	18 18 7	1.5 1.5	DR	32	31-32.5 SPT
CL	34.8-40.0 SANDY CLAY greenish black, 30% sand, 70% clay loamy, very stiff, very moist, moderate plasticity, <5% sand	36				HA	33.5-35 SPT gravel/clay contact seen at 34.8'
	38	S-9 B-9	8 12 12	1.4 1.5	DR	40	38.5-40 gl modified 2-33 PVC 0-25 GR OUT 25-22 150 MM 27-35 100, 250 MM 28-35 500 SC/GR 35-40 600 MM

W Wahler Associates	JACCO CHEMICAL CORP.	EXPLORATION BORING LOG	BORING NO.
		PROJECT NO.	SHEET NO.
		JCD-1944	2 OF 1
			V-4

BORING LOCATION JASCO CHEMICAL CORPORATION							GROUND EL.
DEPTH/ELEV. WATER 32.0'			DRILL CONTRACTOR HEN DRILLING				TOTAL DEPTH 40.5'
DRILL RIG CMC-75		BORING DIA. 8"	DATE DRILLED 4-27-67		LOGGED BY RGB		
SOIL CLASS.	DESCRIPTION	DEPTH	SAMPLE NO.	PR RQD	REC.	MODE	REMARKS
	0.0-1.0 - Excavation - completed during utilities search.	0					Continuous sampling used for sample collection.
GP	1.0-2.0 <sup>FILL</sup> SANDY GRAVEL: light brown "AED 1" clst interspersed with sand pebbles; laminar; dry; loose  ALLUVIUM	2	CC-1	1.5 2.5	CC		
	2.0-8.6 SANDY CLAY: dark brown; damp; 5% coarse sand, poorly graded.  5.0-8.6 color change to light brown; The sand content varies from 5 to 30%.	4	CC-2	2.5 2.5	CC		
CL		6	CC-3	2.5 2.5	CC		
		8	CC-4	2.5 2.5	CC		
SC	9.6-12.0 CLAYEY SAND: light brown 50% sand; 30% clay; 20% gravel, clst up to 1" diameter; damp.  10.5 - increase in gravel content	10					
		12	CC-5	2.5 2.5	CC		
	12.0-23.5+ Gravelly Sand: light brown, 40-60% sand; 35-55% gravel, clst up to 1"; 0-5% fines; slightly damp, loose	14	CC-6	0.5 2.5	CC		
SP/GP	14.5 - increase in clay content	16	CC-7	2.5 2.5	CC		
		18	CC-8	2.5 2.5	CC		CC-8 and CC-9 not recovered due to large gravel clst increasing removal of sample.
		20					0.5 feet of CC-8 recovered on second trip out relatively STABILIZED

Wahler  
Associates

JASCO CHEMICAL CORP.

EXPLORATION BORING LOG

BORING NO.

PROJECT NO.  
CMC-75

SHEET NO.  
1 of 3

V-5

BORING LOCATION						GROUND EL.	
DEPTH/ELEV. WATER		DRILL CONTRACTOR				TOTAL DEPTH	
DRILL RIG		BORING DIA.	DATE DRILLED			LOGGED BY	
SOIL CLASS.	DESCRIPTION	DEPTH	SAMPLE NO.	PR ROD	REC.	MODE	REMARKS
SP/GP	12.0-23.5 - Gravely sand (Cont.)	20					CC-9 NOT recovered.
		22	CC-9		0 2.5	CC	
CL	23.5-31.75 - SANDY CLAY: medium brown, gr contact: 50% clay; 25% gravel; moist 24.0 - decrease in gravel content increase in clay content.	24	CC-10		2.0 2.5	CC	Gravely sand at bottom of core cutter. small clay layers interbedded with gravel.
		26	CC-11		2.5 2.5	CC	
CL		28	CC-12		2.5 2.5	CC	
	31.75- Increase in water content Contact is gradational.	30					
CL	31.75-33.5: SILTY CLAY: blue-green, <2% sand, moderate plasticity, moist	32	CC-13		2.5 2.5	CC	
		34					32.5' standing water.
GP	33.5- Contact is gradational 33.5-35.5 - CLAYER GRAVEL: greenish black; 60% gravel; 20% sand; 20% fines, wet	34	CC-14		2.5 2.5	CC	standing water at 34.1' < 1 foot of standing water
		36	CC-15		2.5 2.5	CC	
CL	36.5-39.5 - SILTY CLAY: greenish black, 0-5%, sand; moderate plasticity; soft.	38	CC-16		1.0 2.5	P	CC-16 pushed, not drilled, hard clay encountered, not 311 recovered, standing water at 32.0'
CL	39.5-40.5 - SANDY CLAY: light brown; 20-40% very fine sand, 60-80% silt; moderate plasticity	40					

W Wichter Associates	JASCO CHEMICAL CORP	EXPLORATION BORING LOG		BORING NO.
		PROJECT NO.	SHEET NO.	V-5
		JASCO. 2000.1	2 OF 2	

BORING LOCATION						GROUND EL.				
DEPTH/ELEV. WATER			DRILL CONTRACTOR			TOTAL DEPTH				
DRILL RIG		BORING DIA.		DATE DRILLED			LOGGED BY			
SOIL CLASS.	DESCRIPTION		DEPTH	SAMPLE NO.	PR RQD	REC.	MODE	REMARKS		
	375-40.5 - SANDYCLAY (cont.)		40					375-40.5 - recovered, at 40.5' the sampler could not be pushed further because of stiff clays so boring was stopped at 40.5'		
	40.5' END OF BORING		42							
			44					<u>WELL CONSTRUCTION INFO.</u>		
			46					0.0-31.0' - GROUT 31.0-32.0' - Bentonite 32.0-36.5' - sand 33.5-36.5' - screen. 36.5-410.5' - Bentonite		
			48							
			50							
			52							
			54							
			56							
			58							
			60							
DATA ON THIS LOG ARE AN APPROXIMATION OF THE GEOLOGIC AND SURFACE CONDITIONS BECAUSE THE INFORMATION WAS OBTAINED FROM INDIRECT, DISCONTINUOUS, AND POSSIBLY DISTURBED SAMPLING NECESSITATED BY USE OF SMALL-DIAMETER HOLES. ROTARY AND WASH BORING HOLES HAVE FURTHER COMPLICATIONS IN THIS REGARD BECAUSE OF THE NEED TO USE DRILLING FLUID AND/OR CASTING IN ADVANCING HOLES.										
THIS LOG INDICATES CONDITIONS IN THIS HOLE ONLY AT THE DATE INDICATED AND MAY NOT REPRESENT CONDITIONS AT OTHER LOCATIONS AND ON OTHER DATES. ANY WATER LEVELS SHOWN ARE SUBJECT TO VARIATION.										
THIS HOLE WAS LOGGED IN SUCH A WAY AS TO PROVIDE DATA PRIMARILY FOR DESIGN PURPOSES AND NOT NECESSARILY FOR THE PURPOSES OF SPECIFIC CONTRACTORS.										
THE STRATIFICATION LINES OR DEPTH INTERVALS REPRESENT THE APPROXIMATE BOUNDARIES BETWEEN MATERIAL TYPES, AND THE TRANSITIONS MAY BE GRADUAL.										
SOIL CLASSIFICATIONS SHOWN ON LOGS ARE FIELD CLASSIFICATIONS BASED ON THE UNIFIED SOILS CLASSIFICATION SYSTEM.										
W Wahler Associates		EXPLORATION BORING LOG			BORING NO.		V-5			
		PROJECT NO.			SHEET #3		3 OF 3			
		JCD-10417								

BORING LOCATION JASCO CHEMICAL CORPORATION						GROUND EL.
DEPTH/ELEV. WATER 24.5'		DRILL CONTRACTOR HESS DRILLING				TOTAL DEPTH 17.5'
DRILL RIG CME-75		BORING DIA. 8"	DATE DRILLED 4-28-87		LOGGED BY RBC	

SOIL CLASS.	DESCRIPTION	DEPTH	SAMPLE NO.	PR ROD	REC.	MODE	REMARKS
CL	FILL 0.0-4.5: GRAVELY CLAY: dark brown; low plasticity; 60% clay, 20% sand, 20% gravel. Up to 1" diameter, loose, dry, earthy odor.	0	CC-1		2.5 2.5		
CL	ACLUVIAL 4.5-13.0. LEANCLAY: dark brown; <20% coarse material, iron staining within cracks, moderate plasticity, slightly damp.	2					
CL	7.5- Fine sand content increases to 10% 8.0- Color changes to yellow brown 9.0- color changes to greenish-black, sand content decreases to <5%, low to moderate plasticity.	4	CC-2		1.5 2.5		
CL/SC	13.0-14.5 - SANDY CLAY: yellow brown; sand content increases with depth from 13 to 14.5 feet, slightly damp, calcite mottling	6	CC-3		2.5 2.5		
SP/SC	14.5-16.0 Gravelly Sand; yellow brown, gravel content increases with depth towards 16.0 feet, 40-60% gravel, 40-60% sand & 10% fine.	8	CC-4		2.5 2.5		
GP/SP	16.0-17.5 - Sandy Gravel: Yellow brown, 40-60% gravel, 20-35 up to 1" lager; 40-60% sand, medium to fine, dry, loose, calcite mottling	10	CC-5		2.5 2.5		
SC/CL	17.5-19.5 - Clayey Sand: yellow brown, 50-60% sand, 40-50% clay, damp.	12	CC-6		2.0 2.5		
CH	19.5-21.5 - Clay: yellow brown; 25% fine gravel; high plasticity.	14	CC-7		2.5 2.5		
		16	CC-8		2.5 2.5		
		18	CC-9		2.5 2.5		
		20					

CONTACTS ARE  
GRADATIONAL

W Wahler Associates	JASCO CHEMICAL CORP.	EXPLORATION BORING LOG		BORING NO.
		PROJECT NO.	SHEET NO.	V-6
		JRC-10417	1 OF 2	

BORING LOCATION							GROUND EL.
DEPTH/ELEV. WATER		DRILL CONTRACTOR				TOTAL DEPTH	
DRILL RIG		BORING DIA.		DATE DRILLED			LOGGED BY
SOIL CLASS.	DESCRIPTION	DEPTH	SAMPLE NO.	PR RQD	REC.	MODE	REMARKS
CH	19.5-21.5 - CLAY (cont.)	20					
SC/CL	21.5-26.5 - Clayey Sand; Medium brown; 40-50% clay, 40-50% sand, 0-10% gravel up to 1" long, damp, 0.25" diameter oxidized clay nodules dispersed in clay. 22.5- gravel content increases to 20-40%.	22	CC-9	2.5 2.5	CC		
	25.0 - water present in 2"						
	gravel lens: very moist.						
CL	26.5-35.5 - GRAVELY CLAY: clay; 5-15% fine gravel; moderate plasticity, no fossils present, calcicrete mottling, damp	26	CC-11	2.5 2.5	CC		
		28	CC-12	2.5 2.5	CC		
		30					
		32	CC-13	2.5 2.5	CC		
	32.5- moderate to high plasticity, 10% gravel class up to 0.25" diameter						
		34	CC-14	2.5 2.5	CC		
GC	35.5-39.0 - Clayey Gravel: 30-40% clay, 10-20% sand, 40-60% gravel, very moist.	36	CC-15	2.5 2.5	CC		
GC	38.0-39.0 - CLAYEY GRAVEL: yellowish, 40-50% gravel, 30-40% clay, 10-20% sand, very moist.	38	CC-16	1.0 2.5	CC		
SP	39.0-42.0 - Sand, Gravel: yellowish, 40% coarse sand, 10-14% fine gravel, 20% gravel, 6-12" up to 0.5" dia. unsorted.	40					

W  
Wohler  
Associates

JASCO CONSTRUCTION CORP.

EXPLORATION BORING LOG

BORING NO.

PROJECT NO.	SHEET NO.	
DEC 10 1984	2 of 3	V-6

BORING LOCATION							GROUND EL.
DEPTH/ELEV. WATER		DRILL CONTRACTOR					TOTAL DEPTH
DRILL RIG		BORING DIA.	DATE DRILLED			LOGGED BY	
SOIL CLASS.	DESCRIPTION	DEPTH	SAMPLE NO.	PR RQD	REC.	MODE	REMARKS
GP	39.0-42.7 Sandy Gravel (cont.)	40					
CL	42.7-47.3: Clay; yellow brown; 0-10% medium to coarse sand, moderate plasticity, occasional rootlets, caliche veinlets. 43.7- Color change to mottled olive green/brown.	42	CC-17	2.5 2.5	CC		4.8' aquitard*
SC	46.9 - Color change to yellow brown 47.3-47.5 - CLAYEY SAND: Yellow brown; 80-90% Medium Sand, 10-20% fines, very moist. END OF BORING 47.5'	44	CC-18	2.5 2.5	CC		<u>Well Construction info</u>
		46	CC-19	2.5 2.5	CC		
		48					0.0-34.5 - Grout 34.5-35.5 - Bentonite 35.5-42.7 - Sand 37.5-42.7 - Screen 42.7-47.5 - Bentonite
		50					
		52					
		54					
		56					
		58					
		60					
W Wahler Associates		JASCO CHEMICAL CORP.			EXPLORATION BORING LOG		BORING NO.
		PROJECT NO.		SHEET NO.		V-6	
		JCO-104.1		3 OF 3			

DATA ON THIS LOG ARE AN APPROXIMATION OF THE GEOPHIC AND SURFACE CONDITIONS BECAUSE THE INFORMATION WAS OBTAINED FROM INTRACONTINUOUS, AND POSSIBLY DISTURBED, SAMPLING NECESSITATED BY USE OF SMALL-DIAMETER HOLES. ROTARY AND WASH BORING HOLES HAVE FURTHER IMPLICATIONS IN THIS REGARD BECAUSE OF THE NEED TO USE DRILLING FLUID AND/OR CASING IN ADVANCING HOLES.

THIS LOG INDICATES CONDITIONS IN THIS BORE ONLY ON THE DATE INDICATED AND MAY NOT REPRESENT CONDITIONS AT OTHER LOCATIONS AND ON OTHER DATES. ART. WATER LEVELS SHOWN ARE SUBJECT TO VARIATION.

THIS BORE WAS LOGGED IN SUCH A MANNER AS TO PROVIDE DATA PERTINENT FOR DESIGN PURPOSES AND NOT NECESSARILY FOR THE PURPOSES OF SPECIFIC CONTRACTS.

THE STRATIFICATION LINES OR DEPTH INTERVALS REPRESENT THE APPROPRIATE BOUNDARIES BETWEEN MATERIAL TYPES, AND THE TRANSITIONS ARE GRADUAL.

SOIL CLASSIFICATIONS SHOWN ON LOGS ARE FIELD CLASSIFICATIONS BASED ON THE UNIFIED SOILS CLASSIFICATION SYSTEM.

BORING LOCATION JASCO CHEMICAL CORPORATION						GROUND EL.
DEPTH/ELEV. WATER 24.0' final		DRILL CONTRACTOR HEW DRILLING				TOTAL DEPTH 42.5
DRILL RIG CME-75	BORING DIA. 8"	DATE DRILLED 4-29-87		LOGGED BY RGB		

SOIL CLASS.	DESCRIPTION	DEPTH	SAMPLE NO.	PR RQD	REC.	MODE	REMARKS
CL	FILL 0.0-1.7: SANDY CLAY: dark brown 60% clay, 40% sand; moderate plasticity, earthy odor, twigs and leaf fragments, dry loose	0	CC-1	2.5 2.5	CC		
CL	ALLUVIUM 1.7-10.5: LEAN CLAY: dark brown 0-5% gravel, fine; organic odor twigs fragments, moderate plasticity caliche veins, slightly damp soil.	2					
		4	CC-2	2.5 2.5	CC		
		6	CC-3	2.5 2.5	CC		
		8	CC-4	2.5 2.5	CC		
	10.5-22.0: LEAN CLAY: yellow brown; 0-5% coarse sand; caliche veins; moderate plasticity, moist,	10		2.5 2.5	CC		
CL	13.0 - Color change to muted blue/green/yellow brown 13.8 - Color change to yellow-brown	12	CC-5	2.5 2.5	CC		
		14	CC-6	2.5 2.5	CC		
	16.5 - Moderate gravel content to up to 20% gravel, classed 0.25-0.75" size	16	CC-7	2.5 2.5	CC		
		18	CC-8	2.0 2.5	CC		
		20					

W Wahler Associates	JASCO CHEMICAL CORP.	EXPLORATION BORING LOG		BORING NO.
		PROJECT NO.	SHEET NO.	V-7
		SDO-1044	1 OF 3	

BORING LOCATION						GROUND EL.	
DEPTH/ELEV. WATER		DRILL CONTRACTOR			TOTAL DEPTH		
DRILL RIG		BORING DIA.		DATE DRILLED			LOGGED BY
SOIL CLASS.	DESCRIPTION	DEPTH	SAMPLE NO.	PR RQD	REC.	MODE	REMARKS
CL	10.5-22.0 : LEAN CLAY (Cont.)	20	CC-9	2.5 2.5	CC		
GP	22.0-26.0: Sandy Gravel: yellow brown; 60% gravel, 40% coarse sand; Gravel clasts up to 0.5" long; very wet to saturated; gravel clasts subangular to subrounded	22					22.5' water encountered - CC-10 not recovered
Sp	26.0-26.9: Gravely Sand; yellow-brown saturated	26	CC-11	2.0 2.5	CC		
CL	26.9-27.3: Clay: mottled blue/yellow						
CL/GC	27.3-28.3: Gravely clay; yellow-brown, 40-60% clay, 40-60% fine gravel very wet to saturated	28	CC-12	2.5 2.5	CC		
CL	28.3-29.8: Sandy Clay; yellow-brown, 60% clay, 30% sand, 10% gravel; very wet						
CL	29.8-30.8: Clay; blue-green; <5% coarse sand; moderate to high plasticity; moist	30					
SC	30.8-33.25: Clayey Sand; yellow-brown; 70% medium sand, 30% clay; occasional gravel clasts; very moist to saturated		CC-13	2.5 2.5	CC		
CL	33.25-35.25: Sand; Clay; blue-green; 70% clay, 30% sand; moderate plasticity - saturated.	34	CC-14	2.5 2.5	CC		
CL	35.25-35.5: Sandy Gravel; greenish-black						
CL	35.5-39.6: GRAVELY CLAY; greenish black; 60-80% clay, 20-40% gravel up to 0.5" diameter, fine gravel, moist.	36	CC-15	2.5 2.5	CC		
CH	39.6-42.5: CLAY; yellowish green; 70-75% clay, 20-25% sand; moist.	40	CC-16	2.5 2.5	CC		

W A Wohler Associates	SASCO CHEMICAL CO., INC.	EXPLORATION BORING LOG		BORING NO. V-7
		PROJECT NO. SD-11014	SHEET NO. 2 OF 3	

BORING LOCATION					GROUND EL.		
DEPTH/ELEV. WATER		DRILL CONTRACTOR			TOTAL DEPTH		
DRILL RIG		BORING DIA.	DATE DRILLED			LOGGED BY	
SOIL CLASS.	DESCRIPTION	DEPTH	SAMPLE NO.	PR ROD	REC.	MODE	REMARKS
	39.6-42.5 - CLAY (cont)	40					
CH		42	CC-17	2.5 2.5	CC		standing water at 24.0' 8 feet standing water
	END OF BORING 42.5'	44					Well Construction Info
		46					0.0-21.0 - GROUT
		48					21.0-22.0 - BENTONITE
		50					22.0-35.5 - SAND
		52					24-35.5 - SCREEN
		54					35.5-42.5 - BENTONITE
		56					
		58					
		60					
<small>DATA ON THIS LOG ARE AN APPROXIMATION OF THE GEOLOGIC AND SURFACE CONDITIONS BECAUSE THE INFORMATION WAS OBTAINED FROM INDIRECT, DEDUCTIVE, AND POSSIBLY OBSERVATIONAL METHODS REPRESENTED BY USE OF DRILL-TESTER Holes. ROTARY AND WASH PAVING Holes MAY FURTHER COMPLICATIONS IN THIS REGARD BECAUSE OF THE NEED TO USE DRILLING FLUID AND/OR CASTING IN ADVANCING HOLES.</small>							
<small>THIS LOG INDICATES CONDITIONS IN THIS BOREHOLE ONLY ON THE DATE INDICATED AND MAY NOT REPRESENT CONDITIONS AT OTHER LOCATIONS AND ON OTHER DATES. ANY WATER LEVELS SHOWN ARE SUBJECT TO VARIATION.</small>							
<small>THIS BOREHOLE WAS LOGGED IN SUCH A WAY AS TO PROVIDE DATA PRIMARILY FOR DESIGN PURPOSES AND NOT NECESSARILY FOR THE PURPOSES OF SPECIFIC CONTRACTORS.</small>							
<small>THE STRATIFICATION LINES OR DEPTH INTERVALS REPRESENT THE APPROPRIATE BOUNDARIES BETWEEN MATERIAL TYPES, AND THE TRANSITIONS MAY BE GRADUAL.</small>							
<small>SOIL CLASSIFICATIONS SHOWN ON LOGS ARE FIELD CLASSIFICATIONS BASED ON THE UNIFIED SOILS CLASSIFICATION SYSTEM.</small>							
W Wahler Associates	TASCO CHEMICAL CORP.	EXPLORATION BORING LOG			BORING NO.		
		PROJECT NO.			SHEET NO.		V-7
		JFO-104A			3 OF 3		

BORING LOCATION JACCO CHEMICAL CORPORATION							GROUND EL.
DEPTH/ELEV. WATER ~ 23.5' 2-24			DRILL CONTRACTOR PC EXPLORATION			TOTAL DEPTH 49.2	
DRILL RIG Acker Soil Max			BORING DIA. 3"		DATE DRILLED 2-24-88		LOGGED BY RGB/PS
SOIL CLASS.	DESCRIPTION	DEPTH	SAMPLE NO.	PR RQD	REC.	MODE	REMARKS
	ALLUVIUM 0.0-6.2 - SANDY CLAY: dark brown. 0-5% fine sand, occasional coarse sand CLAST, damp.	0 - 2				HA	Begin drilling on x-way at 925 AM after Heathard Safety briefing Drilling performed with tower down. Sampler pushed with rig hydraulics system.
CL-CH		2	R-1	— 0.5 1.5	P		2.0-3.5' - 2.5" diameter California Modified Sampler (calmod) pushed very high hydraulics -drilling is slow due to drilling with tower down.
		4				HA	5.0-6.5 CALMOD
	6.2-13.0 SANDY CLAY: Mottled yellow brown / medium brown. Caliche veinlets; 10-15% fine sand. Low to moderate plasticity	6 - 8	R-2	— 0.5 1.5	P		
CL		8				HA	
	11.4 - Increase in sand content to 20%, Color change to mottled light brown / yellow brown moderate plasticity	10 - 12	R-3	— 0.5 1.5	P		10.0-11.5 CALMOD
CL-CH	13.0-15.0 - Sandy Clay; dark 2-3% occasional 3/4" lens gravel - ST: drilling tough ~5% fine sand, damp	12 - 14				HA	13' - drilling tougher stiff clay with gravel fragments.
CL	15.0-31.5 - Sandy Gravelly Clay: yellow brown, 25% fine to medium sand, 2-3% fine gravel, 5-10% clay; low plasticity, slightly damp	14 - 18	R-4	— 0.5 1.5	P	HA	15.0-16.5 CALMOD
		18					
		20					

 Wahler  
Associates

JACCO CHEMICAL CORPORATION

EXPLORATION BORING LOG

PROJECT NO.  
J50-104H

SHEET NO.  
1 OF 3

BORING NO.  
V-8

BORING LOCATION							GROUND EL.	
DEPTH/ELEV. WATER			DRILL CONTRACTOR				TOTAL DEPTH	
DRILL RIG		BORING DIA.	DATE DRILLED			LOGGED BY		
SOIL CLASS.	DESCRIPTION		DEPTH	SAMPLE NO.	PR ROD	REC.	HOOD	REMARKS
	15.0-31.5 : Sandy Gravelly Clay (Continued)		20			0.5 1.5	P	20.0-21.5 CALMOD
			22	R-5				
			24					23.0 - Drilling easier - soft soil material. H2O 23.7' (10:00AM 2-25)
			26	R-6	—	1.5 1.5	P	25.0-26.5 CALMOD
CL	26.2 - Decrease in sand and gravel content to 10-15%. Increase in moisture content. Moderate plasticity; occasional wood fragments; slight rotting.		28					
			30					30.0-31.5 CALMOD
			32	R-7	—	1.2 1.5	P	
	31.5-42.0 : CLAYEY SAND/SANDY CLAY; yellow brown; 50% medium sand, 10% fine gravel, 40% clay; moderate plasticity; dark, moist. Increases in sand depth.		34					32.0 - H2O ENCOUNTERED
SC-CL			36					
	35.0-36.5 CALMOD		36	R-8	—	1.2 1.5	P	
	37.0 - grading near clayey		38					~37.0 - Drilling Action Gets Hard
			40					
	40.0-41.0 very clayey		40					40.0-41.5 CALMOD

W  
Wchler  
Associates

JASCO CHEMICAL CORPORATION

EXPLORATION BORING LOG

BORING NO.

PROJECT NO.  
JCO-104H

SHEET NO.  
2 OF 2

V-3

**Wahler  
Associates**

JASCO CHEMICAL CORPORATION

## **EXPLORATION BORING LOG**

BORING NO.

PROJECT 40

SHEET NO  
3 OF 3

V-8

BORING LOCATION JASCO Corner of Meridian & Prairie							GROUND EL.
DEPTH/ELEV. WATER ~ 21.0' 2-29-88		DRILL CONTRACTOR P.L. Exploration			TOTAL DEPTH 33.0		
DRILL RIG ACKER "Soil-mix"		BORING DIA. 8.0"	DATE DRILLED 26 Feb. 88			LOGGED BY G.F.Z.	
SOIL CLASS.	DESCRIPTION	DEPTH	SAMPLE NO.	PR ROD	REC.	MODE	REMARKS
CL	0.0 - 6.1 ALLUVIUM ~60-70% fines, high plastic, ~30-40% sand, poorly graded, angular, slight organics; firm to stiff; damp. ~2.9 - 3.1 clean sand 3.5' roots	0.0 - 2.0 4.0			HA	P	Advancing hole with 8.0" hollow stem augers. Sampling with a 20" ID split spoon (S.S.) sampler. Advancing sampler by pushing with system hydraulics. Drilling with lower down Mike Ybarra - Driller Mike - Helper Begin setup 11:30, Drilling 2:15 2.0 - 3.5 Pushed S.S. 5.0 - 6.1 Pushed S.S.
CH	~6.1 - 13.0 CLAY: olive gray with brown mottling; 70% fines; high plastic; <10% sand, fine-grained; some cementation, rnx to HCL; Fe staining; slight white fibrous stiff; damp.	6.0	R-1	1.5 1.5	HA	P	Drilling action is smooth and stiff
SW	~11.0 increase in white ppts., slight charred	8.0 10.0	R-2	1.1 1.5	NA	P	10.0 - 11.5 Pushed S.S.
CL	~13.0' hard	12.0	R-3	0.5 1.5	P		~12.0' drilling action gets hard but still smooth.
SW	~13.0' - 22.0 GLEYED SILTY SAND: Lt. olive gray to brownish, ~30% fines, slightly plastic; ~50% sand, fine-to coarse-grained, mod. grading, angular to sub-angular; hard; dry to damp.	14.0			HA	P	~14.0' cuttings get slightly granular 15.0 - 16.5 Pushed S.S.
CL	~15.5 - 16.1 silty clay (stiff?)	16.0	R-4	1.1 1.5	P		
	~19.0 - 20.0 CLAYET loam (by core 100%)	18.0 20.0			UJ		~18.5' drilling gets super hard, bound augers tight and almost broke the gears. ~19.5' - 20.0' Pushed S.S.



JASCO CHEMICAL CORPORATION

## **EXPLORATION BORING LOG**

BORING NO.

PROJECT NO.	SHEET NO.
5-60104 H	1 OF 2

BORING LOCATION							GROUND EL.
DEPTH/ELEV. WATER		DRILL CONTRACTOR					TOTAL DEPTH
DRILL RIG		BORING DIA.	DATE DRILLED			LOGGED BY	
SOIL CLASS.	DESCRIPTION	DEPTH	SAMPLE NO.	PR / RQD	REC.	MODE	REMARKS
SW- CL	13.0-22.0 <u>GRAVELLY SILTY SAND:</u> (cont.)	20.0			1.0 1.5	P	20.0-21.5 Pushed S.S. 4:30 2-26-68 21.5' 10:15 2-29-68
CL- SC	22.0-28.0 <u>CLAYEY SAND-</u> <u>SANDY CL-Y:</u> Mod. yel. Lrn. ; ~40-60% fines; med.-plastic; ~40-60% sand; fine-to coarse- grained; med. grading; rounded to angular; abundant small holes; wht ppn.; Fe staining; shell frags; char. soil; soft to firm, wet. - occasional rounded fine gravel, lenses of coarser & finer material	22.0 24.0 26.0	R-5 R-6		H.A.		- 22.0' Drilling action gets very easy. 24.0-21.5 after well completed. - \$20' ~240' after sampling at 25'. - 25.0-26.5 Pushed S.S.
CH	-35.0-38.0 <u>C-SU:</u> Bluish gray with Fe mottling; >90% fines, high plastic; <10% sand, fine-grained (angular grains); slight whitening; slight root hairs; slaty; damp.	28.0 30.0 32.0 34.0 36.0 38.0			H.A.		- 32.0' Drilled gets harder but smooth.
	32.0-38.0 color slightly bluish, slight increase in sand. Bottom hole 38.0		R-7 R-8	1.5 1.5	P		30.0-31.5 Pushed S.S.
				1.3 1.5	P		31.5-33.0 Pushed S.S.
							Terminated boring at 33.0'. Began well installation
							<u>WELL CONSTRUCTION</u>
							0.0-23.0' 50' dia (20") SC-40 PVC
							23.0-28.0 Slotted (0.020 Factory slots)
							<u>SAND F. SEAL</u>
							20.0-20.0 Grout
							20.0-22.0 Bentonite
							22.0-28.0 14.00" B
							28.0-33.0 Bentonite
<b>Wahler Associates</b>		<b>JACCO CHEMICAL CORPORATION</b>			<b>EXPLORATION BORING LOG</b>		<b>BORING NO.</b>
					<b>PROJECT NO.</b>	<b>SHEET NO.</b>	
					JCO 104 H	2 OF 2	V-9

BORING LOCATION JASCO, East side of main buildings DEPTH/ELEV. WATER - 245' (surface) DRILL CONTRACTOR HEW DRILLING DRILL RIG CME 55 BORING DIA. 3.0" DATE DRILLED 4 MAR. 38							GROUND EL. TOTAL DEPTH 38.0 LOGGED BY G.F. 2.
SOIL CLASS.	DESCRIPTION	DEPTH	SAMPLE NO.	PR / RQD	REC.	MODE	REMARKS
	0.0-0.4' ASPHALT	0.0					Advancing hole with 3.0" hollow-stem augers.
A.L.	0.4-1.2' SILTY SANDY GRAVEL: sub-base material; greenish-gray ALLUVIUM	2.0		5	1.2	DR	Sampling with a 2.5" ID split spoon (S.S.) sampler driven by ~ 140 lb rope line hammer, free-falling 30 in per blow.
CH	1.2-4.8' CLAY: Black; >10% fines, high plastic, high toughness; <10% sand, fine-grained; slight w/H Pct; slight rootlets; very stiff to hard; damp.	4.0	R-1 20	1.5		HA	Driller - Jeff Helper - John
	~4.8-11.3' CLAY: Greenish brown with Fe mottling; >90% fines, med.-to higher plastic, med. toughness; <10% sand, fine-to med.-grained; slight w/H Pct; very stiff to stiff; damp to slightly moist.	6.0	R-2 22	1.5		HA	Began at 1:00 Drilling 1:45 2.0-3.5 Drove S.S. 3.0-3.5 OVA = 12
CH	- slightly crumbly ~ 8.0' color to mostly brn, gray clay stringers, some cementing, slight increase in sand %. ~ 10.5' grading: sandy and gravelly.	8.0	R-3 22	1.5		HA	4.0-5.5 Drove S.S. 5.0-5.5 OVA = 14 Regional Board observes outside: (Liz Cameron)
		10.0		5	1.0	DR	7.0-8.5
				12	1.5	DR	3.0-8.5 OVA = 10
				24	1.5	DR	10.0-11.5 Drove S.S. 11.0-11.5 OVA = 12
G.G.	11.2-13.5' CLAYSY SANDY GRAVEL: Mod. yel. brn.; ~20-40% fines; ~20-50% sand, fine-to coarse-grained, sub-angular to rounded, well graded; ~40-60% gravel, fine, sub to rounded; Fe staining; dense to very dense; damp to slightly moist.	12.0				HA	~12.5' Drilling action gets hard and jumpy.
	13.0-16.5' clean sand, med-to fine-grained	14.0	R-5 30	1.0		DR	13.0-14.0 Drove S.S. 13.5-14.0 OVA = 8
		16.0	R-6 12			HA	15.0-16.5 Drove S.S.
				15	1.2	DR	15.0-16.5 OVA = 3
				15	1.5	DR	
				24			
	~18.5-22.5' SANDY CLAY/CLAYSY SAND: Mod. yel. brn.; ~40-60% fines, med. plastic; ~40-60% sand, fine-to coarse-grained	18.0				HA	~18.5' Drilling action gets easy
SC- CL		20.0					20.0-21.5 Drove S.S.

BORING LOCATION							GROUND EL.
DEPTH/ELEV. WATER			DRILL CONTRACTOR				TOTAL DEPTH
DRILL RIG		BORING DIA.	DATE DRILLED			LOGGED BY	
SOIL CLASS.	DESCRIPTION	DEPTH	SAMPLE NO.	PR RQD	REC.	MODE	REMARKS
SC-CL	<p>18.5 - 32.5 <u>SANDY CLAY / CLAYEY SAND</u></p> <p>(cont.) subangular to subrounded; mot-grinding; slight fine gravel; Fe mottling; <math>\approx</math> 1.47 to medium dense; damp to moist.</p> <p><math>\sim</math> 25.0 - 26.5 more sandy heavy to staining, very moist.</p> <p>DATA ON THIS LOG ARE AN APPROXIMATION OF THE GEOLOGIC AND SUBSURFACE CONDITIONS. BECAUSE THE INFORMATION WAS OBTAINED FROM INDIRECT, DISCONTINUOUS, AND POSSIBLY DISTURBED SAMPLING NECESSITATED BY USE OF SMALL-DIAMETER HOLES. ROTARY AND WASH BORING HOLES HAVE FURTHER COMPLICATIONS IN THIS REGARD BECAUSE OF THE NEED TO USE DRILLING FLUID AND/OR CASING IN ADVANCING HOLES.</p> <p>THIS LOG INDICATES CONDITIONS IN THIS HOLE ONLY ON THE DATE INDICATED AND MAY NOT REPRESENT CONDITIONS AT OTHER LOCATIONS AND ON OTHER DATES. ANY WATER LEVELS SHOWN ARE SUBJECT TO VARIATION.</p> <p>THIS HOLE WAS LOGGED IN SUCH A WAY AS TO PROVIDE DATA PRIMARILY FOR DESIGN PURPOSES AND NOT NECESSARILY FOR THE PURPOSES OF SPECIFIC CONTRACTORS.</p> <p>15.5' wat (saturated)</p> <p>THE STRATIFICATION LINES OR DEPTH INTERVALS REPRESENT THE APPROXIMATE BOUNDARIES BETWEEN MATERIAL TYPES, AND THE TRANSITIONS MAY BE GRADUAL.</p> <p>SOIL CLASSIFICATIONS SHOWN ON LOGS ARE FIELD CLASSIFICATIONS BASED ON THE UNIFIED SOILS CLASSIFICATION SYSTEM.</p> <p>18.5 - 32.5 <u>CLAY</u>: Red brn.; &gt;90% silt, high plastic, high liquidity; &lt;10% sand, fine-grained to staining; <math>\approx</math> 1.47 to very stiff; damp.</p> <p>32.5 - 36.0' sand with slight gravel.</p> <p>Bottom hole 36.0'</p>	20.0 22.0 24.0 26.0 28.0 30.0 32.0 34.0 36.0 38.0 40.0	R-7 R-8 R-9 R-10 R-11	4 4 7 10 14	1.3 1.5	DR	<p>20.0 - 21.5 Drove S.S. 21.0 - 21.5 OVA = 3</p> <p><u>SAND &amp; SEAL</u> 0.0 - 22.0 Grout 22.0 - 24.0 Bentonite 24.0 - 32.0 SAND (<math>\pm</math> 3) 32.0 - 38.0 Bentonite</p> <p><math>\Sigma</math> H<sub>2</sub>O @ ~24.5' after well completed. 25.0 - 26.5 Drove S.S. 26.5 OVA = 2</p> <p>H<sub>2</sub>O to 27.5' after sampling at 30'.</p> <p>30.0 - 31.5 Drove S.S. 31.0 OVA = 2</p> <p>~32.0' Drilling action gets smooth but hard. Drill bits stick (very good aquifainer).</p> <p>35.0 - 36.5 Drove S.S. 36.5' OVA = 4</p> <p>36.5 - 38.0 Drove S.S. 38.0' OVA = 3 Terminated boring at 38.0' installed well.</p> <p><u>WELL CONSTRUCTION</u> 0.0 - 25.0' solid (0.016) 25.0 - 32.0 slotted (0.020) <u>SAND &amp; SEAL</u> - see above</p>

 Wahler  
Associates

TACO CHEMICAL CORPORATION

EXPLORATION BORING LOG

BORING NO.

PROJECT NO.  
JCD 104 H

SHEET NO.  
2 OF 2

V-10

JOB NO.	7403
---------	------

BORE HOLE NO.	V-11
---------------	------

PROJECT	Jasco Chemical Corp		LOCATION	Mountain View, CA	
DRILLING CONTRACTOR	ASE Drilling		DRILLING EQUIPMENT	Mobile B-61 Hollow Stem	
HYDROGEOLOGIST	Scott Rice		DRILLER	Chris	
DATE START/TIME	6/20/90 0900	DATE FINISH/TIME	6/20/90 1515	SURFACE ELEVATION	TOTAL DEPTH
WELL CASING	4" Sched 40 PVC	SCREEN TYPE	4" Sched 40 PVC	LENGTH	41.5 feet
				SLOT	0.010-inch

DEPTH	SAMPLE NUMBER	BLOW COUNT PER 6'	RECOVERY	BORE HOLE LOG		
				LITHOLOGIC DESCRIPTION	REMARKS	GRAPHIC LOG
-				cuttings - sandy clay and clayey sand, dark gray, moist, low plasticity	PID (background) 2-4	XX
-				CL/SC - sandy clay and clayey sand, very dark gray (10YR 3/1), 40-60% sand, 40-60% clay, moist, poorly sorted, subangular, particles to 1 mm diameter, firm, low plasticity	PID (sample) - 3	XX
-	V11-2	4/5/11	13"			XX
-						XX
5-	V11-5	3/5/8	14"	CL/SC - as above SM - silty sand, grayish brown (10YR 5/2), 30-40% silt, slightly moist, moderately well sorted, medium sand, particles to 2 mm diameter, friable	PID (sample) - 7 PID (borehole) - 0	XX
-						XX
10-	V11-10	3/5/8	16"	SM/SC - clayey and silty sand, dark brown (10YR 3/3), 30% clay, 20% silt, 50% medium sand, moist, poorly sorted, subrounded, particles to 1 mm diameter, firm but friable, low plasticity	PID (sample) - 4	XX
-						XX
15-	V11-15	7/8/7	18"	ML - fine sandy silt, dark brown (10YR 4/3), moist, low plasticity SW - medium sand, dark brown to black, <10% clay and silt, slightly moist, poorly sorted, loose SM - silt and fine sand, olive brown (2.5Y 4/4), 40-60% silt, 40-60% fine sand, slightly moist, soft, not plastic	PID (sample) - 3 Driller notes softer sediments at 16 feet	XX
-						XX
20-	V11-20	3/5/8	16"	SW - sand and gravel, dark grayish brown (2.5Y 4/2), trace silt, dry, poorly sorted, friable SC - clayey sand, olive brown to black (2.5Y 4/4 to 2.5Y 3/0), 40% clay, slightly moist to moist, poorly sorted, particles to 4 mm diameter, lenses of hard clay, abundant decayed rootlets	PID (sample) - 2 PID (borehole) - 1	XX
-						XX
25-	V11-25	3/6/9	18"	SM - silty sand, olive (5Y 4/3), 40% silt, 10% clay, moist, poorly sorted, medium to coarse sand to 2 mm diameter, low plasticity GM - silty sand and gravel, 20% silty, moist, very poorly sorted, subangular, friable	PID (sample) - 1	XX
-						XX
30-	V11-30	8/24/33	18"	CL - slightly sandy clay, dark olive gray (5Y 3/2), 10-15% fine to medium sand, moist, moderately plastic, firm GM - sand and gravel, 20% gravel, wet to saturated, very poorly sorted, subangular, particles to 10 mm diameter, loose, friable, zones of iron oxidation throughout	PID (sample) - 1 Driller notes difficult drilling at 32 feet then easier drilling at 32.5 feet	XX
-						XX
35-	V11-35	12/9/14	NA	GM - sand and gravel, 20-25% silty and clay, saturated, very poorly sorted	Sample collected for sieve analysis.	XX
-						XX

JOB NO.  
7403BORE HOLE NO.  
V-11PROJECT  
Jasco Chemical Corp

LOCATION

Mountain View, CA

DEPTH	SAMPLE NUMBER	BLOW COUNT PER 6'	RECOVERY	BORE HOLE LOG		
				LITHOLOGIC DESCRIPTION	REMARKS	GRAPHIC LOG
40				cuttings - sand and gravel		
45						
50						
55						
60						
65						
70						
75						

Total Depth - 41.5 feet

PART 1

JOB NO. 7403

PAGE 1 OF 2

BORE HOLE NO. V-12

PROJECT	Jasco Chemical Corp		LOCATION	Mountain View, CA	
DRILLING CONTRACTOR	ASE Drilling		DRILLING EQUIPMENT	Mobile B-61 Hollow Stem	
HYDROGEOLOGIST	Scott Rice		DRILLER	Chris	
DATE START/TIME	6/20/90 1555	DATE FINISH/TIME	6/21/90 1545	SURFACE ELEVATION	TOTAL DEPTH 42 feet
WELL CASING	4" Sched 40 PVC	SCREEN TYPE	4" Sched 40 PVC	LENGTH 10 feet	SLOT 0.010-inch

DEPTH	SAMPLE NUMBER	BLOW COUNT PER 6'	RECOVERY	BORE HOLE LOG		
				LITHOLOGIC DESCRIPTION	REMARKS	GRAPHIC LOG
-	-	-	-	cuttings - (ML) sandy silt, dark gray, 30% sand, slightly moist, firm color change from dark gray to light tan	PID (background) - 0	.....
5-	-	-	-	cuttings - (SM) fine sand and silt, tan, 40% silt, <10% clay, well sorted, loose	PID (borehole) - 0	.....
10-	-	-	-	cuttings - (CL) sandy clay, dark gray, 25% medium sand, slightly moist, firm but friable, low plasticity	Driller notes difficult drilling 10 to 12 feet	.....
15-	-	-	-	cuttings - (CL) sandy clay, light gray, 25% medium sand, slightly moist, firm but friable, low plasticity	PID (sample) - 1	.....
15-	V12-15	16/19/23	18"	cuttings - (GW) sand and gravel, < 20% clay and silt, poorly sorted, rounded SM - sandy silt and silty sand, dark brown (10YR 3/3), trace clay, slightly moist, hard SW - sand and gravel, dark grayish brown (10YR 4/2), <10% clay and silt, slightly moist, very poorly sorted, subangular, particles to 10 mm diameter, loose	PID (background) - 1	.....
20-	V12-20	NA	18"	SM - sandy silt and silty sand, dark brown (10YR 3/3), 20% clay, firm, moderate plasticity	PID (sample) - 1	.....
25-	V12-25	3/5/8	18"	ML - sandy clay, dark grayish brown (2.5Y 4/2), moist, stiff, moderately plastic, sand replaces decaying rootlets, abundant iron oxidization	PID (sample) - 1	XX XX
30-	V12-30	10/5/6	18"	SW - coarse sand, olive brown (2.5Y 4/4), trace silt, wet, very poorly sorted, subangular loose, grades finer to 20.75 feet CL - clay, dark gray (2.5Y 4/0), trace sand in decayed rootlet zones, moist, stiff	PID (sample) - 1	.....
35-	V11-35	12/9/14	NA		First Water - 32 feet	.....
					Sample collected for sieve analysis.	.....

PART 2

JOB NO.  
7403

PAGE 2 OF 9

BORE HOLE NO.  
V-12PROJECT  
Jasco Chemical Corp

LOCATION

Mountain View, CA

DEPTH	SAMPLE NUMBER	BLOW COUNT PER 6'	RECOVERY	BORE HOLE LOG		GRAPHIC LOG
				LITHOLOGIC DESCRIPTION	REMARKS	
40				cuttings - sand and gravel		
45						
50						
55						
60						
65						
70						
75						

Total Depth - 41.5 feet

BORING LOCATION JASCO CHEMICAL CORPORATION							GROUND EL.
DEPTH/ELEV. WATER 25.0 (A) 26.8 (B.)			DRILL CONTRACTOR HEN DRILLING				TOTAL DEPTH 62.5
DRILL RIG CME-75		BORING DIA. 8 "		DATE DRILLED 4/27 - 5/1/87			LOGGED BY RLB
SOIL CLASS.	DESCRIPTION	DEPTH	SAMPLE NO.	PR ROD	REC.	MODE	REMARKS
	FILL 0.0-2.0- SANDY GRAVEL: light brown; 60% Gravel, cl. 15, up to 1.5" diameter, 40% sand, dry, loose	0			0.6 2.5	CC	
GC	2.0-11.5: LEAN CLAY: dark brown 98% fines, < 2% Medium to Coarse sand, moderate plasticity, damp.	2	CC-1				
		4	CC-2		2.5 2.5	CC	
CL	6.5- Color change to greenish-black, increase in non-plastic fines	6	CC-3		2.5 2.5	CC	
		8	CC-4		2.5 2.5	CC	
	8.5- further increase in non-plastic fines	10					
	11.5- Color change to mottled greenish black/light brown.	12	CC-5		2.5 2.5	CC	
		14	CC-6		2.0 2.5	CC	
GP	14.5-17.0- SANDY GRAVEL: Granish black; alternating Sandy Gravel / Gravel / sand layers. 10-80% Gravel, 20-90% medium sand, moist, loose to very loose.	16	CC-7		2.5 2.5	CC	
CL	17.0-17.5- SANDY CLAY: medium brown	18	CC-8		2.0 2.5	CC	
GP	17.5-17.8- Sandy Gravel: Mottled medium brown/Greenish black						
CL	19.3-20.8: Sandy Clay: Medium brown	20					

BORING LOCATION							GROUND EL.
DEPTH/ELEV. WATER		DRILL CONTRACTOR				TOTAL DEPTH	
DRILL RIG		BORING DIA.		DATE DRILLED			LOGGED BY
SOIL CLASS.	DESCRIPTION	DEPTH	SAMPLE NO.	PR ROD	REC.	MODE	REMARKS
CL	19.8-20.8: Sandy Clay (cont.)	20			2.5		
GP	20.8-24.8 - Sandy Gravel; Mottled greenish black/medium brown.		CC-9		2.5	CC	
CL	21.8-22.5: Lean Clay; Mottled greenish black/medium brown	22					
	22.5-32.5 Sandy Clay; greenish brown; sand content decreased with increasing depth	24			2.5	CC	
	25.0 - Color change to greenish-black	26			2.5	CC	
CL	27.5 - Strong sewer odor	28			2.5	CC	
	30.0 - <2% Concrete	30					
	32.5-33.0: SANDY GRAVEL: greenish black, 40% gravel, 40% sand, 20% clay, strong sewer odor	32			2.5	CC	32.0 - Cutoff encountered!
GC/SC	33.0-39.8: Gravely Sand: greenish-black; 30-40% medium sand; 10-20% gravel.	34			0.8	CC	
SP	36.0-41.3: CLAY: light brown, 95% fines, 5-10% fine sandy mud, no plasticity	36	CC-15		2.5	DR	
CL	39.3-41.3: CLAY: light brown, 95% fines, 5-10% fine sandy mud, no plasticity	38			1.5	CC	
		40					

W Wahler Associates	JASCO CHEMICAL CORP	EXPLORATION BORING LOG	BORING NO.
		PROJECT NO. ECHO 100414	SHEET NO. 2 of 4

I-1

BORING LOCATION							GROUND EL.
DEPTH/ELEV. WATER			DRILL CONTRACTOR				TOTAL DEPTH
DRILL RIG		BORING DIA.	DATE DRILLED			LOGGED BY	
SOIL CLASS.	DESCRIPTION	DEPTH	SAMPLE NO.	PR / ROD	REC.	MODE	REMARKS
	39.8-46.3 - CLAY (cont.)	40			1.0 1.0	CC	bentonite from 39.8-41.0 at end of day 4-27-87
CL		42	CC-18		0.8 2.5		41.0 END OF BORING 4/27/87, work continued 5/1/87, casings pushed to 48.0 46.0; END OF BORING 5/1/87, work resumed 5/1/87.
		44			1.0 2.5		
		46	CC-19				
SP/GP	46.3- 57.5 = GRAVELY SAND greenish black, 25-75% medium sand, 25-75% gravel, very dense, very moist, possibly partially cemented	47.2	B-1	2.5 2.5	CC		46.3- 47.8: extremely push drilling; core tubes broken; material recovered placed in plastic bags.
	47.2 - Color changes to yellow- brown	47.8	B-2	2.5 2.5	CC		
	47.8 - material not cementsed, saturated	48	CC-20	2.5 2.5	CC		
	50.0: Gravel clastics up to 1" diameter.	50	B21A B21B	2.5 2.5	CC		TUBE broken - sample placed in plastic bag.
		52					
		54	B-22	2.5 2.5	CC		
	56.0 - iron staining in sand matrix surrounding gravel clastis	56	CC-23	1.5 2.5	CC		55.0 - Sand in hollow stem - sampler jammed. cc-22 broken, sample placed in bags. 56.0 - drill is like sand.
C4/SC	57.5-62.5 - SANDY CLAY: yellow- brown; 30-50% clay; 30-50% fine sand; soft, very moist.	58	CC-24	2 2.5	CC	CC-24 - NOT CEMENTED	57.0 - drill is like clay
		60					

W Wahler Associates	JASCO CHEMICALS CORP	EXPLORATION BORING LOG		BORING NO.
		PROJECT NO.	EJECT NO.	I-2
		50010011	3 OF 4	

BORING LOCATION							GROUND EL.
DEPTH/ELEV. WATER			DRILL CONTRACTOR				TOTAL DEPTH
DRILL RIG		BORING DIA.	DATE DRILLED			LOGGED BY	
SOIL CLASS.	DESCRIPTION	DEPTH	SAMPLE NO.	PR / RQD	REC.	MODE	REMARKS
	57.5-62.5 SANDY CLAY (cont.)	60	CC-25	2.5 2.5	CL		water at 26.8'
	62.5' END OF BORING	62					<u>well construction info</u>
		64					O-40'-GROUT 40'-46.3 BENTONITE 46.3-57.5 SAND 48.3-57.5 SCREEN 57.5-62.5 : BENTONITE well installed 5/1/87 GROUT SEAL PLACED 5/12/87
<p>DATA ON THIS LOG ARE AN APPROXIMATION OF THE GEOLOGIC AND SUBSURFACE CONDITIONS BECAUSE THE INFORMATION WAS OBTAINED FROM INDIRECT, DISCONTINUOUS, AND POSSIBLY DISTURBED SAMPLING NECESSITATED BY USE OF SMALL-DIAMETER HOLES. ROTARY AND WASH DRILLING HOLES HAVE FURTHER COMPLICATIONS IN THIS REGARD BECAUSE OF THE NEED TO USE DRILLING FLUID AND/OR CASTING IN ADVANCING HOLES.</p> <p>THIS LOG INDICATES CONDITIONS IN THIS BOREHOLE ON THE DATE INDICATED AND MAY NOT REPRESENT CONDITIONS AT OTHER LOCATIONS AND ON OTHER DATES. ANY WATER LEVELS SHOWN ARE SUBJECT TO VARIATION.</p> <p>THIS HOLE WAS LOGGED IN SUCH A WAY AS TO PROVIDE DATA PRIMARILY FOR DESIGN PURPOSES AND NOT NECESSARILY FOR THE PURPOSES OF SPECIFIC CONTRACTORS.</p> <p>THE STRATIFICATION LINES OR DEPTH INTERVALS REPRESENT APPROXIMATE BOUNDARIES BETWEEN MATERIAL TYPES, AND THE TRANSITIONS MAY BE GRADUAL.</p> <p>SOIL CLASSIFICATIONS SHOWN OR LOGGED ARE FAIR CLASSIFICATIONS BASED ON THE UNIFIED SOILS CLASSIFICATION SYSTEM.</p>							
W Wahler Associates	JASCO CHEMICAL CORP	EXPLORATION BORING LOG				BORING NO. I-1	
		PROJECT NO. JASCO-104R	SHEET NO. 4 OF 4				

BORING LOCATION JASCO CHEMICAL CORP. (In median of Central Exp.

GROUND EL.

DEPTH/ELEV. WATER 23.2' (8-11-87) DRILL CONTRACTOR H.E.W. Drilling

TOTAL DEPTH 48.0

DRILL RIG CME 75 BORING DIA. 3.0" DATE DRILLED 11 AUG 87

LOGGED BY G.F. L.

SOIL CLASS.	DESCRIPTION	DEPTH	SAMPLE NO.	PR REQD	REC.	MODE	REMARKS
CL	0.0 - 1.0' SANDY CLAY: Top soil, blackish brown (5YR 2/1); some gravel; slight organics.	0.0				HA	Casto - Driller 9:20
SP- SM	1.0 - 3.4' GRAVELLY SAND: dk. yel. brn. (10 YR 4/2); ~10% fines, nonplastic; ~60% sand, fine-to coarse-grained, mod. grading, angular; ~30% fine gravel, angular, med. dense to dense; damp. (probable road base)	2.0	T-1		1.6 3.0		Anibal - Helper Advancing hole with 8.0" hollow stem augers. Sampling with a 3.0" continuous core sampler, lined with clear plastic tubes (3.0" x 2.5") (samples termed T-1, T-2, etc.).
CL	3.4 - 11.0' SANDY CLAY: olive brn. (5Y 2/1); ~90% fines, mod. to high plastic, no dilatancy, med to high toughness; ~10% sand, fine-grained, rounded; abundant caliche (heavy rxn to HCl); damp.	4.0	T-2		2.5 2.5		0.0 - 3.0 Run #1
		6.0	T-3		2.5 2.5		3.0 - 8.0 Run #2
	~6.0-7.5 slight brn color	8.0					
		10.0	T-4		2.5 2.5		~7.0' slight sugar grinding
CL	11.0 - 20.6' SANDY CLAY: Lt. olive gray (5Y 5/2); ~70-80% fines, med. plastic, slight dilatancy, slight to med toughness; ~20-30% sand, fine-to coarse-grained (mostly fine with rounded coarse), sub angular to rounded; some Fe staining, and coatings; no cement; no odor; damp.	12.0	T-5		2.5 2.5		9:51, 8.0'
		14.0	T-6		2.5 2.5		8.0 - 13.0 Run #3
	15.8 - 17.2' more clayey, less sand.	16.0	T-7		2.5 2.5		
CL	17.8 - 18.7' gravelly clay	18.0	T-8		1.0 1.0		13.0 - 18.0 Run #4
CL		20.0	T-9		2.5 2.5		18.0 - 21.5 Run #5



Wahler  
Associates


JASCO CHEMICAL CORPORATION

EXPLORATION BORING LOG

BORING NO.

PROJECT NO.  
JCD 1044SHEET NO.  
1 OF 3

I - 2



Ena J. Salomon  
CEG #350

BORING LOCATION						GROUND EL.	
DEPTH/ELEV. WATER		DRILL CONTRACTOR				TOTAL DEPTH	
DRILL RIG		BORING DIA.		DATE DRILLED		LOGGED BY	
SOIL CLASS.	DESCRIPTION	DEPTH	SAMPLE NO.	PR RQD	REC.	MODE	REMARKS
CL	11.0 - 20.6 <u>SANDY CLAY</u> : (cont.)	20.0	T-9 (cont)	2.5 2.5	HA		
SP	20.6 - 24.2 <u>GRAVELLY SAND</u> : Dusky yel. brn (10 YR 2/2); ~5% Fines; ~75% sand, fine-to coarse-grained, poorly to mod. grading (lenses of very poorly graded); sub rounded; Fe staining; saturated.	22.0	T-10	1.5 1.5			~21.0 augers grinding 21.5 - 23.0 Run #6
CL	24.2 - 25.5 clay lens	24.0	T-11	2.5 2.5			22.5 ground water while drilling 23.0 - 28.0 Run #7
CL	25.5 - 29.5 <u>SILTY SAND</u> : Dusky yel. brn (10 YR 2/2); ~30% Fines, non plastic; ~70% sand, fine-grained, poorly graded; (occasional rounded gravel); no odor; saturated. - Some thin (~0.1-0.05) lenses of clay.	26.0	No sample	2.0 2.5			25.5 Sample blasted off at 25.5 and assumed sandy to 25.5-28.0' but not recovered.
SM	29.5 - 35.3 <u>SILTY SAND</u> / <u>GRAVELLY SILTY SAND</u> : Dusty, yel. brn (10 YR 2/2); ~20% Fines, non plastic; ~60-80% sand, fine-to coarse-grained, med. grading, sub rounded, sub angular; ~0-20% gravel; abundant Fe staining and coating; wet, . (Gravel is confined to lenses)	30.0	T-12	2.5 2.5			25.5 - Drilling very soft
SM	35.3 - 42.5 <u>SANDY CLAY</u> : Dr. greenish gray (5 G + 1); ~60-80% Fines, med. plastic (some zones of high plastic), slow dilatancy, med. toughness; ~20-40% sand, fine-to medium-grained (some angular coarse frags); no cement; low perviousness; wet.	32.0	T-13	2.5 2.5			33.0' 11:27
CL	35.7 - 37.2 zone of gradation from above material	34.0	T-14	2.5 2.5			33.0-38.0 Run #9
CL	38.0 - 43.0 <u>SANDY CLAY</u> : Dr. greenish gray (5 G + 1); ~60-80% Fines, med. plastic (some zones of high plastic), slow dilatancy, med. toughness; ~20-40% sand, fine-to medium-grained (some angular coarse frags); no cement; low perviousness; wet.	36.0	T-15	2.5 2.5			11:51
		38.0	T-16	2.5 2.5			38.0'
		40.0					38.0-43.0 Run #10

 Wahler  
Associates

JACCO CHEMICAL CORPORATION

EXPLORATION BORING LOG

BORING NO.

PROJECT NO.  
JACCO 1044

SHEET NO.  
2 OF 3

I-2

BORING LOCATION							GROUND EL.			
DEPTH/ELEV. WATER			DRILL CONTRACTOR				TOTAL DEPTH			
DRILL RIG		BORING DIA.	DATE DRILLED			LOGGED BY				
SOIL CLASS.	DESCRIPTION		DEPTH	SAMPLE NO.	PR RQD	REC.	MODE	REMARKS		
CL	35.3 - 42.5' <u>SANDY CLAY:</u> (cont.) 38.0 - 39.5' more sandy 38.0 - 38.5' sand lens. 40.9 - 42.5' ~95% clay		40.0	T-16 (cont.)	2.5 2.5	HA				
CL	42.5 - 47.0' <u>SANDY CLAY:</u> DK.yel.brown (IOYR 4/2); ~80-90% Fines, med to high plastic, slow dilatancy to none, med. to higher toughness; ~10-20% fine-to medium-grained sand (occasional coarse), poorly graded, rounded; Fe coatings + staining; no odor; slight rxn to HCl; low to non pervious; stiff; wet.		42.0	T-17	2.5 2.5			11:55		
CH	44.0 - 46.0' cutting coming up clean (no stop)		44.0	T-18	2.5 2.5			43.0 - 48.0' Run #11 1:00		
CL	46.0 - 48.0' water coming up with cuttings. (stop)		46.0	T-19	2.5 2.5					
SC SP	43.0 - 43.3' possible sluff. 43.3 - 44.4' clay, very slight sand 44.7 - 47.0 sandy clay with slight gravel		43.0					48.0' Terminated drilling.		
47.0 - 48.0' <u>CLAYEY SAND:</u> DK.yel.brown with red staining; as above with ~60% sand and 40% fines; 47.7 - 48.0 sand with no fines.								following termination; Tremie grout to bottom, filled hole with grout to surface.		
Bottom Hole 48.0'										
<small>DATA ON THIS LOG ARE AN APPROXIMATION OF THE GEOLOGIC AND SURFACE CONDITIONS BECAUSE THE INFORMATION WAS OBTAINED FROM INDIRECT, DISCONTINUOUS, AND POSSIBLY DISTURBED SAMPLING NECESSITATED BY USE OF SMALL-DIAMETER HOLES. ROTARY AND WASH DRILLING HOLES HAVE FURTHER COMPLICATIONS IN THIS REGARD BECAUSE OF THE NEED TO USE DRILLING FLUID AND/OR CASING IN ADVANCING HOLES.</small>										
<small>THIS LOG INDICATES CONDITIONS IN THIS HOLE ONLY ON THE DATE INDICATED AND MAY NOT REPRESENT CONDITIONS AT OTHER LOCATIONS AND ON OTHER DATES. ANY WATER LEVELS SHOWN ARE SUBJECT TO VARIATION.</small>										
<small>THIS HOLE WAS LOGGED IN SUCH A WAY AS TO PROVIDE DATA PRIMARILY FOR DESIGN PURPOSES AND NOT NECESSARILY FOR THE PURPOSES OF SPECIFIC CONTRACTORS.</small>										
<small>THE STRATIFICATION LINES OR DEPTH INTERVALS REPRESENT THE APPROXIMATE BOUNDARIES BETWEEN MATERIAL TYPES, AND THE TRANSITIONS MAY BE GRADUAL.</small>										
<small>SOIL CLASSIFICATIONS SHOWN ON LOGS ARE FIELD CLASSIFICATIONS BASED ON THE UNIFIED SOILS CLASSIFICATION SYSTEM.</small>										
 Wahler Associates		JASCO CHEMICAL CORPORATION			EXPLORATION BORING LOG		BORING NO.			
		PROJECT NO.		SHEET NO.		I-2				
		TCO104H		3 OF 3						

BORING LOCATION JASCO CHEMICAL CORP. / In Central Expressway Median							GROUND EL.
DEPTH / <del>FEET</del> WATER 23.6' / 0.95 Stick-up DRILL CONTRACTOR WEEKS DRILLING							TOTAL DEPTH 59.5
DRILL RIG FAILING 1500		BORING DIA. ~ 14.0"	DATE DRILLED 14 AUG. '87		LOGGED BY P.F.L		
SOIL CLASS.	DESCRIPTION	DEPTH	SAMPLE NO.	PR RQD	REC.	MODE	REMARKS
	0.0 - ~ 2.5' GRAVELLY CLAY	0.0			RD		Arrived on site 7:00 set-up rig & equip. Begin Drilling 9:30 Doug - Driller Richard - Helper Jim - Helper Drilling with mud rotary, 13 1/2" tri-cone bit.
C1	- 2.5 - 11.0 grayish	2.0	B-3				Boring is 7.0" at 1700 from Well V-7.
		4.0					
		6.0					
		8.0					8.0' 10:00 AM
		10.0					
		12.0	B-2				
C1	~ 11.0 - 20.0 SANDY CLAY	14.0					13.0' 10:17
		16.0	B-3				
		18.0					
		20.0	B-4				
<i>Emmett Tolson CEG #350</i>							

 Wahler  
Associates

JASCO CHEMICAL CORPORATION

EXPLORATION BORING LOG

BORING NO.

PROJECT NO.  
ECO 1044

SHEET NO.  
1 OF 3

I-2A

BORING LOCATION				GROUND EL.			
DEPTH/ELEV. WATER		DRILL CONTRACTOR			TOTAL DEPTH		
DRILL RIG		BORING DIA.		DATE DRILLED			LOGGED BY
SOIL CLASS.	DESCRIPTION	DEPTH	SAMPLE NO.	PR RQD	REC.	MODE	REMARKS
	20.0 - 24.0 SAND	20.0				RD	
SP		22.0					
		24.0	B-5				24.0 11:00
		26.0	B-6				
SC	27.0 - 47.0 - CLAYEY SAND	28.0					
		30.0	B-7				
		32.0					Drilled to 40.0'
		34.0	B-8				Installed 8.0"
		36.0					steel casing to
		38.0	B-9				40.0' and pushed
		40.0	B-10				to 42.0'.
							Installed grout pipe
							to 38' and pumped
							hole full of grout.
							(used 18 bags
							cement & ~200gals
							H <sub>2</sub> O) 2:00P-
							Note: Arrived Monday
							(17 Aug.) and casing
							was still full of H <sub>2</sub> O,
							meaning that the seal
							was good.
							12:10

 Wahler  
Associates

JASCO CHEMICAL CORPORATION

EXPLORATION BORING LOG

BORING NO.

PROJECT NO.

SHEET NO.

JCO\_104H

2 OF 3

I-2A

BORING LOCATION							GROUND EL.
DEPTH/ELEV. WATER			DRILL CONTRACTOR				TOTAL DEPTH
DRILL RIG		BORING DIA.	DATE DRILLED			LOGGED BY	
SOIL CLASS.	DESCRIPTION	DEPTH	SAMPLE NO.	PR RQD	REC.	MODE	REMARKS
	24.0 - 47.0 - Clayey Sand (Cont.)	40.0				RD	Arrived on site ~10:34AM (17 Aug '87) Start drilling 12:25pm
SC	DATA ON THIS LOG ARE AN APPROXIMATION OF THE GEOLOGIC AND SURFACE CONDITIONS BECAUSE THE INFORMATION WAS OBTAINED FROM INDIRECT, DISCONTINUOUS, AND POSSIBLY DISTURBED SAMPLING NECESSITATED BY USE OF SMALL-DIAMETER HOLE. ROTARY AND WASH DRILLING HOLES HAVE FURTHER COMPLICATIONS IN THIS REGARD BECAUSE OF THE NEED TO USE DRILLING FLUID AND/OR CASING IN ADVANCING HOLES.	42.0	R-1 6				Now drilling with 7½ tri-cone bit. Sampling with 3.0" split spoon sampler line with 2.5" x 6.0" brass tubes (samples termed R-1, R-2, etc.).
	THIS LOG INDICATES CONDITIONS IN THIS HOLE ONLY ON THE DATE INDICATED AND MAY NOT REPRESENT CONDITIONS AT OTHER LOCATIONS AND ON OTHER DATES. ANY WATER LEVELS SHOWN ARE SUBJECT TO VARIATION.	42.0	R-2 10	1.5 20	DR		
	THIS HOLE WAS LOGGED IN SUCH A WAY AS TO PROVIDE DATA PREDIMINARILY FOR DESIGN PURPOSES AND NOT NECESSARILY FOR THE PURPOSES OF SPECIFIC CONTRACTORS.	44.0	R-3 19				
	THE STRATIFICATION LINES OR DEPTH INTERVALS REPRESENT THE APPROXIMATE BOUNDARIES BETWEEN MATERIAL TYPES, AND THE TRANSITIONS MAY BE GRADUAL.	44.0	R-4 33				
	SOIL CLASSIFICATIONS SHOWN ON LOGS ARE FIELD CLASSIFICATIONS BASED ON THE UNIFIED SOILS CLASSIFICATION SYSTEM.	46.0	R-5 8				
	47.0 - 54.5 SILTY GRAVELLY SAND	46.0	R-6 10	1.8	DR		42.0 - 44.0 Drove sampler not saved
SM	05. yel. brn. (10 YR 4/2); ~10% fines, non-plastic; ~60% sand, fine-to coarse-grained, nod to well graded, subrounded to subangular; ~30% gravel, fine-grained, angular; heavy Fe. coatings and staining; no odor; med. to high perviousness; dense to very dense; saturated.	48.0	R-7 9	2.0			* R-1 - no recovery (lost)
SW	48.0	R-8 12					44.0 - 46.0 Driller screwed up - should not have sampled
		48.0	B-1 -			RD	47.0 - 48.5 Drove sampler
		48.0	B-2 -				Note: Gravel will drilling from 46.5 - 47.0.
		48.0	R-9 24	1.1			48.5' sampler refusal
		48.0	R-10 39	1.5	DR		* note: R-9 not saved
		48.0	R-11 80				
		50.0				RD	
		52.0	B-3				
		54.0					
CL	54.5 - 59.5 SANDY CLAY:	56.0	R-12 20				2.0" ID PVC
CH	Med. blue gray (5 B 5/1); ~90% fines, highly plastic, high toughness; ~10% sand, fine-to med.-grained (mostly fine); heavy mix to HCl; non-pervious; slight organics (root like brown spots); no odor; hard; damp.	56.0	R-13 34	2.0			0.0 - 49.0 solid
	56.0	R-14 44	2.0	DR			49.0 - 54.5 slotted (6.0")
		56.0	R-15 40				Install locking well seal
		58.0					Cover
		58.0	B-4			RD	0.0 - 45.0 grout
		58.0					45.0 - 47.0 Bentonite
		58.0					47.0 - 54.5 Sand (#3)
		58.0					54.5 - 59.5 Bentonite
		58.0					
		58.0					55.0 - 57.0 Drove sampler
		58.0					+ grout seal pumped 18 Aug 8:30AM
							Terminated boring at 59.5'
							2:15 Water truck left 59.5'
							4:15 Water truck return

 Wahler  
Associates

JASCO CHEMICAL CORPORATION

EXPLORATION BORING LOG

BORING NO.

PROJECT NO.

SHEET NO.

JCO 104H

3 OF 3

I-2A

BORING LOCATION JASCO CHEMICAL CORP., CENTRAL EXP. MEDIAN							GROUND EL.
DEPTH/ELEV. WATER 24.0' (standing) DRILL CONTRACTOR HEW Drilling							TOTAL DEPTH 33.5
DRILL RIG CME 75	BORING DIA. 3.0"	DATE DRILLED 12 Aug 84		LOGGED BY P.F.Q.			
SOIL CLASS.	DESCRIPTION	DEPTH	SAMPLE NO.	PR RQD	REC.	MODE	REMARKS
CL	0.0 - 1.0' <u>SANDY CLAY:</u> Brownish black; Topsoil; mod. organics; worms; wood; etc.	0.0	T-1	0.5 1.0	HA		Casto - Driller 2:30 Sal - Helper
CLL	1.0 - 5.3' <u>SANDY CLAY:</u> Brownish black (5 YR 2/1); ~85% fines, high plastic, no dilatancy, high toughness; ~15% sand, fine-to coarse-grained, poorly graded (mostly fine), rounded to subangular; abundant carbonate ppt.; slight roots; non-porous; damp.	2.0	T-2	2.5 2.5			Boring is advanced using 3.0" hollow stem augers. Sampling is done by a CME Continuous Core Sampler with 3.0"x2.5" clear plastic liners.(T)
CH	4.2 - 4.6 zone of heavy whit. ppt. 4.6 - 5.3 gradation zone 5.3 - 12.1' <u>CLAY:</u> Mod. to dark yell. brn. (10 YR 5/4 & 1/2); >95% fines, high plastic, high toughness; <5% sand, fine-grained; mod. rxn. to HCL; Fe staining (nodding); no odor; damp. (sporadic whit. ppt. throughout)	6.0	T-3	2.3 2.5			0.0 - 3.5 Run # 1 3.5 - 8.5 Run # 2
CL	12.1 - 16.3' <u>GRAVELLY SANDY CLAY:</u> Lt. olive gray (5Y=1/2); ~70% fines, mod. plastic, slight dilatancy, med. toughness; ~15% sand, fine-to coarse-grained, mod. grading, sub-round to angular; g+3 frags; heavy rxn to HCL; no odor; damp.	8.0	T-4	2.5 2.5			9:04 8.5'
CL	16.3 - 18.7' <u>GRAVELLY SAND:</u> dk. yell. brn. (10 YR 4/2); <5% fines; ~65% sand, fine-to medium-grained, well graded, sub-rounded, sub-angular; Fe staining; saturated (but drained).	12.0	T-6	2.5 2.5			13.5 13.5 - 18.5 Run # 4
SW	18.7 - 24.1' <u>SILTY SAND:</u>	14.0	T-7	0.8 —			~15.0' augers chattering.
SM		16.0	T-8	2.5 2.5			
		18.0	T-9	2.1 2.5			18.5 18.5 - 23.5 Run # 5
		20.0					No dripping water on sampler.

 Wahler  
Associates

JASCO CHEMICAL CORPORATION

EXPLORATION BORING LOG

BORING NO.

PROJECT NO.  
JCO 104H

SHEET NO.  
1 OF 2

I-3

BORING LOCATION				GROUND EL.			
DEPTH/ELEV. WATER		DRILL CONTRACTOR			TOTAL DEPTH		
DRILL RIG		BORING DIA.		DATE DRILLED		LOGGED BY	
SOIL CLASS.	DESCRIPTION	DEPTH	SAMPLE NO.	PR RQD	REC.	MODE	REMARKS
SM	18.7 - 24.1 <u>SILTY SAND:</u> OK. yel. brn. (10YR 4/2); ~40% fines; slight to med. plastic (grading more or less), quick dilatancy, low toughness; ~60% sand, fine-to coarse-grained (mostly fine, sporadic coarse), sub-angular; Fe staining; mod. peruvius; moist.	20.0	T-9 (cont.)	2.1 2.5			No water coming to surface
		22.0	T-10	2.5 2.5			
		24.0		2.5 2.5			23.5
CL	- occasional gravel frags 23.0 - 24.1 grading less sandy 24.1 - 33.5' <u>SANDY CLAY:</u> OK. greenish gray (5G 4/1); ~85% fines, mod to high plastic, med. to high toughness; ~15% sand, fine-grained, poorly graded; no organics; no odor; moist.	26.0	T-11	2.5 2.5			23.5 - 28.5 Run # 6
		28.0	T-12	2.5 2.5			24.0' H <sub>2</sub> O level when augers removed.
		30.0	T-13	2.5 2.5			28.5
	29.0 - 32.5' less sandy, almost fat clay			2.5 2.5			28.5 - 33.5 Run # 7
	32.0	T-14		2.5			
	Bottom Hole 33.5						11:15 33.5'
		34.0					Terminated boring at 33.5'.
							Pulled augers, hole open to 33.5', installed grout pipe to bottom hole, filled hole with grout. Cuttings and displaced H <sub>2</sub> O removed from site.
<small>DATA ON THIS LOG ARE AN APPROXIMATION OF THE GEOLOGIC AND SUBSURFACE CONDITIONS BECAUSE THE INFORMATION WAS OBTAINED FROM INDIRECT, DISCONTINUOUS, AND POSSIBLY DISTURBED SAMPLING ASSESSTED BY USE OF SMALL-DIAMETER HOLES. ROTARY AND WASH DRILLING HOLE HAVE FURTHER COMPLICATIONS IN THIS REGARD BECAUSE OF THE NEED TO USE DRILLING FLUID AND/OR CASING IN ADVANCING HOLES.</small>							
<small>THIS LOG INDICATES CONDITIONS IN THIS HOLE ONLY ON THE DATE INDICATED AND MAY NOT REPRESENT CONDITIONS AT OTHER LOCATIONS AND ON OTHER DATES. ANY WATER LEVELS SHOWN ARE SUBJECT TO VARIATION.</small>							
<small>THIS HOLE WAS LOGGED IN SUCH A WAY AS TO PROVIDE DATA PRIMARILY FOR DESIGN PURPOSES AND NOT NECESSARILY FOR THE PURPOSES OF SPECIFIC CONTRACTORS.</small>							
<small>THE STRATIFICATION LINES OR DEPTH INTERVALS REPRESENT THE APPROXIMATE BOUNDARIES BETWEEN MATERIAL TYPES, AND THE TRANSITIONS MAY BE GRADUAL.</small>							
<small>SOIL CLASSIFICATIONS SHOWN ON LOGS ARE YIELD CLASSIFICATIONS BASED ON THE UNIFIED SOILS CLASSIFICATION SYSTEM.</small>							

**W** Wahler Associates

JACCO CHEMICAL CORPORATION

EXPLORATION BORING LOG

BORING NO.

PROJECT NO.

SHEET NO.

JCO 104H

2 OF 2

I-3

 Wahler  
Associates

JASCO CHEMICAL CORPORATION

## **EXPLORATION BORING LOG**

BORING NO.

PROJECT NO.  
T-601st

SHEET NO.  
1 OF 4

I-3A

BORING LOCATION					GROUND EL.		
DEPTH/ELEV. WATER		DRILL CONTRACTOR			TOTAL DEPTH		
DRILL RIG		BORING DIA.	DATE DRILLED			LOGGED BY	
SOIL CLASS.	DESCRIPTION	DEPTH	SAMPLE NO.	PR / RQD	REC.	MODE	REMARKS
		20.0				RJ	
		22.0					
		24.0					
	<u>SANDY CLAY:</u> As log of boring I-3	24.0					Drilled to 29.0' with 13 1/2 tri-cone, stopped at 29.0' and installed 8 5/8" steel casing. Pushed casing to 31.0' with rig.
		26.0					
		28.0					
		30.0		PUSH	3:18 19 AUG '87 29.0'		Arrived on site 8:00AM Switched to 7.0" tri-cone start drilling 11:03 AM
		32.0	R-1 8 R-2 15 R-3 24 R-4 30	1.6 2.0	DR	11:21	31.0 - 33.0" Drove 3.0" split spoon sampler w/a 140 lb slide hammer free falling 30.0" per blow. Sampler is lined with 2 1/2" x 6.0" brass tubes (termed R-1, R-2, ..., etc).
		34.0	B-3		RD	11:38	
		36.0					
		38.0	B-4				
	~39.0 grading more sandy (rounded)	40.0					

 Wahler  
Associates

JASCO CHEMICAL CORPORATION

EXPLORATION BORING LOG

BORING NO.

PROJECT NO.

SHEET NO.

JCA 104

2 OF 4

I - 3A

BORING LOCATION					GROUND EL.		
DEPTH/ELEV. WATER		DRILL CONTRACTOR			TOTAL DEPTH		
DRILL RIG		BORING DIA.		DATE DRILLED		LOGGED BY	
SOIL CLASS.	DESCRIPTION	DEPTH	SAMPLE NO.	PR / RQD	REC.	MODE	REMARKS
CL	24.1 - 47.5 <u>SANDY CLAY:</u> (cont.)	400 420 44.0 46.0	B-4 (cont)  B-5			RD	<u>WELL CONSTRUCTION</u> 2.0" SCH 40 PVC 0.0-49.0 solid 49.0-55.0 slotted Install locking well cover SEAL 0.0-43.5 grout 12:20 43.5-46.5' bentonite 46.5-55.5 SAND (+3) 55.0-59.5 Bentonite 59.5-71.0 SAND
SW	47.5 - 71.0 <u>GRAVELLY SAND:</u> DK yel. brn. (10 yr 1/2); ~5-10% fines, non plastic; ~60-70% sand, fine- to coarse-grained, mod to well graded, sub rounded; sandstone fragments, Fe coatings; ~20-35% gravel, fine, rounded, Fe coatings; non cemented; soil is highly pervious no odor; very dense; saturated.  54.5 some brn clay in cuttings.	480 50.0 52.0 54.0 56.0	B-6 R-5 B-8 R-9	135 0.4/ 106	DR	RD	12:30 49.0-49.6 Drove 3.0" 00 split-spoon Sampler with 140 lb slide hammer. Refusal.
CL	56.5 - 57.5 <u>Sandy CLAY</u> blueish gray, roots, damp.	58.0	R-6 R-7 2-10	18 45 50	DR	RD	11:25 57.0 - 58.2 Drove split-spoon sampler Refusal @ 58.2'
SW		59.0 60.0	B-11				

 Wahler  
Associates

Jasco CHEMICAL CORPORATION

EXPLORATION BORING LOG

BORING NO.

PROJECT NO.  
JCO-104 H

SHEET NO.  
3 OF 4

I-3A

 Wahler  
Associates

JASCO CHEMICAL CORPORATION

**EXPLORATION BORING LOG**

BORING NO.

PROJECT NO.	SHEET NO.
JCD 104-H	4 OF 4

Crest Solander  
CES # 350 7/2/87

BORING LOCATION JASCO CHEMICAL CORPORATION							GROUND EL.
DEPTH/ELEV. WATER NOT ENCOUNTERED			DRILL CONTRACTOR HEW DRILLING			TOTAL DEPTH 21.5'	
DRILL SITE CME-75			BORING DIA. 6"			LOGGED BY RGR	
SOIL CLASS.	DESCRIPTION	DEPTH	SAMPLE NO.	PR/RQD	REC.	MODE	REMARKS
	ALLUVIUM 0.0-5.0: SANDYCLAY; dark brown 5.0-10.0: clay, 20% sand, dry, moderate plasticity, very stiff.	0				AD	DRILLED WITH 6" AUGER
C+	3.0-4.5 CALCIUM MUDLINE	2	R-1 7 7 10	1.5 1.5	DR		3.2.5-2.5" California modified sampler (CMS) driven by 140# S Hammer falling 30"
		4	R-2 7 15 20	1.5 1.5	DR		3.0-4.5 CMS
SC	5.0-15.0 CLAY & SAND; light brown, 50% silt, 40% sand, 10% clay; dry to slightly damp, low moderate plasticity; very stiff.	6	R-3 7 10 14	1.5 1.5	DR		3.0-6.5 CMS
C+	5.0-15.0 - CLAY; mottled yellow-green/greenish brown; 95-98% clay; 2-5% fine sand; very stiff, moist, high plasticity.	8				AD	
		10	R-4 8 12 17	1.5 1.5	DR		3.0-11.5 CMS
		12					
		14				A'	
SP	5.0-15.0 - GRAVELY SAND; medium brown; 80% medium sand, 20% gravel (subangular) medium size; dried slightly damp.	16	R-5 27 20 7	1.5 1.5	PA		5.0-16.5 CMS
C+	5.0-20.0 - SANDY CLAY; yellow-green, 70% clay, 30% fine sand; moderate plasticity; damp.	18				AD	
		20					

W  
Walter  
Associates

JASCO CHEMICAL CORPORATION

EXPLORATION BORING LOG

BORING NO.

PROJECT #:

SHEET #:

JCO-104A

1 OF 2

B-1

BORING LOCATION							GROUND EL.
DEPTH/ELEV. WATER		DRILL CONTRACTOR					TOTAL DEPTH
DRILL RIG		BORING DIA.	DATE DRILLED			LOGGED BY	
SOIL CLASS.	DESCRIPTION	DEPTH	SAMPLE NO.	PR ROD	REC.	MODE	REMARKS
	ALLUVIUM	20					20.0-21.5 CMS
SC	16.5-20.2 - Sandy clay (cont.) 20.2-21.5 CLAYEY SAND: Light brown; 80% fine sand, 20% clay; Low plasticity; moist; dense.	21.5' TOTAL DEPTH	R-6	7 16 24	1.5 1.5	DR	21.5 Terminate hole - Boring backfilled with cement grout
		22					
		24					
		26					
		28					
		30					
		32					
		34					
		36					
		38					
		40					

DATA ON THIS LOG ARE AN APPROXIMATION OF THE GEOLOGIC AND SUBSURFACE CONDITIONS BECAUSE THE INFORMATION WAS OBTAINED FROM INDIRECT, DISCONTINUOUS, AND POSSIBLY DISTURBED SAMPLES. RECENTLY DRILLED HOLE OF SMALL-DIAMETER, ROTARY AND WASH DRILLING HOLE HAVE FURTHER COMPLICATIONS IN THIS REGARD BECAUSE OF THE NEED TO USE DRILLING FLUID AND/OR Casing IN ADVANCING HOLES.

THIS LOG INDICATES CONDITIONS IN THIS HOLE ONLY ON THE DATE INDICATED AND MAY NOT REPRESENT CONDITIONS AT OTHER LOCATIONS AND ON OTHER DATES. ANY WATER LEVELS SHOWN ARE SUBJECT TO VARIATION.

THIS HOLE WAS LOGGED IN SUCH A WAY AS TO PROVIDE DATA PRIMARILY FOR DESIGN PURPOSES AND NOT NECESSARILY FOR THE PURPOSES OF SPECIFIC CONTRACTORS.

THE STRATIFICATION LINES OR DEPTH INTERVALS REPRESENT THE APPROXIMATE BOUNDARIES BETWEEN MATERIAL TYPES, AND THE TRANSITIONS MAY BE GRADUAL.

SOIL CLASSIFICATIONS SHOWN ON LOG ARE FIELD CLASSIFICATIONS BASED ON THE DRILLED SOILS CLASSIFICATION SYSTEM.

W  
A Wahler  
Associates

JASCO CHEMICAL CORPORATION

EXPLORATION BORING LOG

BORING NO.

PROJECT NO.  
JCS-1044

SHEET NO.  
2 OF 2

B-1

*Enest Galano*  
CEG #350 7/2/87

BORING LOCATION JASCO CHEMICAL CORPORATION							GROUND EL.
DEPTH/ELEV. WATER NOT ENCOUNTERED			DRILL CONTRACTOR HEW DRILLING				TOTAL DEPTH 21.5'
DRILL RIG CME-75		BORING DIA. 6"	DATE DRILLED 6-9-87			LOGGED BY RG&	
SOIL CLASS.	DESCRIPTION	DEPTH	SAMPLE NO.	PR RQD	REC.	MODE	REMARKS
SC	ALLUVIUM 0.0-1.2 - CLAYEY SAND; dark brown 65% Medium Sand, 35% Clay; low to moderate plasticity; earthy odor; 1.2-5.4 - SANDY CLAY; dark brown 90% Clay, <10% fine sand; mod- erate plasticity; tiny fragments, some iron staining; very stiff!	0				AD	Drill with 6" Auger
CL		2	R-1 8 17	1.5 1.5	DR		1.0-2.5 2.5" California Modified Simpler (CMS) driven by 140lb hammer fall/12' 20"
CL		4	R-2 8 16	1.5 1.5	DR		3.0-4.5 CMS
SC- CL	5.4-7.5 - CLAYEY SAND-SANDY CLAY; light brown; 50% sand, fine, 50% fines, low plasticity; medium dense; damp, slight odor	6	R-3 7 12 14	1.5 1.5	DR		5.0-6.5 CMS
CL	7.5-14.0 - SANDY CLAY; light brown; 70% clay; 25% sand, 5% gravel; no voids; moderate plasticity; Hard.	8				AD	
CL		10	R-4 9 13 20	1.5 1.5	DR		10.0-11.5 CMS
SP	14.0-18.5 GRAVELLY SAND; light brown; no gravel - sand; 20% gravel, dry, very dense.	14				AD	
CL		16	R-5 22 27 27	1.5 1.5	DR		15.0-16.5 CMS
CL	18.5-21.5 - SANDY CLAY; light brown; 53% clay, 15% fine sand; moderate plasticity; damp, hard.	18				AD	
		20					

**W** Wahler  
Associates

JASCO CHEMICAL CORPORATION

EXPLORATION BORING LOG

PROJECT NO.  
JCO-1044

SHEET NO.  
1 OF 2

BORING NO.  
B-2

BORING LOCATION							GROUND EL.	
DEPTH/ELEV. WATER			DRILL CONTRACTOR				TOTAL DEPTH	
DRILL RIG		BORING DIA.	DATE DRILLED			LOGGED BY		
SOIL CLASS.	DESCRIPTION		DEPTH	SAMPLE NO.	PR / ROD	REC.	MODE	REMARKS
	<i>ALLUVIUM</i> 18.5-21.5 - Sandy Clay (Cont.)		20					20.0 - 21.5 CMS 21.5 Terminate hole. Boring backfilled with cement grout
CL			22					
	21.5 - Total Depth		24					
			26					
			28					
			30					
			32					
			34					
			36					
			38					
			40					

DATA ON THIS LOG ARE AN APPROXIMATION OF THE GEOLOGIC AND SUBSURFACE CONDITIONS BECAUSE THE INFORMATION WAS OBTAINED FROM INDIRECT, DISCONTINUOUS, AND POSSIBLY DISTORTED SAMPLING NECESSITATED BY USE OF SMALL-DIAMETER DRILLS. ROTARY DRILLS AND MASS BORING BOLES HAVE FURTHER COMPLICATIONS IN THIS REGARD BECAUSE OF THE NEED TO USE DRILLING FLUID AND/OR CASTING IN ADVANCED Holes.

THIS LOG INDICATES CONDITIONS IN THIS HOLE ONLY ON THE DATE INDICATED AND MAY NOT REPRESENT CONDITIONS AT OTHER LOCATIONS AND ON OTHER DATES. ANY WATER LEVELS KNOWN ARE SUBJECT TO VARIATION.

THIS HOLE WAS LOGGED IN SUCH A WAY AS TO PROVIDE DATA PRIMARILY FOR DESIGN PURPOSES AND NOT NECESSARILY FOR THE PURPOSES OF SPECIFIC CONTRACTORS.

THE STRATIFICATION LINES OR DEPTH INTERVALS REPRESENT THE APPROXIMATE BOUNDARIES BETWEEN MATERIAL TYPES, AND THE TRANSITIONS MAY BE GRADUAL.

SOIL CLASSIFICATIONS SHOWN ON LOGS ARE FIELD CLASSIFICATIONS BASED ON THE UNIFIED SOILS CLASSIFICATION SYSTEM.

W  
Wahler  
Associates

JASCO CHEMICAL CORPORATION

EXPLORATION BORING LOG

BORING NO.

PROJECT NO.  
JCO-10414

SHEET NO.  
2 of 2

B-2

CE6 350 7/2/87

BORING LOCATION JASCO CHEMICAL CORPORATION							GROUND EL.
DEPTH/ELEV. WATER NOT ENCOUNTERED			DRILL CONTRACTOR NEW DRILLING				TOTAL DEPTH 21.5'
DRILL RIG CME-75		BORING DIA. 6"	DATE DRILLED 5-5-87			LOGGED BY RGB	
SOIL CLASS.	DESCRIPTION	DEPTH	SAMPLE NO.	PR ROD	REC.	ZONE	REMARKS
CL	0.0-0.8 - ALUVIUM 0.0-0.8-SANDY CLAY: Light brown, 60% clay; 40% medium sand; low to moderate plasticity; dry; very stiff 0.8-10.0 - SANDY CLAY: dark brown 90% clay; 10% fine sand; moderate plasticity; moist; organic odor; rootlets present; very stiff 3.5 - color change to mottled yellow brown/medium brown; calciche veinlets 5.4 - increase in sand content to 35-40%	0 2 4 6 8 10 12 14 16 18 20	R-1 R-2 R-3 R-4 R-5	3 8 12 7 13 19 7 7 12 7 13 25 13	1.5 1.5 1.5 1.5 1.5 1.5 1.5 1.5 1.5 1.5 1.5 1.5	DR DR DR DR DR DR DR DR DR DR DR	DRILL WITH 6" AUGER 1.0-2.5 - 2.5" California Modified Sampler driven by 140lb hammer falling 30" 3.0-4.5 CMS 5.0-6.5 CMS 10.0-11.5 CMS 15.0-16.5 CMS
SC	10.0-14.0 - CLAYEY SAND: light brown, 75% medium sand, 25% clay; low to moderate plasticity; damp; dense						
SP.	14.0-18.0 - GRAVELLY SAND: yellow brown; 75% sand, 20% gravel <5% clay; dry; dense.						
SC-CL	18.0-21.5 - SANDY CLAY-CLAYEY SAND: light brown; 50% medium sand, 50% clay; moderate plasticity; moist; very stiff.						



 Wahler  
Associates

# JASCO CHEMICAL CORPORATION

**EXPLORATION BORING LOG**

PROJECT 40.

BORING NO.

B-3

BORING LOCATION				GROUND EL.				
DEPTH/ELEV. WATER		DRILL CONTRACTOR			TOTAL DEPTH			
DRILL RIG		BORING DIA.		DATE DRILLED			LOGGED BY	
SOIL CLASS.	DESCRIPTION		DEPTH	SAMPLE NO.	PR RQD	REC.	HODD	REMARKS
	ALLUVIUM		20					20.0-21.5 CMS
CL	18.0-21.5 - SANDY CLAY (CONT.)			R-6	6 9 19	1.5 1.5	DR	21.5 Terminate hole. boring backfilled with cement grout
	21.5 total depth		22					
			24					
			26					
			28					
			30					
			32					
			34					
			36					
			38					
			40					
Wahler Associates		JASCO CHEMICAL CORPORATION			EXPLORATION BORING LOG			BORING NO.
					PROJECT NO.	SHEET NO.		
					JCO-104H	2 OF 2		B-3

DATA ON THIS LOG ARE AN APPROXIMATION OF THE GEOLOGIC AND SUBSURFACE CONDITIONS BECAUSE THE INFORMATION WAS OBTAINED FROM INDIRECT, DISCONTINUOUS, AND POSSIBLY DISTURBED SAMPLING NECESSITATED BY USE OF SMALL-DIAMETER HOLES. ROTARY AND WASH BORING HOLES HAVE FURTHER COMPLICATIONS IN THIS REGARD BECAUSE OF THE NEED TO USE DRILLING FLUID AND/OR CASTING IN ADVANCING HOLES.

THIS LOG INDICATES CONDITIONS IN THIS HOLE ONLY ON THE DATE INDICATED AND MAY NOT REPRESENT CONDITIONS AT OTHER LOCATIONS AND ON OTHER DATES. ANY WATER LEVELS SHOWN ARE SUBJECT TO VARIATION.

THIS HOLE WAS LOGGED IN SUCH A WAY AS TO PROVIDE DATA PRIMARILY FOR DESIGN PURPOSES AND NOT NECESSARILY FOR THE PURPOSES OF SPECIFIC CONTRACTORS.

THE STRATIFICATION LINES OR DEPTH INTERVALS REPRESENT APPROXIMATE BOUNDARIES BETWEEN MATERIAL TYPES, AND THE TRANSITIONS MAY BE GRADUAL.

SOIL CLASSIFICATIONS SHOWN ON LOGS ARE FIELD CLASSIFICATIONS BASED ON THE UNIFIED SOILS CLASSIFICATION SYSTEM.

BORING LOCATION JASCO CHEMICAL CORPORATION							GROUND EL.
DEPTH/ELEV. WATER NOT ENCOUNTERED			DRILL CONTRACTOR NEW DRILLING				TOTAL DEPTH 21.5'
DRILL RIG CME-75		BORING DIA. 6"	DATE DRILLED 6-9-87			LOGGED BY RCB	
SOIL CLASS.	DESCRIPTION	DEPTH	SAMPLE NO.	PR RQD	REC.	MODE	REMARKS
	ALLUVIUM	0					DRILL WITH 6" AUGER
	0.0-9.0 - SANDY CLAY: dark brown; 80% silt, 20% sand; moderate plasticity; dry; Hard.	2	R-1	7 12 21	1.5 1.5	DR	1.0-2.5 2.5" California Modified Sampler (CMS) driven by 140 lb hammer falling 30"
		4	R-2	6 9 15	1.5 1.5	DR	3.0-4.5 CMS
CL	5.0- decrease in sand content to 5-10%	6	R-3	8 9 17	1.5 1.5	DR	5.0-6.5 CMS
		8					AD
	9.0-18.0 - GRAVELY SAND: Light brown; 80% sand, 20% gravel; gravel clasts up to 1" long; dry; dense.	10	R-4	10 16 22	1.5 1.5	DR	10.0-11.5 CMS
SP		12					AD
		14					AD
		16	R-5	18 15 10	1.5 1.5	DR	15.0-16.5 CMS
		18					AD
CL	18.0-21.5 - SANDY CLAY: medium brown; 80% clay; 20% fine sand; moderate plasticity; damp; very stiff.	20					

BORING LOCATION							GROUND EL.
DEPTH/ELEV. WATER		DRILL CONTRACTOR				TOTAL DEPTH	
DRILL RIG		BORING DIA.	DATE DRILLED				LOGGED BY
SOIL CLASS.	DESCRIPTION	DEPTH	SAMPLE NO.	PR RQD	REC.	HODGE	REMARKS
	ALLUVIUM (8.0-21.5 - SANDY CLAY (CUMT.) CL	20	R-6	9 12 19	1.5 1.5	DR	20.0-21.5 CMS 21.5 Terminate hole. boring backfilled WITH CEMENT GROUT
	21.5 - TOTAL DEPTH	22					
		24					
		26					
		28					
		30					
		32					
		34					
		36					
		38					
		40					

DATA ON THIS LOG ARE AN APPROXIMATION OF THE GEOLOGIC AND SUBSURFACE CONDITIONS BECAUSE THE INFORMATION WAS OBTAINED FROM INDIRECT, DISCONTINUOUS, AND POSSIBLY DISTURBED SAMPLING NECESSITATED BY USE OF SMALL-DIAMETER HOLES. ROTARY AND WASH BORING HOLES HAVE FURTHER COMPLICATIONS IN THIS REGARD BECAUSE OF THE NEED TO USE DRILLING FLUID AND/OR Casing IN ADVANCING HOLES.

THIS LOG INDICATES CONDITIONS IN THIS HOLE ONLY ON THE DATE INDICATED AND MAY NOT REPRESENT CONDITIONS AT OTHER LOCATIONS AND ON OTHER DATES. ANY WATER LEVELS SHOWN ARE SUBJECT TO VARIATION.

THIS HOLE WAS LOGGED IN SUCH A MANNER AS TO PROVIDE DATA PREDIMINARILY FOR DESIGN PURPOSES AND NOT NECESSARILY FOR THE PURPOSES OF SPECIFIC CONTRACTORS.

THE STRATIFICATION LINES OR DEPTH INTERVALS REPRESENT THE APPROXIMATE BOUNDARIES BETWEEN MATERIAL TYPES, AND THE TRANSITIONS MAY BE GRADUAL.

SOIL CLASSIFICATIONS SHOWN ON LOGS ARE FIELD CLASSIFICATIONS BASED ON THE UNIFIED SOILS CLASSIFICATION SYSTEM.

Wahler  
Associates

JASCO CHEMICAL CORPORATION

EXPLORATION BORING LOG

BORING NO.

PROJECT NO.  
JCO-1041F

SHEET NO.  
2 OF 2

B-4

Crest Solomon  
CE 6# 350 7/2/87

BORING LOCATION JASCO CHEMICAL CORPORATION							GROUND EL.
DEPTH/ELEV. WATER NOT ENCOUNTERED		DRILL CONTRACTOR HEW DRILLING			TOTAL DEPTH 21.5'		
DRILL RIG CME-115		BORING DIA. 6"		DATE DRILLED 6-10-87		LOGGED BY RGB	
SOIL CLASS.	DESCRIPTION	DEPTH	SAMPLE NO.	PR RQD	REC.	HOLE	REMARKS
SP	0.0-0.5 - FILL medium, dry, loose. ACCUMULUS	0				AD	DRILL WITH 6" TUBE
CH	0.5-4.5 - CLAY; dark brown; 79.5% clay <3% sand, moderate to high plasticity, damp. STIFF.	2	R-1	1.5 1.5	P		1.0-2.5 2.5" California Modified Sampler (CMS).
		4	R-2	1.5 1.5	P		3.0-4.5 CMS
	4.5-14.0 - SANDYCLAY; blue/green 70% clay, 30% silt, sand, moderate plasticity, strong chemical odor, stiff, firm	6	R-3	1.5 1.5	P		5.0-6.5 CMS
CL		8				AD	
	10.5 - carbonate, somewhat blue-green/brown, CALICHE veins	10	R-4	1.5 1.5	P		10.0-11.5 CMS
		12				AD	
	14.0-20.5 - GRAVELYSAND; medium brown, 80% sand, 20% gravel, <3% clay; LOOSE, dry,	14					
SP1	water present.	16	R-5	1.5 1.5	P		13.0-15.5 CMS
		18				AD	
		20					

Wahler Associates	JASCO CHEMICAL CORPORATION	EXPLORATION BORING LOG		BORING NO.
		PROJECT NO.	SHEET NO.	
		JCO-104H	1 OF 2	B-5

BORING LOCATION							GROUND EL.		
DEPTH/ELEV. WATER			DRILL CONTRACTOR				TOTAL DEPTH		
DRILL RIG		BORING DIA.	DATE DRILLED			LOGGED BY			
SOIL CLASS.	DESCRIPTION		DEPTH	SAMPLE NO.	PR RQD	REC.	MODE	REMARKS	
ESP	14.0-20.5 Gravelly Sand (Crun)           20.5-21.5 Gravelly clayey Sand           Medium brown; Go 10% Sand, 20% Gravel, 20% Clay;		20	R-6	1.5	1.5	P	20.0-21.5 CMS 21.5 Terminate hole. boring backfilled with cement grout	
SC	21.5 - TOTAL DEPTH		22						
			24						
			26						
			28						
			30						
			32						
			34						
			36						
			38						
			40						
DATA ON THIS LOG ARE AN APPROXIMATION OF THE GEOLOGIC AND SUBSURFACE CONDITIONS BECAUSE THE INFORMATION WAS OBTAINED FROM INDIRECT, DISCONTINUOUS, AND POSSIBLY DISTURBED SAMPLING, NECESSITATED BY USE OF A SMALL-DIAMETER DRILL. ROTARY AND WASH DRILLING HOLE SAW FURTHER COMPLICATIONS IN THIS REGARD BECAUSE OF THE NEED TO USE DRILLING FLUID AND/OR CASING IN ADVANCING HOLES.									
THIS LOG INDICATES CONDITIONS IN THIS HOLE ONLY ON THE DATE INDICATED AND MAY NOT REPRESENT CONDITIONS AT OTHER LOCATIONS AND ON OTHER DATES. ANY WATER LEVELS SHOWN ARE SUBJECT TO VARIATION.									
THIS HOLE WAS LOGGED IN SUCH A WAY AS TO PROVIDE DATA PRIMARILY FOR DESIGN PURPOSES AND NOT NECESSARILY FOR THE PURPOSES OF SPECIFIC CONTRACTORS.									
THE STRATIFICATION LINES OR DEPTH INTERVALS REPRESENT THE APPROXIMATE BOUNDARIES BETWEEN MATERIAL TYPES, AND THE TRANSITIONS MAY BE GRADUAL.									
SOIL CLASSIFICATIONS SHOWN ON LOGS ARE FIELD CLASSIFICATIONS BASED ON THE UNIFIED SOILS CLASSIFICATION SYSTEM.									
 Wahler Associates		JASCO CHEMICAL CORPORATION			EXPLORATION BORING LOG		BORING NO.		
					PROJECT NO.	SHEET NO.			
					JCO-10414	2 OF 2	B-5		

BORING LOCATION JASCO CHEMICAL CORPORATION						GROUND EL.
DEPTH/ELEV. WATER NOT ENCOUNTERED			DRILL CONTRACTOR IT&EW DRILLING			TOTAL DEPTH 21.5'
DRILL RIG CME-45	BORING DIA. 6"		DATE DRILLED 6-10-87		LOGGED BY RGC	
SOIL CLASS.	DESCRIPTION	DEPTH	SAMPLE NO.	PR ROD	REC.	MODE
SP	0.0-0.8' FILL Medium, dry loose,	0			AD	DRILL WITH 5" AUGER
CH	0.8-5.8' ALCUVIUM 0.9-5.8' SANDY CLAY: dark brown 95% clay, <5% sand; moderate plasticity; damp; SOFT.	2	R-1	1.5 1.5	P	1.0-2.5 2.5" (California Modified Sampler (CMS))
	3.0- Color change to medium brown	4	R-2	1.5 1.5	P	3.0-4.5 CMS
	5.8-15.2' SANDY CLAY: medium brown; 60% clay; 40% sand, fine; moderate plasticity; moist; firm; slightly odor	6	R-3	1.5 1.5	P	5.0-6.5 CMS
CL	10.5- decrease in Sand Content to 25%	8			AD	
		10	R-4	1.5 1.5	P	10.0-11.5 CMS
		12			AD	
		14			AD	
SP	15.2-17.0' GRAVELY SAND: medium brown; 25% sand, 15% gravel, dry, loose.	16	R-5	1.5 1.5	P	15.0-16.5 CMS
SC-CL	17.0-21.5' CLAYERSAND - SANDY CLAY: Med. brown; 30% fine sand; 50% clay, soft, "moderate" low plasticity	18			F.D.	
		20				

BORING LOCATION							GROUND EL.
DEPTH/ELEV. WATER		DRILL CONTRACTOR					TOTAL DEPTH
DRILL RIG		BORING DIA.	DATE DRILLED			LOGGED BY	
SOIL CLASS.	DESCRIPTION	DEPTH	SAMPLE NO.	PR RQD	REC.	HOLE	REMARKS
	ACQUARIUM 17.0-21.5 Clayey Sand (Cont.)	20					20.0-21.5 CMS 21.5 Terminate hole. Boring backfilled with cement grout
CL			B-6		1.5 1.5	P	
	21.5 TOTAL DEPTH	22					
		24					
		26					
		28					
		30					
		32					
		34					
		36					
		38					
		40					

DATA ON THIS LOG ARE AN APPROXIMATION OF THE GEOLOGIC AND SUBSURFACE CONDITIONS BECAUSE THE INFORMATION WAS OBTAINED FROM INDIRECT, DISCONTINUOUS, AND POSSIBLY DISTURBED SAMPLING NECESSITATED BY USE OF SMALL-DIAMETER HOLES. ROTARY AND WASH BORING HOLES HAVE FURTHER COMPLICATIONS IN THIS REGARD BECAUSE OF THE NEED TO USE DRILLING FLUID AND/OR CASING IN ADVANCING HOLES.

THIS LOG INDICATES CONDITIONS IN THIS HOLE ONLY ON THE DATE INDICATED AND MAY NOT REPRESENT CONDITIONS AT OTHER LOCATIONS AND ON OTHER DATES. ANY WATER LEVELS SHOWN ARE SUBJECT TO VARIATION.

THIS HOLE WAS LOGGED IN SUCH A WAY AS TO PROVIDE DATA PRIMARILY FOR DESIGN PURPOSES AND NOT NECESSARILY FOR THE PURPOSES OF SPECIFIC CONTRACTORS.

THE STRATIFICATION LINES OR DEPTH INTERVALS REPRESENT THE APPROXIMATE BOUNDARIES BETWEEN MATERIAL TYPES, AND THE TRANSITIONS MAY BE GRADUAL.

SOIL CLASSIFICATIONS SHOWN ON LOGS ARE FIELD CLASSIFICATIONS BASED ON THE UNIFIED SOILS CLASSIFICATION SYSTEM.

 Wahler  
Associates

JASCO CHEMICAL CORPORATION

EXPLORATION BORING LOG  
PROJECT NO. JCO-104H  
SHEET NO. 2 OF 2

BORING NO.  
B-6

OEG #350 7/2/87

BORING LOCATION FASCO CHEMICAL CORPORATION							GROUND EL.
DEPTH ELEV. WATER NOT ENCOUNTERED			DRILL CONTRACTOR HENI DRILLING			TOTAL DEPTH 21.5'	
DRILL RIG CUE-5			BORING DIA. 6"		DATE DRILLED 6-10-87		LOGGED BY RGB
SOIL CLASS.	DESCRIPTION	DEPTH	SAMPLE NO.	PR ROD	REC.	MODE	REMARKS
		0					DRILLED WITH 5" AUGER
CL	3.0-10.5 - Silt - CLAY: dark brown, 30% silt; 20% fine sand; low to moderate plasticity, damp, stiff.	2	R-1	1.5 1.5	P	AD	1.0-2.5 2.5" California Modified Sampler (CMS)
	3.0-10.5 - Silt + clay: Mottled blue-green/medium brown; 70% silt; 30% fine sand; low to moderate plasticity, damp, stiff.	4	R-2	1.5 1.5	P	AD	3.0-4.5 CMS
CL	5.5 - Clay changes to medium brown, sand cement dominant to 10'.	6	R-3	1.5 1.5	P	AD	5.0-6.5 CMS
		8				AD	
		10				AD	
SC	5.5- 6.5 - SANDY CLAY/SAND: light brown, medium brown/yellow brown, 50% gravel (sand, 20% gravel); 20% silt; loose, friable, loose	12	R-4	1.5 1.5	P	AD	10.0-11.5 CMS
		14				AD	
		16				AD	
CL	5.5- 7.5 - SANDY CLAY: light brown, 50% silt-free; 30-40% fine sand mixed w/ sand; soft to firm; moderate plasticity	18	R-5	0.7 1.5	P	AD	15.0-16.5 CMS
		20				AD	

Walter  
Associates

FASCO CHEMICAL CORPORATION

EXPLORATION BORING LOG

BORING NO.

PROJECT NO.  
JCO-10414SHEET NO.  
1 OF 2

B-7

BORING LOCATION						GROUND EL.	
DEPTH/ELEV. WATER		DRILL CONTRACTOR				TOTAL DEPTH	
DRILL RIG		BORING DIA.	DATE DRILLED			LOGGED BY	
SOIL CLASS.	DESCRIPTION	DEPTH	SAMPLE NO.	PR RQD	REC.	HOE	REMARKS
CL	ALLUVIUM 16.8-21.5 - SANDY CLAY (CONT)	20	R-6	1.5 1.5	P		20-21.5 CMS 21.5 terminate hole boring backfilled with cement grout
	21.5 - TOTAL DEPTH	22					
		24					
		26					
		28					
		30					
		32					
		34					
		36					
		38					
		40					

DATA ON THIS LOG ARE AN APPROXIMATION OF THE GEOLOGIC AND SURFACE CONDITIONS BECAUSE THE INFORMATION WAS OBTAINED FROM INDIRECT, DISCONTINUOUS AND POSSIBLY DISTORTED SAMPLING NECESSITATED BY USE OF SMALL-DIAMETER HOLE. ROTARY AND WASH BORING HOLES HAVE FURTHER COMPLICATIONS IN THIS REGARD BECAUSE OF THE NEED TO USE DRILLING FLUID AND/OR CASING IN ADVANCING HOLES.

THIS LOG INDICATES CONDITIONS IN THIS HOLE ONLY ON THE DATE INDICATED AND MAY NOT REPRESENT CONDITIONS AT OTHER LOCATIONS AND ON OTHER DATES. ANY WATER LEVELS SHOWN ARE SUBJECT TO VARIATION.

THIS HOLE WAS LOGGED IN SUCH A WAY AS TO PROVIDE DATA PRIMARILY FOR DESIGN PURPOSES AND NOT NECESSARILY FOR THE PURPOSES OF SPECIFIC CONTRACTORS.

THE STRATIFICATION LINES OR DEPTH INTERVALS REPRESENT THE APPROXIMATE BOUNDARIES BETWEEN MATERIAL TYPES, AND THE TRANSITIONS MAY BE GRADUAL.

SOIL CLASSIFICATIONS SHOWN ON LOGS ARE FIELD CLASSIFICATIONS BASED ON THE UNIFIED SOILS CLASSIFICATION SYSTEM.

W  
Wahler  
Associates

JASCO CHEMICAL CORPORATION

EXPLORATION BORING LOG

BORING NO.

PROJECT NO.  
JCU-104H

SHEET NO.  
2 OF 2

B-7

BORING LOCATION JASCO CHEMICAL CORPORATION							GROUND EL.
DEPTH/ELEV. WATER NOT ENCOUNTERED				DRILL CONTRACTOR H&W DRILLING			TOTAL DEPTH 21.5'
DRILL RIG CME-45	BORING DIA. 6"	DATE DRILLED 6-10-87			LOGGED BY RSB		
SOIL CLASS.	DESCRIPTION	DEPTH	SAMPLE NO.	PR RQD	REC.	MODE	REMARKS
EX	0.0-0.5: EXCAVATION	0				AD	DRILL WITH 6" AUGER.
OR	0.5-1.5: ORGANIC RESIDUE; white, crystalline, Odorous, highly odorous, soft ALLUVIUM	2	R-1	0.5 1.5	P		1.0-2.5 2.5" California Modified Smoother (CMS)
CL	1.5-13.5- SANDY CLAY; dark brown; 60% clay, 40% sand; low to moderate plasticity; extremely odorous with organic vapors;	4	R-2	1.5 1.5	P		3.0-4.5 CMS
		6	R-3	1.5 1.5	P		5.0-6.5 CMS
		8				AD	
		10					10.0-11.5 CMS
	10.0- Moderate plasticity, extremely odorous; caliche veins,	12	R-4	1.5 1.5	P		
SP1	13.5-16.5- GRANULAR SAND; greenish black to olive green; 70% medium sand, 20% gravel, moist, loose, highly odorous.	14				AD	
		16	R-5	1.5 1.5	P		15.0-16.5 CMS
CL- SC	16.5-21.5- SANDY CLAY- CLAYEY SAND: greenish black 50% clay, 50% fine sand. Low to moderate plasticity; odorous	18				AD	
		20					

W Wahler Associates	JASCO CHEMICAL CORPORATION	EXPLORATION BORING LOG		BORING NO.
		PROJECT NO.	SHEET NO.	B-8
		C0004H	1 OF 2	

BORING LOCATION							GROUND EL.	
DEPTH/ELEV. WATER			DRILL CONTRACTOR				TOTAL DEPTH	
DRILL RIG		BORING DIA.	DATE DRILLED			LOGGED BY		
SOIL CLASS.	DESCRIPTION		DEPTH	SAMPLE NO.	PR / RQD	REC.	MODE	REMARKS
CL/ SC	16.5-21.5' <sup>ACLUVIAL</sup> Sandy Clay/clayey Sand (cont.)		20	R-6	15 15	P		20.0-21.5 CMS 21.5 Terminate hole. boring backfilled with cement grout
	21.5 - TOTAL DEPTH		22					
			24					
			26					
			28					
			30					
			32					
			34					
			36					
			38					
			40					
DATA ON THIS LOG ARE AN APPROXIMATION OF THE GEOLOGIC AND SURFACE CONDITIONS BECAUSE THE INFORMATION WAS OBTAINED FROM INDIRECT, DISCONTINUOUS, AND POSSIBLY DISTURBED SAMPLING NECESSITATED BY USE OF SMALL-DIAMETER HOLES. ROTARY AND WASH BORING HOLES HAVE FURTHER COMPLICATIONS IN THIS REGARD BECAUSE OF THE NEED TO USE DRILLING FLUID AND/OR CASING IN ADVANCING HOLES.  THIS LOG INDICATES CONDITIONS IN THIS HOLE ONLY ON THE DATE INDICATED AND MAY NOT REPRESENT CONDITIONS AT OTHER LOCATIONS AND ON OTHER DATES. ANY WATER LEVELS SHOWN ARE SUBJECT TO VARIATION.  THE STRATIFICATION LINES OR DEPTH INTERVALS REPRESENT THE APPROXIMATE BOUNDARIES BETWEEN MATERIAL TYPES, AND THE TRANSITIONS MAY BE GRADUAL.  SOIL CLASSIFICATIONS SHOWN ON LOGS ARE FIELD CLASSIFICATIONS BASED ON THE UNIFIED SOILS CLASSIFICATION SYSTEM.								
<b>W</b> Wahler Associates		<b>JASCO CHEMICAL CORPORATION</b>				<b>EXPLORATION BORING LOG</b>		
		PROJECT NO. JCO-10044		SHEET NO. 2 OF 2		<b>BORING NO.</b> <b>B-8</b>		

BORING LOCATION: SEE SITE PLAN			GROUND EL.		TOTAL DEPTH: 21.5'		
DEPTH/ELEV. WATER: not encountered		DRILL CONTRACTOR: HEW Drilling			LOGGED BY: PGB		
DRILL RIG: CME 45		BORING DIR: S.0°		DATE DRILLED: 4-5-88		APPROVED BY: F-H	
SOIL CLASS	DESCRIPTION	DEPTH	SAMPLE #	PR REQ	RQD	MODE	REMARKS
LL	<u>ALLUVIUM</u> 0.0'- 4.5' <u>SANDY CLAY</u> : dark brown, damp; hard; moderate to high plasticity, occasional gravel fragments; chemical odor present	0				HA	1.0'-2.5': 2.5" dia California modified sampler driven using 140 lb hammer falling 30" (CALMOD) 2.0'-2.5': Gas Tech = 56 ppm
CL		2	R-1	9 17 20	0.8 1.5	DR	2.0'-2.5': Sample taken 3.0'-4.5': CALMOD 3.0'-3.5': Gas Tech = 125 ppm
CL		4	R-2	10 14 20	0.9 1.5	DR	4.0'-4.5': Sample taken 5.0'-6.5': CALMOD 5.0'-5.5': Gas Tech = 265 ppm
SP	4.5'-13.0' <u>SANDY CLAY</u> : greenish brown; very stiff; low to moderate plasticity, chemical odor.	6	R-3	6 9 10	1.3 1.5	DR	6.0'-6.5': Sample taken
SC-CL		8				HA	
SC-CL	11.0' Color change to grayish olive green.	10	R-4	6 11 17	1.2 1.5	DR	10.0'-11.5': CALMOD 10.5'-11.0': Gas Tech = 250 ppm 11.0'-11.5': Sample taken
SC-CL	13.0'-16.0' <u>GRAVELLY SAND</u> : same, medium dense, low plasticity.	12				HA	
SC-CL		14				HA	
SC-CL		16	R-5	7 7 9	1.1 1.5	DR	15.0'-16.5': CALMOD 15.5'-16.0': Gas Tech = 255 ppm 16.0'-16.5': Sample taken
SC-CL	18.0'-21.5' <u>CLAYEY SAND - SANDY CLAY</u> : grayish olive green	18				HA	
SC-CL		20				HA	



HAHLER  
ASSOCIATES

Jasco Chemical Corporation

EXPLORATION BORING LOG		BORING NO.
Project No.	Sheet No.	
JCO-105H	of 2	B-9

BORING LOCATION: SEE SITE PLAN			GROUND EL:		TOTAL DEPTH 21.5'			
DEPTH/ELEV. WATER: not encountered		DRILL CONTRACTOR: HEW Drilling			LOGGED BY: PCB			
DRILL DIS. CME 45	BORING DIA: 8.0"	DATE DRILLED: 4-5-88			APPROVED BY: F.A.			
SOIL CLASS	DESCRIPTION	DEPTH (ft.)	SAMPLE #	PR REQ	RQD	MODE	REMARKS	
SC-1	18.0'-21.5' CLAYEY SAND (cont.)	20	R-6	6 14 20	1.3 1.5	DR	20.0'-21.5' CALMOC 20.5-21.5' Gas Tech = 170 ppm 21.0'-21.5'. Sample taken	
		22					Terminate boring at 21.5'. Filled with neat cement to surface.	

DATA ON THIS LOG ARE AN APPROXIMATION OF THE GEOLOGIC AND SURFACE CONDITIONS BECAUSE THE INFORMATION WAS OBTAINED FROM INDIRECT, DISCONTINUOUS, AND POSSIBLY DISTURBED SAMPLING, NECESSITATED BY USE OF SMALL-DIAMETER HOLES. ROTARY AND WASH DRILLING HOLES HAVE FURTHER COMPLICATIONS IN THIS REGARD BECAUSE OF THE NEED TO USE DRILLING FLUID AND/OR CASING IN ADVANCING HOLES.

THIS LOG INDICATES CONDITIONS IN THIS HOLE ONLY ON THE DATE INDICATED AND MAY NOT REPRESENT CONDITIONS AT OTHER LOCATIONS AND ON OTHER DATES. ANY WATER LEVELS SHOWN ARE SUBJECT TO VARIATION.

THIS HOLE WAS LOGGED IN SUCH A MANNER AS TO PROVIDE DATA PRIMARILY FOR DESIGN PURPOSES AND NOT NECESSARILY FOR THE PURPOSES OF SPECIFIC CONTRACTORS.

THE STRATIFICATION LINES OR DEPTH INTERVALS REPRESENT THE APPROXIMATE BOUNDARIES BETWEEN MATERIAL TYPES, AND THE TRANSITIONS MAY BE GRADUAL.

SOIL CLASSIFICATIONS SHOWN ON LOGS ARE FIELD CLASSIFICATIONS BASED ON THE UNIFIED SOILS CLASSIFICATION SYSTEM.



Jasco Chemical Corporation

EXPLORATION BORING LOG		BORING NO.
Project No	Sheet No 2 of 2	8-9
JCO-104H		

BORING LOCATION: SEE SITE PLAN			GROUND EL:		TOTAL DEPTH: 21.5'		
DEPTH/ELEV. WATER: not encountered		DRILL CONTRACTOR: HEW Drilling			LOGGED BY: PL		
DRILL RIG: CME 45	BORING DIR: S.0°	DATE DRILLED: 4-5-88		APPROVED BY: E.H.			
SOIL CLASS	DESCRIPTION	DEPTH (ft.)	SAMPLE #	PR REQ	RQD	MODE	REMARKS
CL	<u>ALLUVIUM</u> 0.0'-11.5' <u>SANDY CLAY</u> . Dark brown; damp; hard; moderate to high plasticity, occasional gravel fragment.	0				HA	1.0'-2.5': 2.5" cal modified sampler driven using 140 lb hammer falling 30" (CALMOD)
		2	R-7	10 20 25	0.5 1.5	DR	2.0'-2.5': Gas Tech = 100 ppm
		4	R-8	10 17 20	0.5 1.5	DR	2.0'-2.5': Sample taken 3.0'-3.5': CALMOD 3.0'-3.5': Sample taken
		6	R-9	3 11 19	0.4 1.5	DR	5.0'-6.5': CALMOD 6.0'-6.5': Gas Tech = 115 ppm
		8				HA	6.0'-6.5': Sample taken
		10	R-10	17 20 25	0.5 1.5	DR	10.0'-11.5': CALMOD 10.5'-11.0': Gas Tech = 145 ppm
	11.5' Color change to grayish olive green	12					11.0'-11.5': Sample taken
	14.25' - 18.0' <u>GRAVELLY SAND</u>	14					
SP		16	R-11	35 50	1.0 1.0	DR	15.0'-16.5': CALMOD 15.0'-15.5': Gas Tech = 155 ppm
		18				HA	15.5'-16.0': Sample taken
SC-CL	18.0'-21.5' <u>CLAYEY SAND - SANDY CLAY</u> . Dusky green.	20					

URHLER ASSOCIATES	Jasco Chemical Corporation	EXPLORATION BORING LOG		BORING NO.
		Project No.	Sheet No.	
		JCO-104H	1 of 2	E-10

BORING LOCATION: SEE SITE PLAN			GROUND EL:			TOTAL DEPTH: 21.5'	
DEPTH/ELEV WATER: not encountered			DRILL CONTRACTOR: HEW Drilling			LOGGED BY: PL	
DRILL RIG: CME 45	BORING DIR: 80°	DATE DRILLED: 4-5-88	APPROVED BY: F-H				
SOIL CLASS	DESCRIPTION	DEPTH (ft.)	SAMPLE #	PR REQ	ROD	MODE	REMARKS
SC-CL	18.0'-21.5' CLAYEY SAND (cont)	20	R-12	7 14 16	1.0 1.5	DR	20.0'-21.5' CALMOD 20.0'-21.0' Gas Tech = 125 ppm 21.0'-21.5' Sample taken
		22					Terminate boring at 21.5'. Filled with neat cement to surface.
DATA OF THIS LOG ARE AN APPROXIMATION OF THE GEOLOGIC AND SURFACE CONDITIONS BECAUSE THE INFORMATION WAS OBTAINED FROM INDIRECT, DISCONTINUOUS, AND POSSIBLY DISTURBED SAMPLING NECESSITATED BY USE OF SMALL-DIAMETER HOLES. ROTARY AND WASH BORING HOLES HAVE FURTHER COMPLICATIONS IN THIS REGARD BECAUSE OF THE NEED TO USE DRILLING FLUID AND/OR CASING IN ADVANCING HOLES.							
THIS LOG INDICATES CONDITIONS IN THIS HOLE ONLY ON THE DATE INDICATED AND MAY NOT REPRESENT CONDITIONS AT OTHER LOCATIONS AND ON OTHER DATES. ANY WATER LEVELS SHOWN ARE SUBJECT TO VARIATION.							
THIS HOLE WAS LOGGED IN SUCH A WAY AS TO PROVIDE DATA PRIMARILY FOR DESIGN PURPOSES AND NOT NECESSARILY FOR THE PURPOSES OF SPECIFIC CONTRACTORS.							
THE STRATIFICATION LINES OR DEPTH INTERVALS REPRESENT THE APPROXIMATE BOUNDARIES BETWEEN HYPOTHETICAL TYPES, AND THE TRANSITIONS MAY BE GRADUAL.							
SOIL CLASSIFICATIONS SHOWN ON LOG ARE FIELD CLASSIFICATIONS BASED ON THE UNIFIED SOILS CLASSIFICATION SYSTEM.							



Jasco Chemical Corporation

Project No.	Sheet No.	No.
JCD-104H	2 of 2	6-10

#### EXPLORATION BORING LOG BORING

BORING LOCATION: SEE SITE PLAN			GROUND EL.		TOTAL DEPTH: 21.5'			
DEPTH/ELEM. WATER, not encountered		DRILL CONTRACTOR HEM Drilling		LOGGED BY PL				
DRILL RIG: CME 45	BORING DIR: S.0°	DATE DRILLED: 4-5-88		APPROVED BY: E.H				
SOIL CLASS	DESCRIPTION	DEPTH (ft)	SAMPLE #	PR REQ	ROD	MODE	REMARKS	
CL	<u>ALLUVIUM</u>	0				HA	1.0'-2.5'; 2.5" dia. California modified sampler driven using 140 lb hammer falling 30" (CALMOD)	
	0.0' - 16.2' SANDY CLAY dark brown; damp; hard; moderate to high plasticity, occasional gravel fragments	2	R-13	40 35 15	0.7 1.5	DR	1.0'-2.0'; Gas Tech = 85 ppm 2.0'-2.5'; Sample taken	
		4	R-14	7 17 21	0.8 1.5	DR	3.0'-4.5'; CALMOD 3.0'-4.0'; Gas Tech = 100 ppm	
		5	R-15	9 14 16	0.8 1.5	DR	4.0'-4.5'; Sample taken 5.0'-6.5'; CALMOD 5.5'-6.0'; Gas Tech = 125 ppm	
	6.0' - 6.5' Caliche mottling; moderate plasticity.	8				HA	6.0'-6.5'; Sample taken	
		10				HA	10.0'-11.5'; CALMOD	
		12				HA	10.5'-11.0'; Gas Tech = 115 ppm	
		14				HA	11.0'-11.5'; Sample taken	
GC	16.2' - 18.0' CLAYEY GRAVEL grayish olive / moderate yellow brown mottling; moist; dense.	16	R-17	16 20 35	1.2 1.5	DR	15.0'-16.5'; CALMOD 15.5'-16.0'; Gas Tech = 0.0 ppm	
SC	18.0' - 20.5' CLAYEY SAND light olive gray, moist, medium dense.	18				HA	16.0'-16.5'; Sample taken	
		20				HA		



WRRLER  
ASSOCIATES

Jasco Chemical Corporation

EXPLORATION BORING LOG		BORING NO.
Project No	Sheet No	
JCC-104H	of 2	8-11

BORING LOCATION: SEE SITE PLAN		GROUND EL:	TOTAL DEPTH: 21.5'				
DEPTH/ELEV. WATER: not encountered		DRILL CONTRACTOR: HEW Drilling	LOGGED BY: PL				
DRILL: BIG CME 45	BORING DIR: 90°	DATE DRILLED: 4-5-88	APPROVED BY: E.H.				
SOIL CLASS	DESCRIPTION	DEPTH (ft.)	SAMPLE #	PR REQ	RQD	MODE	REMARKS
SC	18.0' - 20.5' CLAYEY SAND (cont)	20		16	15		20.0'-21.5': CALMOD
SP	20.5' - 21.5' GRAVELLY SAND: mod. erate yellow brown; moist; dense		R-18	40	15	DR	20.5'-21.0': Gas Tech = 120 ppm 21.0'-21.5': Sample taken
		22					Terminate boring at 21.5'. Filled with neat cement to surface.
<p style="text-align: center;">DATA ON THIS LOG ARE AN APPROXIMATION OF THE GEOLOGIC AND SUBSURFACE CONDITIONS BECAUSE THE INFORMATION WAS OBTAINED FROM INDIRECT, DISCONTINUOUS, AND POSSIBLY DISTURBED SAMPLING NECESSITATED BY USE OF SMALL-DIAMETER HOLES. ROTARY AND WASH DRILLING Holes HAVE FURTHER COMPLICATIONS IN THIS REGARD BECAUSE OF THE NEED TO USE DRILLING FLUID AND/OR CASING IN ADVANCING HOLES.</p> <p style="text-align: center;">THIS LOG INDICATES CONDITIONS IN THIS HOLE ONLY ON THE DATE INDICATED AND MAY NOT REPRESENT CONDITIONS AT OTHER LOCATIONS AND ON OTHER DATES. ANY WATER LEVELS SHOWN ARE SUBJECT TO VARIATION.</p> <p style="text-align: center;">THE STRATIFICATION LINES OR DEPTH INTERVALS REPRESENT THE APPROXIMATE BOUNDARIES BETWEEN MATERIAL TYPES, AND THE TRANSITIONS MAY BE GRADUAL.</p> <p style="text-align: center;">SOIL CLASSIFICATIONS SHOWN ON LOGS ARE FIELD CLASSIFICATIONS BASED ON THE UNIFIED SOIL CLASSIFICATION SYSTEM.</p>							
 <b>WRHLER ASSOCIATES</b>		<b>Jasco Chemical Corporation</b>		EXPLORATION BORING LOG		BORING NO.	
		Project No.	Shut No.	2	of	2	
		JCU-104H				B-11	

BORING LOCATION: SEE SITE PLAN			GROUND EL:			TOTAL DEPTH: 6.5			
DEPTH/ELEV. WATER: Not encountered		DRILL CONTRACTOR: HEW Drilling			LOGGED BY: PL				
DRILL RIG: SME 45	BORING DIA: 8.0"	DATE DRILLED: 4-5-86			APPROVED BY: F.H.				
SOIL CLASS	DESCRIPTION	DEPTH	SAMPLE #	PR. REQD	RQD	NOTE	REMARKS		
CL		0'				HA	1.0'-2.5': Cal. modified sampler driven using 140 lb hammer falling 30" (CALMOD)		
CL		2'	R-19	5	0.7	DR	1.5'-2.5': Gas Tech = 0.0 ppm		
CL		2'		7	1.5		2.0'-2.5': Sample taken		
CL		2'		9			3.0'-4.5': CALMOD		
CL		4'	R-20	7	0.7	DR	3.5'-4.0': Gas Tech = 125 ppm		
CL		4'		23	1.5		4.0'-4.5': Sample taken		
CL		4'		29			5.0'-6.5': CALMOD		
CL		6'	R-21	5	1.0	DR	5.5'-6.0': Gas Tech = 0.0 ppm		
CL		6'		9	1.5		6.0'-6.5': Sample taken		
CL							Boring terminated @ 6.5'		
CL							Filled with neat cement to surface.		
<p>DATA ON THIS LOG ARE AN APPROXIMATION OF THE GEOLOGIC AND SUBSURFACE CONDITIONS BECAUSE THE INFORMATION WAS OBTAINED FROM INDIRECT, DISCONTINUOUS AND POSSIBLY DISTURBED SAMPLING NECESSITATED BY USE OF SMALL-DIAMETER Holes. ROTARY AND WASH DRILLING HOLES HAVE FURTHER COMPLICATIONS IN THIS REGARD BECAUSE OF THE NEED TO USE DRILLING FLUID AND/OR CASING IN ADVANCING HOLES.</p> <p>THIS LOG INDICATES CONDITIONS IN THIS HOLE ONLY ON THE DATE INDICATED AND MAY NOT REPRESENT CONDITIONS AT OTHER LOCATIONS AND ON OTHER DATES. ANY WATER LEVELS SHOWN ARE SUBJECT TO VARIATION.</p> <p>THE STRATIFICATION LINES OR DEPTH INTERVALS REPRESENT THE APPROXIMATE BOUNDARIES BETWEEN MATERIAL TYPES, AND THE TRANSITIONS MAY BE GRADUAL.</p> <p>SOIL CLASSIFICATIONS SHOWN ON LOG ARE FIELD CLASSIFICATIONS BASED ON THE UNIFIED SOILS CLASSIFICATION SYSTEM.</p>									

  
**WAHLER  
ASSOCIATES**

Jasco Chemical Corporation

EXPLORATION BORING LOG		BORING NO.
Project No.	Sheet No.	
JCO-104H	of	B-12
	1	

JOB NO.	7403
---------	------

BORE HOLE NO.	C-1
---------------	-----

PROJECT	Jasco Chemical Corp.		LOCATION	Mountain View, CA	
DRILLING CONTRACTOR	ASE Drilling		DRILLING EQUIPMENT	'8" Hollow Stem Auger	
HYDROGEOLOGIST	Scott Rice		DRILLER	Chris	
DATE START/TIME	7/13/90 0900	DATE FINISH/TIME	7/13/90 1045	SURFACE ELEVATION	TOTAL DEPTH
WELL CASTING			SCREEN TYPE	LENGTH	SLOT

DEPTH	SAMPLE NUMBER	BLOW COUNT PER 6'	RECOVERY	BORE HOLE LOG		
				LITHOLOGIC DESCRIPTION	REMARKS	GRAPHIC LOG
	B-1-3	7/9/14	16"	CL - sandy clay, black (7.5YR 2/0), 30-40% medium sand, subrounded particles to 2 mm diameter, low plasticity cuttings grade lighter in color----- SM - silty fine to medium sand, very dark gray (7.5YR 3/0), 30% silt, trace clay, moist, poorly sorted, particles to 0.5 mm diameter, friable	hydrocarbon odor PID (sample) - 60	
5	B-1-5	4/5/8	13"	cuttings grade finer-----	hydrocarbon odor PID (sample) - 120 PID (borehole) - 1.0	
				ML - sandy silt, greenish gray, 20-25% moderately well sorted sand to 0.5 mm diameter, trace clay, moist, friable, not plastic	hydrocarbon odor in cuttings	
10	B-1-10	6/7/8	16"	cuttings grade finer-----	hydrocarbon odor PID (sample) - 72	
				CL - clay, olive gray (5Y 4/3), trace sand, trace silt, moist, moderate plasticity, firm -- SW - gravelly sand, greenish gray, 25% gravel to 1 cm diameter, very moist, very poorly sorted CL - clay, olive gray (5Y 4/3), 15-20% poorly sorted, medium sand, trace silt, moist, moderate plasticity, firm	hydrocarbon odor PID (borehole) - 1.0	
15	B-1-15	7/4/5	18"	CL/SC - sandy and silty clay, greenish gray, 30% silt, 20% sand, moist, low plasticity, firm, interbedded with clayey and silty sand, olive (5Y 4/4), moist, poorly sorted, particles to 2 mm diameter	moderate hydrocarbon odor PID (sample) - 34	
				SC - sandy silt and clay, bluish gray, 30% silt, 30% poorly sorted sand, moist abundant plant rootlets SM - fine sand, olive gray (5Y 4/2), 20% silt, no clay, wet, moderately well sorted, soft	moderate hydrocarbon odor PID (sample) - 110	
20	B-1-20	4/7/11	17"			
				SC - clayey sand, bluish gray, 30% clay, moist but wet at 31.5 feet, poorly sorted, particles to 3 mm diameter, abundant plant rootlets, friable	moderate hydrocarbon odor PID (sample) - 52	
25	B-1-25	NA	18"	Total depth - 31.5 feet		
30	B-1-30	NA	18"			
35						

## PART 1

PAGE 1 OF 1

JOB NO.	7403
---------	------

BORE HOLE NO.	C-2
---------------	-----

PROJECT	Jasco Chemical Corp.		LOCATION	Mountain View, CA	
DRILLING CONTRACTOR	ASE Drilling		DRILLING EQUIPMENT	'8" Hollow Stem Auger	
HYDROGEOLOGIST	Scott Rice		DRILLER	Chris	
DATE START/TIME	7/13/90 1115	DATE FINISH/TIME	7/13/90 1230	SURFACE ELEVATION	TOTAL DEPTH
WELL CASING		SCREEN TYPE	-	LENGTH	31.5 feet
					SLOT

DEPTH	SAMPLE NUMBER	BLOW COUNT PER 6'	RECOVERY	BORE HOLE LOG		
				LITHOLOGIC DESCRIPTION	REMARKS	GRAPHIC LOG
2	B-2-3	7/9/14	10"	CL - sandy clay, 30-40% poorly sorted sand to 1 mm diameter, low plasticity, subangular, firm cuttings grade coarser-----	no odor PID (sample) - 0.2	
5	B-2-5	6/7/8	18"	SC - clayey sand, olive gray (5Y 4/2), 40% clay, trace silt, moist, poorly sorted, subangular particles to 1 mm diameter, friable, abundant plant rootlets	no odor PID (sample) - 0.0	
10	B-2-10	7/8/10	18"	SC - clayey sand, olive (5Y 4/3), 30% clay, moist, poorly sorted, subrounded particles to 0.5 mm diameter, friable, zoned with blue-gray clay	no odor PID (sample) - 0.4	
15	B-2-15	10/10/7	18"	ML - sandy silt, dark yellowish brown (10Y 4/6), 30% poorly sorted sand to 0.5 mm diameter, moist, moderately plastic -- SW - gravelly sand, salt and pepper, <10% silt and clay, moist, subangular, very poorly sorted ML - sandy silt, dark yellowish brown (10Y 4/6), 30% poorly sorted sand to 0.5 mm diameter, moist, moderately plastic	no odor PID (sample) - 0.6	
20	B-2-20	4/7/10	17"	SM - silty sand, olive (5Y 4/3), 25% silt, trace clay, moist, poorly sorted, subangular particles to 1 mm diameter, friable, not plastic	no odor PID (sample) - 1.4	
25	B-2-25	8/16/13	18"	SM - sandy silt and silty sand, olive (5Y 4/4), 40-60% silt, 40-60% sand, very moist, low plasticity, soft, grades coarser to blue gray silty sand at 27.75 feet, 30% silt, trace clay, moist, very poorly sorted, particles to 2 mm diameter, friable	slight hydrocarbon odor PID (sample) - 0.8	
30	B-2-30	6/5/7	18"	SW - coarse sand and gravel, bluish gray, 20% silt clay, wet, very poorly sorted, subangular particles to 1 cm diameter, friable to loose	no odor PID (sample) - 0.0	
35				Total depth - 31.5 feet		

## PART 1

JOB NO.  
7403

PAGE 1 OF 1

BORE HOLE NO.  
C-3

PROJECT Jasco Chemical Corp.	LOCATION Mountain View, CA
DRILLING CONTRACTOR ASE Drilling	DRILLING EQUIPMENT 8" Hollow Stem Auger
HYDROGEOLOGIST Scott Rice	DRILLER Chris
DATE START/TIME 7/13/90 1320	DATE FINISH/TIME 7/13/90 1500
WELL CASING	SURFACE ELEVATION LENGTH SLOT

DEPTH	SAMPLE NUMBER	BLOW COUNT PER 6"	RECOVERY	BORE HOLE LOG		GRAPHIC LOG
				LITHOLOGIC DESCRIPTION	REMARKS	
5	B-3-3	4/9/16	12"	SC - clayey sand and sandy clay, dark grayish brown (2.5Y 4/2), 40-60% sand, 40-60% silt, moist, very poorly sorted, particles to 2 mm diameter, not plastic, firm but friable	no odor PID (sample) - 0.0	
	B-3-5	5/11/14	18"	SC - sandy and silty clay, dark grayish brown (2.5Y 4/2), 20-30% sand in lenses to 2 cm thick, 20% silt, poorly sorted, subrounded, low plasticity	no odor PID (sample) - 2.0	
10	B-3-10	7/9/14	18"	SC - clayey sand and sandy clay, dark grayish brown (2.5Y 4/2), 40-60% sand, 40-60% silt, moist, poorly sorted, not plastic, firm	no odor PID (sample) - 0.0	
15	B-3-15	9/9/4	18"	ML - silt and fine sand, dark grayish brown (2.5Y 4/2), grading coarser to 15.5 feet -- SW - coarse sand and gravel, <10% silt and clay, loose, very poorly sorted, subangular CL - sandy clay, 20% silt, moist, moderately plastic	no odor PID (sample) - 0.0	
20	B-3-20	9/15/21	18"	SM - silty sand, olive brown (2.5Y 4/4), 20% silt, moist, very poorly sorted, subrounded particles to 1 cm diameter, loose to friable	no odor PID (sample) - 0.0	
25	B-3-25	6/8/12	18"	SM - silty and clayey sand, dark grayish brown (2.5Y 4/2), 30% silt and clay, very moist, very poorly sorted, subrounded particles to 2 mm diameter, friable, not plastic, abundant iron oxidized plant rootlets	no odor PID (sample) - 0.0	
30	B-3-30	5/9/28	18"	SW - coarse sand and gravel, 15% silt and clay, saturated, very poorly sorted, subangular particles to 1 cm diameter, loose	insufficient sample for PID analysis	
35				Total depth - 31.5 feet		

## PART 1

PAGE 1 OF 1

JOB NO.

7403

BORE HOLE NO.

C-4

PROJECT

Jasco Chemical Corp.

LOCATION

Mountain View, CA

DRILLING CONTRACTOR

ASE Drilling

DRILLING EQUIPMENT

8" Hollow Stem Auger

HYDROGEOLOGIST

Scott Rice

DRILLER

Chris

DATE START/TIME

7/14/90 0800

DATE FINISH/TIME

7/14/90 0930

SURFACE ELEVATION

TOTAL DEPTH

31.5 feet

WELL CASTING

SCREEN TYPE

LENGTH

SLOT

DEPTH	SAMPLE NUMBER	BLOW COUNT PER 6'	RECOVERY	BORE HOLE LOG		
				LITHOLOGIC DESCRIPTION	REMARKS	GRAPHIC LOG
-	-	-	-			
-	B-4-3	3/6/14	2"	CL - sandy clay, black (5Y 2.5/1), 30% poorly sorted sand to 1 mm diameter, moist, moderately plastic, firm, abundant plant rootlets	no odor PID (sample) - 0.0	
5-	B-4-5	5/7/8	12"	CL - sandy clay, very dark gray (5Y 3/1), 30% poorly sorted sand to 2 mm diameter, moist, subangular, not plastic, friable	no odor PID (sample) - 0.0	
-	-	-	-			
10-	B-4-10	5/9/16	18"	CL - sandy clay, very dark gray (5Y 3/1), 30% poorly sorted sand to 2 mm diameter, moist, subangular, not plastic, friable, mottled with coarse sand	no odor PID (sample) - 0.0	
-	-	-	-	ML - silty fine sand, grayish brown (2.5Y 5/2), 20% silt, 30% medium to coarse sand, poorly sorted, particles to 4 mm diameter		
15-	B-4-15	4/5/6	18"	SW - coarse sand and gravel, olive brown (2.5Y 4/4), 10-15% gravel, 10-15% silt, moist, very poorly sorted, subrounded particles to 1 cm diameter	no odor PID (sample) - 0.0	
-	-	-	-	ML - fine sandy silt and silty fine sand, olive brown (2.5Y 4/4), 15-20% medium to coarse sand, moist, low plasticity, firm, poorly sorted, particles to 3 mm diameter		
20-	B-4-20	6/7/13	18"	SC - clayey sand, olive (5Y 5/3), 40% clay, moist, very poorly sorted, subrounded particles to 1 cm diameter, moderately firm, low plasticity, abundant plant rootlets, pockets of coarse sand	no odor PID (sample) - 0.2	
-	-	-	-			
25-	B-4-25	4/8/11	18"	SW - sand and gravel, 20% clay and silt, very poorly sorted, loose, particles to 1 cm diameter CL - sandy clay, dark gray (5Y 4/1), 25% sand, moist, firm, not plastic, particles to 2 mm diameter SM/SC - sandy silt and clay, bluish gray, 30% medium sand to 0.5 mm diameter, moist, low plasticity, firm, abundant iron oxidized plant rootlets	no odor PID (sample) - 0.2	
-	-	-	-			
30-	B-4-30	7/8/7	18"	ML - sandy silt, dark olive gray (5Y 3/2), 30-40% medium sand, moist, low plasticity, subangular SW - coarse sand and gravel, bluish gray, 15% silt and clay, wet to saturated, very poorly sorted, subangular particles to 1 cm diameter, loose	no odor PID (sample) - 0.0	
-	-	-	-	Total depth 31.5 feet		
35-	-	-	-			

## PART 1

PAGE 1 OF 1


JOB NO. 7403


BORE HOLE NO. C-5

PROJECT	Jasco Chemical Corp.		LOCATION	Mountain View, CA	
DRILLING CONTRACTOR	ASE Drilling		DRILLING EQUIPMENT	8" Hollow Stem Auger	
HYDROGEOLOGIST	Scott Rice		DRILLER	Chris	
DATE START/TIME	7/14/90 1115	DATE FINISH/TIME	7/14/90 1300	SURFACE ELEVATION	TOTAL DEPTH
WELL CASING		SCREEN TYPE		LENGTH	31.5 feet
					SLOT

DEPTH	SAMPLE NUMBER	BLOW COUNT PER 6'	RECOVERY	BORE HOLE LOG		
				LITHOLOGIC DESCRIPTION	REMARKS	GRAPHIC LOG
-	-	-	-			
-	B-5-3	NA	11"	SC - clayey sand, dark grayish brown (2.5Y 4/2), 40% clay, moist, poorly sorted, subrounded particles to 1 mm diameter, firm, not plastic	no odor PID (sample) - 0.6	
5	B-5-5	4/6/9	15"	SC - sandy and silty clay, dark grayish brown (2.5Y 4/2), 30% fine to medium sand and silt, moderately plastic	no odor PID (sample) - 0.6	
-	-	-	-			
10	B-5-10	6/8/7	15"	SC - clayey sand, olive gray (5Y 4/2), 20-25% clay, slightly moist, poorly sorted, subangular particles to 2 mm diameter, not plastic, friable  grades coarser to gravels up to 5 cm diameter	no odor PID (sample) - 0.0	
-	-	-	-			
15	B-5-15	9/9/9	18"	SW - coarse sand and gravel, dark brown (10YR 3/3), trace silt, moist, very poorly sorted, subrounded particles to 4 cm diameter, loose  cuttings grade finer	no odor PID (sample) - 0.0	
-	-	-	-			
20	B-5-20	5/27/50	14"	SM - silty sand and gravel, dark grayish brown (2.5Y 4/2), 20% silt, 30% gravel to 1 cm diameter, moist, very poorly sorted, subrounded, friable, predominantly quartz gravels	no odor PID (sample) - 0.1	
-	-	-	-			
25	B-5-25	3/4/6	18"	CL - sandy and silty clay, blue-gray, 20% sand, 30% silt, moist, moderate plasticity, firm, abundant decaying plant rootlets	no odor PID (sample) - 0.2	
-	-	-	-			
30	B-5-30	6/20/16	18"	CL - sandy and silty clay, blue-gray, moist to wet, moderate plasticity SC - sandy clay, wet, 30% clay, 40% gravel to 2 cm diameter, poorly sorted, loose  Total depth - 31.5 feet	no odor PID (sample) - 0.8 groundwater encountered at 31.5 feet	
-	-	-	-			
35						

**APPENDIX C**  
**MONITOR WELL CONSTRUCTION DIAGRAMS**


PLATE 3  
V-1 WELL CONSTRUCTION DETAILSDEPTH  
(ft.)



Questa Engineering Corp.  
Point Richmond, Calif.

V#2 WELL  
CONSTRUCTION DETAILS


Fig.  
2



Questa Engineering Corp.  
Point Richmond, Calif.

V #3 WELL  
CONSTRUCTION DETAILS


Fig.  
2



Note: Well construction as shown is based upon data presented in original consultant's technical report.

OHM CORP.

WELL COMPLETION DIAGRAM  
MONITOR WELL V-4  
JASCO CHEMICAL CORPORATION  
MOUNTAIN VIEW, CA




Note: Well construction as shown is based upon data presented in original consultant's technical report.



OHM CORP.

WELL COMPLETION DIAGRAM  
MONITOR WELL V-5  
JASCO CHEMICAL CORPORATION  
MOUNTAIN VIEW, CA




Note: Well construction as shown is based upon data presented in original consultant's technical report.




OHM CORP.

WELL COMPLETION DIAGRAM  
MONITOR WELL V-6  
JASCO CHEMICAL CORPORATION  
MOUNTAIN VIEW, CA



TOP OF STEEL WELL HOUSING  
ELEVATION 57.50 FEET  
GROUND SURFACE ELEVATION:  
55.90 FEET



NOT TO SCALE

Walker  
Associates


JASCO CHEMICAL CORPORATION  
PHASE II A HYDROGEOLOGIC INVESTIGATION

PALO ALTO • CALIFORNIA

WELL COMPLETION DIAGRAM OF Y-8

PROJECT NO.	DATE	FIGURE NO.
JCO-104H	MARCH 1988	3

TOP OF STEEL WELL HOUSING  
ELEVATION 56.69 FEET  
GROUND SURFACE ELEVATION  
55.0 FEET



NOT TO SCALE

Walter  
Associates

JASCO CHEMICAL CORPORATION  
PHASE II A HYDROGEOLOGIC INVESTIGATION  
PALO ALTO • CALIFORNIA

WELL COMPLETION DIAGRAM OF Y-9

PROJECT NO.

DATE


FIGURE NO.

JCD-104H


MARCH 1988

4

TOP OF STEEL WELL HOUSING  
ELEVATION 59.03 FEET  
GROUND SURFACE ELEVATION  
59.30 FEET





NOT TO SCALE



OHM CORP.

WELL COMPLETION DIAGRAM  
MONITOR WELL V-11  
JASCO CHEMICAL CORPORATION  
MOUNTAIN VIEW, CA





Note: Well construction as shown is based upon data presented in original consultant's technical report.



OHM CORP.


WELL COMPLETION DIAGRAM  
MONITOR WELL I-1  
JASCO CHEMICAL CORPORATION  
MOUNTAIN VIEW, CA

TOP OF STEEL WELL HOUSING

ELEVATION 57.88 FEET

GROUND SURFACE ELEVATION

58.80 FEET.



NOT TO SCALE

Wahler  
Associates

JASCO CHEMICAL CORPORATION  
PHASE II HYDROGEOLOGIC INVESTIGATION


PALO ALTO • CALIFORNIA

WELL COMPLETION DIAGRAM OF  
I-2

PROJECT NO.	DATE	FIGURE NO.
JCO-104H	OCTOBER 1987	4

TOP OF STEEL WELL HOUSING  
ELEVATION 57.29 FEET.

GROUND SURFACE ELEVATION:  
58.30 FEET.



NOT TO SCALE

**W** Wahler  
Associates

JASCO CHEMICAL CORPORATION  
PHASE II HYDROGEOLOGIC INVESTIGATION

PALO ALTO • CALIFORNIA

WELL COMPLETION DIAGRAM OF  
I-3

PROJECT NO.	DATE	FIGURE NO.
JCD-104H	OCTOBER 1987	3

**APPENDIX D**

**LABORATORY INVESTIGATION OF  
ENGINEERING PROPERTIES OF SOIL**

APPENDIX B  
LABORATORY INVESTIGATION

A. INTRODUCTION

This appendix includes a discussion of the procedures followed during the laboratory testing performed on soil samples from wells I-2 and I-3. The investigation program was carried out employing, in most cases, currently accepted test procedures of the American Society of Testing and Materials (ASTM).

Undisturbed thin wall tube samples used in the laboratory investigation were obtained during the course of the field investigation as described in the Well Construction Section of this report. Identification of each sample is by hole number, sample number, and depth.

B. INDEX PROPERTIES TESTING

In the field of soil mechanics, it is advantageous to have a standard method of identifying soils and classifying them into categories or groups that have similar or distinct engineering properties. The most commonly used method of identifying and classifying soils according to their engineering properties is the Unified Soil Classification System (USCS), as described by ASTM D2487-83. The USCS is based on a recognition of the various types and significant distribution of soil characteristics, and plasticity of materials.

The index properties tests discussed in this report include the determination of natural and as-tested water content and dry density, vertical permeability, grain-size distribution, and Atterberg limits.

1. Natural Water Content and Dry Density

Natural water content and dry density were determined, usually in conjunction with other tests, on selected undisturbed tube samples. The samples



Wahler Associates

Project JCO-104H

B-1

were extruded and visually classified, trimmed to obtain a smooth flat face, and accurately measured to obtain volume and wet weight. The samples were then dried, in accordance with ASTM 2216-80, for a period of 24 hours in an oven maintained at a temperature of 110°C. After drying, the weight of each sample was determined and the moisture content and dry density calculated. All the water content and dry density results are summarized in Table B-1 and are also shown with the various other index and engineering properties test results.

## 2. Grain-Size Distribution

The gradation characteristics of selected samples were determined in accordance with ASTM D422-63 and USBR E-6, except as modified below. The gravelly samples were initially sieved through the 3/4-inch and 1-1/2-inch sieves. Representative samples were obtained and soaked in water until individual soil particles were separated and then washed on the No. 200 mesh sieve. That portion of the material retained on the No. 200 mesh sieve was oven-dried and then mechanically sieved. A hydrometer analysis was performed on a representative portion of the minus No. 200 mesh material of selected samples. The hydrometer test was run in a constant-temperature hydrometer bath using sodium hexametaphosphate as a dispersing agent. The grain-size distribution tests are presented on Figures B-1 and B-2.

## 3. Atterberg Limits

Liquid and plastic limits were determined on selected samples in accordance with ASTM Designation D4318-83. Results of the Atterberg limits tests are summarized on Figure B-3.

## C. ENGINEERING PROPERTIES TESTING

Vertical permeability tests were performed on selected soil samples from wells I-2 and I-3.



### Permeability Tests

The tests were performed in general accordance with the Corps of Engineers Test Method EM-1110-2-1906. Below is a description of the test procedure.

The samples were extruded from the tubes and placed in a special cradle that supported the specimen horizontally while the ends were trimmed to a flat face. After the initial weight and volume measurements were determined, each specimen was placed in a triaxial cell, encased in a latex membrane and sealed to the bottom pedestal and top cap with rubber "O" rings. After securing the triaxial chamber, the cell was filled with water and transported to the saturation bay. The samples were saturated using a combination vacuum-back pressure technique. A small vacuum was applied to de-air the lines and increase the initial saturation without a change in void ratio. A back pressure of 50 psi was then incrementally applied to obtain a sufficient degree of saturation prior to consolidation. In order to determine whether the back pressure applied was causing complete saturation, Skempton's "B" parameter in excess of 0.9 was measured for all samples. After achieving saturation, the samples were consolidated to pressures equivalent to overburden load.

The permeability was determined by applying a constant head hydraulic gradient and monitoring the flow of water from bottom to top of the sample through calibrated constant diameter sight tubes as a function of time. The consolidation pressure and head pressure used for each test appears on the data sheet. The permeability test results, together with the gradation characteristics of the samples tested are presented in Table B-1.



TABLE B-1  
PERMEABILITY TEST RESULTS

Hole No.	Sample No.	Depth, ft.	USCS Classification	Natural		As-Tested		Consolidated Pressure (psi)	Head, (psi)	Coefficient of Permeability cm/sec
				Water Content (%)	Dry Density (pcf)	Water Content (%)	Dry Density (pcf)			
I-2	T-6	13.7-14.2	CH	26.2	92.5	29.5	95.2	11	0.5	$2.4 \times 10^{-4}$ *
I-2	T-13	31.7-32.4	SW-SM	15.1	119.1	15.2	121.1	27	0.5	$2.3 \times 10^{-4}$
I-2	T-15	37.4-37.9	CL	27.5	97.7	25.8	101.5	26	2.0	$3.1 \times 10^{-7}$
I-2	R-10	47.5-48.0	SW-SM	17.4	110.9	17.9	113.5	32	0.5	$2.3 \times 10^{-4}$
I-2	R-15	56.5-57.0	CL	23.0	104.8	20.8	110.5	36	5.0	$2.3 \times 10^{-8}$
I-3	T-6	12.9-13.4	CL	20.0	102.6	23.7	105.1	11	0.5	$2.5 \times 10^{-4}$ *
I-3	T-10	22.7-23.2	SP-SM	14.8	122.7	14.3	124.8	23	1.0	$5.2 \times 10^{-5}$
I-3	T-12	26.2-26.7	CL	25.7	98.5	24.3	101.7	22	2.0	$2.8 \times 10^{-6}$
I-3	R-5	49.0-49.5	SW	13.4	124.7	12.3	128.2	37	0.5	$1.2 \times 10^{-4}$
I-3	R-6	57.0-57.5	SC	21.6	108.4	19.7	112.5	38	2.0	$2.9 \times 10^{-7}$


\*Permeability was influenced by roots and root holes in samples.

Samples were tested in triaxial cells after back pressure saturation and consolidation equal to overburden load. The permeability was determined by applying a constant head hydraulic gradient and monitoring the flow of water from bottom to top of the sample through calibrated constant diameter sight tubes as a function of time..


\*DISPERSING AGENT WAS INEFFECTIVE  
AFTER 7 HOUR READING

**K E Y:**


LL	52	NP	38	NP	42				
PL	20	NP	21	NP	20				
PI	32	0	17	0	22				
NAT. W/OF	27.1	15.1	27.5	17.4	21.4				
SPEC. GRAVITY	---	---	---	---	---				
CLASSIF.SYMB.	CH	SW-SM	CL	SW-SM	CL				
SAMPLE NO.	T-6	T-13	T-15	R-10	R-15				
DEPTH, FT.	13.7-14.2	31.7-32.9	37.4-37.9	47.5-48.0	56.5-57.0				
HOLE NO.	I-2	I-2	I-2	I-2	I-2				



\*DISPERSING AGENT WAS INEFFECTIVE  
AFTER 7 HOUR READING.



### PLASTICITY CHART



### PLASTICITY DATA

KEY SYMBOL	HOLE NUMBER	DEPTH (ft)	NATURAL WATER CONTENT W (%)	PLASTIC LIMIT (%)	LIQUID LIMIT (%)	PLASTICITY INDEX (%)	LIQUIDITY INDEX ( $\frac{W - PL}{LL - PL}$ )	UNIFIED SOIL CLASSIFICATION SYMBOL
○	I-2, T-6	13.7-14.2	27.1	20	52	32	---	CH
●	I-2, T-15	37.4-37.9	27.5	21	38	17	---	CL
◐	I-2, R-15	56.5-57.0	21.4	20	42	22	---	CL
◑	I-3, T-6	12.9-13.4	18.6	19	45	26	---	CL
◑	I-3, T-12	26.2-26.7	24.8	21	37	16	---	CL
●	I-3, R-6	57.0-57.5	20.2	21	32	11	---	SC

 Wahler  
Associates

JASCO CHEMICAL CORPORATION  
PHASE II HYDROGEOLOGIC INVESTIGATION

PALO ALTO • CALIFORNIA

ATTERBERG LIMITS - PLASTICITY DATA

ASTM D4318-84

PROJECT NO.

DATE

FIGURE NO.

JCD-104H

OCTOBER 1987

B-3

**APPENDIX E**  
**AQUIFER TESTING REPORT**

AQUIFER TESTING REPORT  
JASCO CHEMICAL CORPORATION  
MOUNTAIN VIEW, CALIFORNIA

A. INTRODUCTION

1. Purpose

This aquifer testing report has been prepared in response to Provision C.2.c.2 of Cleanup and Abatement Order No. 87-094 issued to Jasco Chemical Corporation (Jasco) by the California Regional Water Quality Control Board (CRWQCB) on August 3, 1987. The objectives of the investigation are as follows:

- a. To determine values of transmissivity, hydraulic conductivity and storativity for the A-aquifer, as well as lateral variability in these properties.
- b. To evaluate whether the A-aquifer at the Jasco facility is a confined aquifer.
- c. To evaluate whether hydraulic connection exists between the A and B<sub>1</sub>-aquifers at and in the vicinity of the Jasco site.
- d. To evaluate the effects of external influences (e.g., barometric pressure) on ground water levels.
- e. To evaluate the effectiveness of well V-4 as an extraction well.

This report presents the methods used during the field investigation, summary of the site hydrogeology, the solution techniques used to analyze the data acquired in the field, analysis of the aquifer testing results, and conclusions based on the data. Appendices containing the field data, analytical solution documentation, and aquifer testing protocols are also included.



Wahler Associates

Project JCO-104H

This report is organized into six sections: (A) an introductory section, (B) a discussion of the site hydrogeology, (c) the pumping test methodology and results, (D) the slug test methodology and results, (E), a conclusions section, and (F) a statement of limitations.

## 2. Site Description

Jasco Chemical Corporation is located at 1710 Villa Street, Mountain View, California (Figure 1). The 2.05-acre Jasco site is bordered on the north by the Southern Pacific Railroad and the Central Expressway and by residential units on the remaining sides. The Jasco site has historically been zoned and used for industrial purposes, but is now zoned residential. Within a one-mile radius of the site, the current land use is a combination of light industrial, commercial and residential. The actual plant location is on the northern portion of the property, leaving approximately 66 percent of the site as vacant land.

The Jasco site is located on a gently sloping alluvial plain which terminates at San Francisco Bay, approximately 2.5 miles north of the site. Permanente Creek, a northward-flowing, concrete-lined and channelized stream is located approximately 600 feet to the west-northwest of the site.

Preliminary investigations of the Jasco site have led to the discovery of a number of volatile organic compounds in the subsurface, primarily chemicals that have been stored at the site by Jasco. While a variety of organic compounds have been detected in the subsurface, the compounds with the highest observed concentrations are: 1,1,1-trichloroethane, 1,1-dichloroethane, and methylene chloride.

## 3. Scope of Work Performed

As part of the work program, slug tests were performed on existing A-aquifer wells V-1 through V-7 and existing B<sub>1</sub>-aquifer wells I-1, 2, and 3. The A-aquifer wells yielded reliable estimates of transmissivity, hydraulic



conductivity, and storativity. The recovery at the  $B_1$ -aquifer wells was too rapid to yield reliable estimates of these parameters. The slug tests were performed on September 27, 1987. On September 28, 1981, a step discharge test was performed at A-aquifer well V-4. The purpose of the step discharge test was to determine the appropriate pumping rate for the 48-hour constant discharge test as well as to determine the well loss coefficient for well V-4. Finally, a 48-hour constant discharge test was performed on September 29, 30, and October 1, 1987. Well V-4 was used as the pumping well. Water level variation was measured in the well V-4, as well as in observation well V-2 using an electronic data logger. Water level variations in the additional monitoring wells were monitored using an electric water level meter.

#### STRATIGRAPHY AND HYDROGEOLOGY

As discussed above, seven A-aquifer monitoring wells have been installed thus far, V-1 through V-7 (Figure 2). Three  $B_1$ -aquifer wells have been installed, I-1, I-2, and I-3 (Figure 2). As part of the Phaes II hydrogeologic investigation conducted earlier, laboratory classification and laboratory vertical permeability testing were performed on soil samples from I-2 and I-3 (Wahler Associates, November, 1987). The results of the classification and laboratory permeability testing will be incorporated into the discussion. The soil types have been classified according to the Unified Soil Classification System which is summarized on Figure 3.

The stratigraphy encountered in the completed borings can be divided into four relatively permeable zones: the Vadose Higher Permeability Zone, the A-aquifer, the  $B_1$ -aquifer, and the  $B_2$ -aquifer, separated by zones of lower permeability including the Vadose Lower Permeability Zone, the A- $B_1$  aquitard, and the  $B_1$ - $B_2$  aquitard. Two representative cross-sections taken from Wahler's report, "Phase II Hydrogeologic Investigation, Jasco Chemical Corporation, November, 1987", showing the above described units are enclosed as Figures 4 and 5.



a. Vadose Lower Permeability Unit - The upper 9 to 18 feet of section encountered in wells V-1 through V-7 and I-1, 2, and 3 consist of clay, and silty, sandy, or gravelly clay. In I-2, a soil sample from approximately 14 feet (I-2,T-6) was classified as a CH with a vertical coefficient of permeability of  $4.7 \times 10^{-4}$  ft/min. A sample from approximately 13 feet in I-3 was classified as a CL, with a vertical coefficient of permeability of  $4.9 \times 10^{-4}$  ft/min. The vertical permeabilities of the clay samples are much higher than one could expect considering their composition. Laboratory analysis revealed that both of the samples contained rootlets and rootlet holes, features which can increase the permeability of a soil sample.

A lower permeability unit consisting of clay to sandy clay is located between the VHPZ (discussed below) and the A-aquifer. In V-7 and I-2, this unit is located within the vadose zone. In I-3, this lower permeability unit is located within the zone of saturation.

b. Vadose Higher Permeability Zone (VHPZ) - The VHPZ ranges in thickness from a few inches in the case of V-7 and I-2 to 14.9 feet as was observed in V-5. In I-3, the VHPZ consists of 7.8 feet of dark, yellow-brown, silty to gravelly sand. The VHPZ appears to thin towards the northeast, as evidenced by the unit being represented by 7.8 feet of gravelly and silty sand in I-3, a 0.9-foot layer of gravelly clay in I-2, and by an increase in gravel content within a clay layer in V-7. This type of deposition pattern is common in an alluvial setting where rapid changes in stratigraphy are observed over short distances, both vertically and laterally.

Properties testing was performed on one VHPZ section sample from I-3 (I-3, T-10). The grain size analysis and vertical permeability testing revealed the soil to be an SP-SM, with a vertical permeability of  $1.0 \times 10^{-4}$  ft/min, which is rather low for sandy material. Even though the VHPZ is composed of predominantly sandy material, the VLPU has a higher coefficient of permeability, induced by rootlets and rootlet holes present in the clay.



c. A-Aquifer - In wells V-1 through V-7 and I-1, the A-aquifer ranges in thickness from 0.5 to 13.5 feet. In V-7, located adjacent to I-2 on the median of the Central Expressway, the A-aquifer is represented by 13.5 feet of alternating layers of sand, gravel, and clay. In I-2, located 8 feet east of V-7, the A-aquifer is represented by 14.7 feet of gravelly sand and silty sand. Soil sample I-2, T-13, identified in the field as an SM, was determined in the laboratory to be an SW-SM with a vertical permeability of  $4.5 \times 10^{-4}$  ft/min. From a comparison of the boring logs of I-2, I-3, and V-7, it is apparent that the thickness of the A-aquifer decreases towards the west on the median of the Central Expressway. At I-3, the equivalent of the A-aquifer is recognized as a change in the color of the soil from dark, greenish-gray to yellow-brown, as well as an increase in the sand content of the clayey material. A sample of the A-aquifer equivalent material in I-3 was not analyzed in the materials testing laboratory, as it was not recognized as aquifer material in the field.

d. A-B<sub>1</sub> Aquitard - The full thickness of the A-B<sub>1</sub> aquitard has been penetrated by B<sub>1</sub>-aquifer wells I-1, 2, and 3. The thickness of the A-B<sub>1</sub> aquitard ranges from 6.5 feet at I-1, to 17 feet at I-2, and finally 14 feet at I-3. The A-B<sub>1</sub> aquitard is composed of clay to sandy clay. Properties testing was performed on two samples of A-B<sub>1</sub> aquitard material. Sample I-2, T-15 was classified as a CL with a vertical permeability of  $6.1 \times 10^{-7}$  ft/min. Sample T-12 from I-3, was also classified as a CL, but had a slightly higher vertical permeability,  $5.5 \times 10^{-6}$  ft/min. Rootlets or rootlet holes were not observed in either of the A-B<sub>1</sub> aquitard samples. The vertical permeability data indicate that the A-B<sub>1</sub> aquitard is of sufficiently low permeability to substantially retard the vertical migration of ground water to deeper aquifers.

e. B<sub>1</sub>-Aquifer - Before the installation of B<sub>1</sub>-aquifer monitoring wells I-2 and I-3, the full thickness of the B<sub>1</sub>-aquifer had been penetrated only at I-1 where it was composed of gravelly sand (SP-GP) and had an observed thickness of 11.2 feet. At I-2, the B<sub>1</sub>-aquifer is composed of 7.5 feet of silty, gravelly, sand, identified in the laboratory as an SW-SM, with a



vertical permeability of  $4.5 \times 10^{-4}$  ft/min. The  $B_1$ -aquifer at I-3 is composed of 9.0 feet of gravelly sand, identified in the laboratory as an SW. The vertical permeability observed at I-3,  $2.4 \times 10^{-4}$  ft/min, is similar to that observed for the  $B_1$ -aquifer at I-2. The vertical permeability values obtained for soil samples from the  $B_1$ -aquifer are similar to the value calculated for the A-aquifer material taken from I-2 ( $4.5 \times 10^{-4}$  ft/min).

f.  $B_1-B_2$  Aquitard - At I-2, five feet of  $B_1-B_2$  aquitard material were penetrated before drilling was terminated at 59.5 feet. Laboratory testing revealed the aquitard material to be a CL (field identified as a sandy clay) with a vertical permeability of  $4.5 \times 10^{-8}$  ft/min. At I-3, a one-foot thick bed of bluish-gray, sandy clay, of the same type as observed in I-2, was found from 56.5 to 57.5 feet. A sample taken from the same sandy clay unit N-I-3 (I-3, R-6) was identified in the laboratory as an SC (clayey sand). Although the sample was identified as an SC, the vertical permeability,  $5.7 \times 10^{-7}$  ft/min, is typical for aquitard material. Although only one foot of aquitard material exists between the  $B_1$  and  $B_2$ -aquifers at I-3, the stratigraphic and permeability data strongly show that first, the same aquitard exists at both locations, and second, the  $B_1-B_2$  aquitard is of low permeability ( $5.7 \times 10^{-7}$  ft/min at I-3 and  $5.5 \times 10^{-8}$  ft/min at I-2). The permeability data indicate that the  $B_1-B_2$  aquitard is of sufficiently low permeability to substantially retard the vertical migration of ground water to deeper aquifers.

g.  $B_2$ -Aquifer - The  $B_2$ -aquifer was penetrated only at I-3. There are no monitoring wells screened within the  $B_1$ -aquifer. During the drilling of I-3, it was observed that the  $B_1$  and  $B_2$  aquifers are very similar in composition, both being composed of dark, yellow-brown gravelly sand. The top of the  $B_2$ -aquifer was penetrated at 57.5 feet. I-3 was terminated at 71.0 feet without reaching the bottom of the  $B_2$ -aquifer. A total of 13.5 feet of  $B_2$ -aquifer material were penetrated.

h. Ground Water Elevations - Maps of both the A and  $B_1$ -aquifer potentiometric surface have been constructed using water level data collected on October 7, 1987 (Figures 6 and 7).



Examination of Figure 6 reveals that at the time the ground water level data were taken, the general direction of ground water flow in the A-aquifer was 30 degrees east of north ( $N30^{\circ}E$ ) and the gradient 0.004 ft/ft. This A-aquifer gradient was used in the calculation of ground water velocities for the A-aquifer. The water level data from wells I-1, I-2, and I-3, indicate that the general flow direction of  $B_1$ -aquifer ground water is  $N15^{\circ}E$ . The  $B_1$ -aquifer ground water gradient is 0.003 ft/ft (Figure 7).

#### PUMPING TESTS

The pumping tests were conducted using A-aquifer monitoring well V-4, a four-inch diameter well installed by WA as part of a ground water investigation being conducted at and in the vicinity of Jasco Chemical Corporation. Two types of pumping tests were performed at well V-4: a step-drawdown test, and a 48-hour constant discharge test (including 12 hours of recovery). Slug tests were performed in all the A-aquifer wells. Attempts were made to carry out slug tests in  $B_1$ -aquifer wells, but the test data collected was unusable due to the rapid recovery of water levels after insertion and withdrawal of the slug. The slug test results will be discussed later in this report.

Well V-4 was chosen as the pumping test location based on existing hydrogeological and ground water quality information. Extraction pumping has been conducted in V-4 since April 1987. Therefore, it was the logical choice for the constant discharge test location. Results from the pumping test in V-4 will indicate the approximate radius of influence due to pumping and hence will aid in determining the effect of extraction pumping on reducing the concentrations of chemicals in the ground water. The step-drawdown test was performed to assess the well loss coefficient and to determine a suitable pumping rate for the constant-discharge test.

The pumping test procedure is described below. Detailed pumping test protocols and a further description of the pumping test procedure may be found in Appendix A.



- o All pumping test equipment was decontaminated and calibrated before being placed down each well.
- o The variation in water level in well V-4 induced during the step-drawdown test were recorded with a pressure transducer/data logger system.
- o A constant-discharge test was conducted after water levels had re-equilibrated following the step-drawdown test. From the step-drawdown test, 2 gpm was found to be a suitable pumping rate for V-4 in order to maintain a suitable water level above the pump. Water level variations in V-4, as well as observation well V-2, were recorded automatically with an electronic data logger system. Water levels in all other wells (A and B<sub>1</sub>-aquifer wells) were measured manually at set time intervals during the test using an electric water level meter.
- o All extracted ground water from well V-4 was discharged to local sanitary sewers in accordance with the permit issued to Jasco by the City of Mountain View.
- o At the end of the constant-discharge test, water levels were monitored until they had recovered to within approximately 90 percent of their original levels.

#### STEP-DRAWDOWN TEST

A two-hour step-drawdown test was carried out in well V-4 on September 28, 1987. An increase in the water level drawdown was observed as the pumping rate was increased, indicating the stability of the well during the test. The test data were analyzed using the Bierschenk method (Driscoll, 1986), which involves plotting the drawdown to discharge ratio versus discharge. The well loss coefficient was determined from the resulting linear curve. From this coefficient, the head loss due to pumping well geometry and construction could be estimated for a specific pumping rate. The test data,



plotted curve and detailed calculations may be found in Appendix B. A pumping rate of approximately 2 gpm was found to be suitable to sustain a desirable water level above the pump.

#### CONSTANT DISCHARGE TEST

A 48-hour constant-discharge test was performed in pumping well V-4, for a duration from September 29, 1987 to October 1, 1987. The pumping portion of the test lasted 36 hours. The recovery period was scheduled to be 12 hours in length, but 90 percent recovery was reached after approximately 4.5 hours.

Water level variations in V-4, the pumping well, as well as in observation well V-2 were recorded by an electric data logger/pressure transducer system. V-2 was chosen as the observation well because it was the closest to V-4 (8 feet away) and should show the largest drawdown due to pumping. Water levels in all other wells were measured periodically throughout the test, using an electric water level meter. Two analysis techniques, the Hantush-Jacob (1955) method for leaky, confined aquifer and the Jacob straight line method (Freeze and Cherry, 1979) were used in calculating the aquifer parameters from the time versus drawdown data collected at well V-2.

A computer program called Graphical Well Analysis Package (GWAP) which incorporated the Hantush-Jacob method was used to obtain estimates of transmissivity, hydraulic conductivity and storativity. The results were compared with those calculated manually using the Jacob straight line method.

After the constant-discharge test, water level recoveries in well V-4 and other wells were monitored for 12 hours until the levels reached approximately 90 percent of their original values. The recovery data was analyzed by hand, using the modified Theis equation (Driscoll, 1986). Data records of V-4 and V-2, plotted data curves, type curves, method assumptions and calculations may be found in Appendix C. The pumping test results are



tabulated in Table 1. The temporal variation in water elevations measured in wells V-1, V-5, V-6, and V-7 are shown on Figure 8. The water elevation variation in V-3 is shown on Figure 9. Figure 10 shows the variation in  $B_1$ -aquifer wells I-1, 2, and 3.

The variation in barometric pressure recorded at San Jose Airport during the pumping test is shown on Figure 11. The data were used to determine if the variation in water levels was positively correlated with the barometric pressure variation. The data indicated very small pressure fluctuation over the test period. The difference between the highest and the lowest pressure was only 0.17 inches of mercury.

Comparison of the water level variation measured in the monitoring wells (Figures 8, 9, and 10) with the barometric pressure data (Figure 11) reveals little positive correlation between the two variables. The minimum barometric pressure reading was observed at hour thirty-one. Theoretically, if barometric pressure were driving the water level variation, the water elevations should have reached a maximum at this time. In fact, water levels in all of the A and  $B_1$ -aquifer wells reached their lowest elevations at hour thirty-six, just before pumping was terminated. In addition, only well V-3 shows significant water level variation during the first 25 hours of pumping, during which time the barometric pressure increases and decreases harmonically. After pumping was stopped, all wells rapidly recovered to their pre-pumping levels. Therefore, it is concluded that the decrease in water levels observed in monitoring wells V-1, V-3 through V-7 and I-1, 2, and 3 were induced by extraction from well V-4. The influence of barometric pressure on water levels, if any, was not significant. All of the A-aquifer monitoring wells monitored during the test lie within the area of influence of well V-4. The steepest drawdown of 2.2 feet at the end of pumping was observed in well V-2, located only 8 feet from V-4 (see Appendix C for drawdown records). The water elevation in well V-3, located directly up-gradient of V-4, was lowered 0.30 feet due to pumping at well V-4 (Figure 9). After pumping was terminated, the water level increased 0.19 feet during the first 3 hours of recovery. Wells V-1, V-5, V-6, and V-7 showed



decreases in water elevation ranging from 0.08 to 0.13 feet (Figure 8). As was observed in well V-3, the other A-aquifer wells quickly recovered to their pre-pumping levels after pumping was terminated.

Drawdown was also observed in  $B_1$ -aquifer wells I-1, 2, and 3. Maximum drawdown was again observed at the 36-hour measurement. The drawdown ranged from 0.10 to 0.14 feet. The observed drawdown in the  $B_1$ -aquifer wells implies that under the stressed conditions created by pumping, there is a degree of interconnection between the A and  $B_1$ -aquifer at and in the vicinity of the Jasco facility.

#### SLUG TESTS

Slug tests were conducted in all A and  $B_1$ -aquifer wells on September 15, 1987 to evaluate the hydraulic conductivity of the aquifer material immediately adjacent to the wells. The data supplied by slug tests were used to compare with the more reliable data produced by the pumping tests. The slug test data were also used to observe the amount of variability in hydraulic conductivity there is in the A-aquifer. The slug tests consisted of lowering a solid slug of known volume into the standing water of each well which induces an instantaneous rise in water level. The decrease in water level with time inside each well was monitored using a pressure transducer/electric data logger system. After the water level had equilibrated with the slug inside well, the slug was withdrawn and the rise in water level was recorded.

The technique for determining the aquifer characteristics from slug test data was adopted from a method derived by Cooper, Bredehoeft, and Papadopules (1967). In this method, changes in water levels are plotted against time to form a curve. The curve is then matched with a type curve for slug tests, and the resulting values are used in calculating the parameters. Instead of analyzing the data manually, the computer program GWAP which incorporated the above method was used. Data records, plotted data curves and slug test type curves may be found in Appendix E. A summary of the test results is presented in Table 2.



The slug tests conducted at the A-aquifer wells yielded reliable results, the B<sub>1</sub>-aquifer wells recovered too quickly to yield reliable data. Estimates of hydraulic conductivity, transmissivity, and storativity were therefore not calculated for the B<sub>1</sub>-quifer wells.

### CONCLUSIONS

The average horizontal hydraulic conductivity of A-aquifer was estimated to be  $7.90 \times 10^{-3}$  ft/min from in-situ pumping tests. The corresponding average velocity is 41.5/yr based on a hydraulic gradient of 0.004 (from Figure 6) and an effective porosity of 0.4 (see Appendix C for calculations). The three methods of analysis were:

1. Hantush-Jacob method for leaky confined aquifers;
2. Jacob Straight-Line method for bounded confined aquifers with short distance between the pumping and observation wells;
3. Jacob Solution for Recovery Data.

The hydraulic conductivity measured by the in-situ pumping test is an average value of a larger aquifer volume surrounding well V-4. This conductivity corresponds to the range for material such as silty sand or clean sand (Freeze and Cherry, 1979), which is the type of material most commonly found within the A-aquifer. The storativity estimate is within the range for confined aquifers (Freeze and Cherry, 1979), indicating that the A-aquifer is confined by the vadose zone.

The hydraulic conductivity and storativity of the A-aquifer in the immediate vicinity of each well were determined using slug tests. There is a large variation in hydraulic conductivity and storativity across the site. The highest conductivity value,  $1.03 \times 10^{-1}$  ft/min, was found at well V-6, with a corresponding seepage velocity of 541.4 ft/yr (see Appendix E for calculations). The lowest hydraulic conductivity was found at well V-5,



with a value of  $6.6 \times 10^{-4}$  ft/min, and a corresponding flow velocity of 3.5 ft/yr. The hydraulic conductivities at the rest of the well locations, V-1, V-2, V-3, V-4, and V-7 are of similar order of magnitude and are comparable with those calculated using the pumping test data from well V-4.

The storativities at all well locations except well V-2, fall into the range for confined aquifers, while that of well V-2 is in the range for unconfined aquifers. The A-aquifer at well V-2 may not be as confined as other locations across the site. Alternatively, the fact that well V-2 is screened through a portion of the vadose zone may account for anomalous low storativity value.

The water levels at all wells during the pumping test were monitored to assess the extent of radius of influence due to pumping at well V-4. All A and  $B_1$ -aquifer wells showed positive drawdown response towards the latter portion of pumping. This indicates that the on and off-site aquifer wells lie within the zone of influence of well V-4. Drawdowns in  $B_1$ -aquifer wells indicate probable hydraulic connection between A and  $B_1$ -aquifers.

#### F. LIMITATIONS

The data, information, interpretations, and conclusions contained within this report are presented specifically and solely for Bronson, Bronson, and McKinnon. The conclusions and professional opinions presented herein were developed by Wahler Associates, in accordance with currently accepted geologic and hydrogeologic principles and practices. Wahler Associates cannot be responsible for any conclusions and recommendations that may be made by others, unless we have been given an opportunity to review such conclusions and concur in writing.



TABLE 1  
CONSTANT DISCHARGE TEST RESULTS OF WELL V-4

<u>Method of Analysis</u>	<u>T</u> (ft <sup>2</sup> /min)	<u>K</u> (ft/min)	<u>S</u> (--)	<u>v</u> (ft/yr)
Hantush-Jacob by GWAP	$6.29 \times 10^{-2}$	$8.98 \times 10^{-3}$	$1.59 \times 10^{-3}$	47.2
Jacob Straight-Line Method	$6.04 \times 10^{-2}$	$8.63 \times 10^{-3}$	$1.44 \times 10^{-3}$	45.4
Theis Solution for Recovery Data	$4.26 \times 10^{-2}$	$6.09 \times 10^{-3}$ Average: $7.90 \times 10^{-3}$	*	<u>32.0</u> Average: 41.5

Note:

T - Transmissivity

K - Hydraulic Conductivity

S - Storativity (dimensionless)

v - seepage velocity

\* - residual-drawdown plot cannot be used for determining storativity (Driscoll, 1986).



Wahler Associates

Project JCO-104H

TABLE 2  
A-AQUIFER WELLS SLUG TEST RESULTS

<u>Well No.</u>	<u>Aquifer Thickness (ft)</u>	<u>T (ft<sup>2</sup>/min)</u>	<u>K (ft/min)</u>	<u>S (--)</u>	<u>v (ft/yr)</u>
V-1	22.0	$6.11 \times 10^{-2}$ 5	$2.78 \times 10^{-3}$ 5	$5.88 \times 10^{-10}$ 6	14.6 5
V-2	12.0	$6.95 \times 10^{-2}$ 4	$5.79 \times 10^{-3}$ 4	$3.67 \times 10^{-2}$ 1	30.4 4
V-3	12.0	$2.98 \times 10^{-2}$ 6	$2.48 \times 10^{-3}$ 6	$4.77 \times 10^{-5}$ 3	13.0 6
V-4	7.0	$1.05 \times 10^{-1}$ 3	$1.50 \times 10^{-2}$ 2	$1.64 \times 10^{-3}$ 2	78.8 2
V-5	3.0	$1.98 \times 10^{-3}$ 7	$6.60 \times 10^{-4}$ 7	$5.88 \times 10^{-6}$ 4	3.5 7
V-6	7.0	$7.18 \times 10^{-1}$ 1	$1.03 \times 10^{-1}$ 1	$5.88 \times 10^{-9}$ 5	541.4 1
V-7	13.5	$1.80 \times 10^{-1}$ 7	$1.33 \times 10^{-2}$ 3	$5.88 \times 10^{-6}$ 4	70.0 3

Note:

T - Transmissivity

K - Hydraulic conductivity

S - Storativity (dimensionless)

v - seepage velocity



Wahler Associates

Project JCO-104H


REFERENCES

- Cooper, H.H., Jr., Bredehoeft, J.D., and Papadopoulos, I.S.; (1967), Response of a Finite-Diameter Well to An instantaneous Charge of Water. Water Resources Res., 3, pp. 263-269.
- Driscoll, F.G; (1986), Ground Water and Wells, Johnson Division, Minnesota.
- Freeze A., and Cherry, J.A.; (1979), Ground Water, Prentice Hall.
- Hantush, M.S., and Jacob, C.E.; (1955), Nonsteady Radial Flow in an Infinite Leaky Aquifer, Trans. Amer. Geophys. Union, 36, pp. 95-100.
- Wahler Associates; (1987), Phase II Hydrogeologic Investigation, Jasco Chemical Corporation, Mountain View, California, November, 1987.



Wahler Associates

Project JCO-104H



**Wahler  
Associates**

JASCO CHEMICAL CORPORATION  
AQUIFER - TESTING REPORT

**LOCATION OF STUDY AREA  
(AREA SHOWN IN FIGURE 2)**



PALO ALTO • CALIFORNIA

PALO ALTO • CALIFORNIA 100-104H DECEMBER 1987

PALO ALTO • CALIFORNIA 1CO-104H DECEMBER 1987

EXPLANATION

- ◎ A - AQUIFER MONITORING WELL  
△ B<sub>1</sub> - AQUIFER MONITORING WELL



 Walker  
Associates

JASCO CHEMICAL CORPORATION  
AQUIFER - TESTING REPORT

PALO ALTO • CALIFORNIA

A AND B<sub>1</sub> AQUIFER MONITORING WELLS AND  
GEOLOGIC CROSS SECTIONS

PROJECT NO.	DATE	FIGURE NO.
JCO-104H	DECEMBER 1987	2

**UNIFIED SOIL CLASSIFICATION SYSTEM (ASTM D-2487)**

PRIMARY DIVISIONS <sup>1</sup>			GROUP SYMBOL	SECONDARY DIVISIONS
COARSE GRAINED SOILS MORE THAN HALF OF MATERIAL IS LARGER THAN #200 SIEVE SIZE	GRAVELS MORE THAN HALF OF COARSE FRACTION IS SMALLER THAN #4 SIEVE	CLEAN GRAVELS (LESS THAN 5% FINES)	GW	WELL GRADED GRAVELS, GRAVEL-SAND MIXTURES, LITTLE OR NO FINES.
		POORLY GRADED GRAVELS OR GRAVEL-SAND MIXTURES, LITTLE OR NO FINES.	GP	
		GRAVEL WITH FINES	GM	SILTY GRAVELS, GRAVEL-SAND-SILT MIXTURE, NON PLASTIC FINES.
		CLEAN SANDS (LESS THAN 5% FINES)	GC	CLAYEY GRAVELS, GRAVEL-SAND-CLAY MIXTURES, PLASTIC FINES.
		POORLY GRADED SANDS OR GRAVELLY SANDS, LITTLE OR NO FINES.	SW	
	SANDS MORE THAN HALF OF COARSE FRACTION IS SMALLER THAN #4 SIEVE	SANDS WITH FINES	SP	
		SILTY SANDS, SAND-SILT MIXTURES, NON-PLASTIC FINES.	SM	
		CLAYEY SANDS, SAND-CLAY MIXTURES, PLASTIC FINES.	SC	
		INORGANIC SILTS AND VERY FINE SANDS, ROCK FLOUR, SILTY OR CLAYEY FINE SANDS OR CLAYEY SILTS WITH SLIGHT PLASTICITY.	ML	
		INORGANIC CLAYS OF LOW TO MEDIUM PLASTICITY, GRAVELLY CLAYS, SANDY CLAYS, SILTY CLAYS, LEAN CLAYS.	CL	
FINE GRAINED SOILS MORE THAN HALF OF MATERIAL IS SMALLER THAN #200 SIEVE SIZE	CLAYS LIQUID LIMIT IS LESS THAN 50	ORGANIC SILTS AND ORGANIC SILTY CLAYS OF LOW PLASTICITY.	OL	
		INORGANIC SILTS, MICACEOUS OR DIATOMACEOUS FINE SANDY OR SILTY SOILS, ELASTIC SILTS.	MH	
		INORGANIC CLAYS OF HIGH PLASTICITY, FAT CLAYS.	CH	
		ORGANIC CLAYS OF MEDIUM TO HIGH PLASTICITY, ORGANIC SILTS.	OH	
		PEAT AND OTHER HIGHLY ORGANIC SOILS.	PT	
	HIGHLY ORGANIC SOILS			

**DEFINITION OF TERMS**

**GRAIN SIZES**

U.S. STANDARD SERIES SIEVE

200	50	16	4	3/4"	3"	6"
-----	----	----	---	------	----	----

SILTS & CLAYS DISTINGUISHED ON BASIS OF PLASTICITY	SAND		GRAVEL		COBBLES	BOULDERS
	FINE	MEDIUM	COARSE	FINE		

MOISTURE CONDITION (INCREASING MOISTURE →)

DRY	SLIGHTLY DAMP	DAMP (PL)	MOIST	VERY MOIST	WET (SATURATED) (LL)
-----	---------------	-----------	-------	------------	----------------------

**KEY**

SAMPLE NUMBER	MODE	RECOVERY	PENETRATION RESISTANCE (PR) (RECORDED AS BLOWS/0.5 FOOT)
SAMPLE CONTAINER:	METHOD OF ADVANCING HOLE:	RECOVERY RATIO INDICATED BY A FRACTION:	SANDS & GRAVELS
BAG..... B	DRILL	1.2 = FOOTAGE RECOVERED 1.5 = FOOTAGE SAMPLED	RELATIVE DENSITY      BLOWS/FOOT*
JAR..... J	FLIGHT AUGER..... AD		VERY LOOSE      0-4
SHELBY TUBE... S	BUCKET AUGER..... BA		LOOSE      4-10
DRIVE SAMPLER	SPIN AUGER..... SD		MEDIUM DENSE      10-30
RINGS..... R	HOLLOW STEM AUGER... HA		DENSE      30-50
	ROTARY DRILL..... RD		VERY DENSE      OVER 50
	CABLE TOOL..... CT	REMARKS	CLAYS & SILTS
	SAMPLER	INCLUDES DRILLING INFORMATION, E.G. WATER LEVEL, DATES.	CONSISTENCY      BLOWS/FOOT*      STRENGTH†
	DRIVE..... DR	REFUSAL: STOPPED BY MATERIAL TOO HARD FOR EQUIPMENT.	VERY SOFT      0-2      0-½
	PITCHER BARREL.... PB	TERMINATED: SUFFICIENT INFORMATION OBTAINED.	SOFT      2-4      ½-1
	CORE..... C	ABANDONED: STOPPED BECAUSE OF DIFFICULTIES EXPLAINED ON LOG.	FIRM      4-8      ½-1
	PUSH..... P		STIFF      8-15      1-2
			VERY STIFF      15-30      2-4
			HARD      OVER 30      OVER 4

\* Number of blows of 140 pound hammer falling 30 inches to drive a 2 inch O.D. (1-3/8 inch I.D.) Split-Barrel sampler (ASTM-1586 standard penetration test).


† Unconfined compressive strength in tons/sq ft. Read from a pocket penetrometer.

 Wahler  
Associates

JASCO CHEMICAL CORPORATION  
AQUIFER - TESTING REPORT

**KEY FOR  
SOIL EXPLORATION LOGS**

PROJECT NO.	FIGURE NO.
JCB-104M	3




JASCO CHEMICAL CORPORATION  
AQUIFER - TESTING REPORT

PALO ALTO • CALIFORNIA

GEOLOGIC CROSS SECTION A-A'

PROJECT NO.	DATE	FIGURE NO.
SCB-104K	DECEMBER 1987	4



**W** Wahrler  
Associates

JASCO CHEMICAL CORPORATION  
AQUIFER-TESTING REPORT

PALO ALTO • CALIFORNIA

GEOLOGIC CROSS SECTION D-D'

PROJECT NO.	DATE	FIGURE NO.
JCO-104H	DECEMBER 1987	5

EXPLANATION

◎ A-AQUIFER MONITORING WELL



V-7

◎ 33.54

CENTRAL EXPRESSWAY

33.8 33.6 33.4

V-8

◎ 33.85

33.8 34.0

SOUTHERN PACIFIC RAILROAD

34.2 34.11 ◎ 34.07 V-4

34.0 34.14

V-5

34.2

34.4

V-3

34.4

34.50 ◎ 34.58



V-1

34.58

GRADIENT = 0.004

DIRECTION OF GROUNDWATER  
FLOW = N30° E

JASCO CHEMICAL CORPORATION



Wahrler  
Associates

JASCO CHEMICAL CORPORATION  
AQUIFER - TESTING REPORT


PALO ALTO • CALIFORNIA

POTENSIOMETRIC SURFACE A-AQUIFER  
OCTOBER 7, 1987

PROJECT NO.	DATE	FIGURE NO.
JCO-104H	DECEMBER 1987	8

EXPLANATION

$\triangle$  B<sub>1</sub> - AQUIFER MONITORING WELL



I-3  $\triangle$  33.52      I-2 33.60  
33.6

SOUTHERN PACIFIC RAILROAD


33.8



GRADIENT = 0.003

DIRECTION OF GROUNDWATER  
FLOW = N15°E

JASCO CHEMICAL CORPORATION



Wahler  
Associates


JASCO CHEMICAL CORPORATION  
AQUIFER - TESTING REPORT

PALO ALTO • CALIFORNIA

POTENTIOMETRIC SURFACE - B<sub>1</sub>, AQUIFER  
OCTOBER 7, 1987

PROJECT NO.	DATE	FIGURE NO.
JCO-104M	DECEMBER 1987	7

## TEMPORAL VARIATION IN GW ELEVATION



**W** Wahrler  
Associates


JASCO CHEMICAL CORPORATION  
AQUIFER-TESTING REPORT

PALO ALTO • CALIFORNIA

TEMPORAL VARIATIONS IN WATER LEVELS  
WELLS Y-1, Y-5, Y-8, Y-7

PROJECT NO.	DATE	FIGURE NO.
JCO-104H	DECEMBER 1987	8

## TEMPORAL VARIATION IN GW ELEVATION



**W** Walker  
Associates

JASCO CHEMICAL CORPORATION  
AQUIFER - TESTING REPORT

PALO ALTO • CALIFORNIA

TEMPORAL VARIATION IN WATER LEVEL  
WELL V-3

PROJECT NO.

DATE


FIGURE NO.

JCO-104H

DECEMBER 1987

9

## TEMPORAL VARIATION IN GW ELEVATION



Walter  
Associates

JASCO CHEMICAL CORPORATION  
AQUIFER-TESTING REPORT


PALO ALTO • CALIFORNIA

TEMPORAL VARIATIONS IN WATER LEVELS  
WELLS I-1, I-2, I-3

PROJECT NO.	DATE	FIGURE NO.
JCO-104H	DECEMBER 1987	10

## BAROMETRIC READINGS—SAN JOSE AIRPORT

11:00AM, 9/29/87 TO 10/1/87



Walter  
Associates

JASCO CHEMICAL CORPORATION  
AQUIFER-TESTING REPORT

PALO ALTO • CALIFORNIA

BAROMETRIC PRESSURE READINGS AT  
SAN JOSE INTERNATIONAL AIRPORT

PROJECT NO.	DATE	FIGURE NO.
JCB-104H	DECEMBER 1987	11

**APPENDIX A**

APPENDIX A  
PUMPING AND SLUG TEST PROTOCOL

A. FIELD PROCEDURE

1. Slug Tests

Slug tests were performed in wells V-1 through V-7 and wells I-1, 2, and 3. This method was used because it provides a simple method of determining values of hydraulic conductivity and transmissivity for the aquifer material in the immediate vicinity of the well screen. The hydraulic conductivity data were also used to determine the degree of spatial variability in hydraulic conductivity possessed by the A-aquifer.

On September 28, 1987, a representative of Wahler Associates visited the Jasco site and conducted slug tests on ground water monitoring wells V-1 through V-7 and I-1, 2, and 3. The slug test consisted of lowering a solid "slug" of known volume into the standing water of each monitoring well which induced a rise in the water level. An electronic data logging device manufactured by Envirolabs of Glendale, California, was simultaneously used to record the decrease in water levels with time. In addition, a reverse slug test was conducted, when possible, by withdrawing the solid "slug" and recording the increase in water level with time. The rate at which the water level rises or falls is controlled by the permeability of the materials in which the monitoring well is screened.

Calculation methods used to determine values of permeabilities from slug tests are found in Appendix E. The QA protocol for the slug tests is outlined below.

2. Pumping

Procedures and equipment used for performing the step discharge and constant discharge pumping tests are described below. Eight episodes of water levels



Wahler Associates

Project JCO-104H

A-1

were measured six days before the step discharge test to determine the amount of temporal variation in water levels that occurs over an eight-hour period. In addition, water levels were measured immediately prior to pumping, both before and after the pumping equipment was placed into the well. At the start of pumping, water levels measurement were made at exponentially expanded intervals, beginning with five second intervals. Water levels were measured in V-4, the pumping well, as well as in well V-2, during the constant discharge test using an Envirolabs electric data logger and a calibrated pressure transducer. Well V-2 was chosen as the most closely monitored observation well due to its proximity to well V-4. Well V-2 is located just eight feet west of well V-4. Proximity was the key issue because a steep cone of depression was anticipated.

Water level measurements were taken periodically from wells V-1, V-4 through V-7 and I-1, 2, and 3 using an electric water level meter. Water level measurements were not taken as frequently from wells V-7, I-2, and I-3 compared to other wells, due to problems with gaining access to the Central Expressway at night as well as for safety reasons.

All pumping tests were conducted using a Grunfus-stainless steel submersible pump. Discharged volume was measured using an in-line flow meter. The flow meter was field checked periodically during the test by calculating the time it took to fill a bucket of known volume. No problems with the pump or flow meter were observed during the test. Extracted ground water was transferred away from the well site using a two-inch flexible hose to the sanitary sewer correction at the Jasco facility. The long-term constant discharge consisted of a 36-hour pumping period followed by a recovery period. Twelve hours of recovery were planned prior to carrying out the test. In the field, it was determined that at least 90 percent recovery had occurred after only approximately 4.5 hours. Monitoring of wells V-2 and V-4 using the data logger was discontinued at that time. A final set of water level measurements were taken 48 hours after pumping began to document the final set of recovery data.



### 3. Quality Assurance Protocol

The following set of quality assurance guidelines were followed during the slug and pumping tests:

- o Horizontal and vertical control for the pumping well and observation wells was established by a licensed surveyor to provide a reliable basis for water level measurements and pumping test calculations.
- o The performance of the pump, generator and flow meter was monitored periodically throughout the pumping test to verify the quality of measurements as well as the continuity of the test.
- o All equipment was thoroughly steam-cleaned and then rinsed with clean tap water prior to being lowered down the hole.
- o A representative of Wahler Associates was on-site at all times during the test to verify the reliability of the data, as well as to make sure the equipment did not malfunction.



**APPENDIX B**

**Step Discharge Test: V-4**

9-28-87

$Q=1.2 \text{ gpm}, 2.81 \text{ gpm}, 2.69 \text{ gpm}, 2.16 \text{ gpm}, 2.07 \text{ gpm}, 6.08 \text{ gpm}, 4.56 \text{ gpm}$

Time	ch	H (ft)
15:53	HRS 7	9.37
15:52	HRS 7	9.22
15:51	HRS 7	9.02
15:50	HRS 7	8.78
15:49	HRS 7	7.88
15:48	HRS 7	7.87
15:47	HRS 7	6.95
15:46	HRS 7	6.80
15:45	HRS 7	6.57
15:44	HRS 7	6.17
15:43	HRS 7	5.17
15:42	HRS 7	3.28
15:41	HRS 7	2.25
15:40	HRS 7	2.42
15:39	HRS 7	2.55
15:38	HRS 7	2.62
15:37	HRS 7	2.58
15:36	HRS 7	1.82
15:35	HRS 7	2.98
15:34	HRS 7	7.85
15:33	HRS 7	7.85
15:32	HRS 7	7.82
15:31	HRS 7	7.82
15:30	HRS 7	7.82
15:29	HRS 7	7.82
15:28	HRS 7	7.82
15:27	HRS 7	7.82
15:26	HRS 7	7.88
15:25	HRS 7	7.88
15:24	HRS 7	7.88
15:23	HRS 7	7.77
15:22	HRS 7	7.77
15:21	HRS 7	7.77
15:20	HRS 7	7.75
15:19	HRS 7	7.72
15:18	HRS 7	7.70
15:17	HRS 7	7.65
15:16	HRS 7	7.57
15:15	HRS 7	7.15
15:14	HRS 7	7.17
15:13	HRS 7	7.12
15:12	HRS 7	7.12
15:11	HRS 7	7.12
15:10	HRS 7	7.15
15:09	HRS 7	7.15
15:08	HRS 7	7.15
15:07	HRS 7	7.17
15:06	HRS 7	7.22
15:05	HRS 7	7.20
15:04	HRS 7	7.20
15:03	HRS 7	7.22
15:02	HRS 7	7.22
15:01	HRS 7	7.25
15:00	HRS 7	7.25
14:59	HRS 7	7.27
14:58	HRS 7	7.27
14:57	HRS 7	7.30
14:56	HRS 7	7.30
14:55	HRS 7	7.32
14:54	HRS 7	7.32
14:53	HRS 7	7.35

Begin test

**W** Wahler  
Associates

**STEP DRAWDOWN TEST**  
WELL PUMPING/TESTING DATA SHEET

Page 1 of 2

JOB NO. : JCO-10411 WELL NO. : V-4 DATE: 9-28-07 PUMPED/TESTED BY: RGB/C

WELL DIA.: 4" Pumping Method: Grönfors Submersible Weather: Sunny + warm

REFERENCE POINT: Pressure Transducer REFERENCE ELEVATION: —

INITIAL DEPTH TO WATER: — INITIAL DEPTH OF OPEN WELL: —  
INITIAL HEIGHT OF WATER COLUMN IN WELL: —

VOLUME OF 1 CASING FULL OF WATER: — CU. FEET  
( $\pi \times R^2 \times H$ ), IN FT<sup>3</sup> —  $\times 7.479 =$  — GAL.

CLOCK TIME	STEP number	VOLUME PUMPED per Q-estimate (gallons)	DEPTH OF WATER ABOVE PROBE (ft)	Q (gpm)	mercer reading (ft <sup>3</sup> )
1347.23	1	0	10.82	—	12087.45
1406.42	1	5	9.57	—	12088.27
1410.35	1	10	9.57	1.2	12089.57
—	SAME Q	—	—	—	—
1416.45	1A	0	9.57	—	12089.97
1420.31	1A	5	9.52	1.19	12090.57
1422.45	△ Q	—	9.52	—	12090.93
1424.00	2	0	8.47	—	12091.44
1425.46	2	5	8.22	2.81	12092.10
1426.12	2	—	8.07	—	—
1456.20	2	—	7.30	—	—
1456.30	△ Q	—	—	—	—
1457.00	3	0	7.27	—	12103.24
1500.00	3	8	7.22	2.69	12104.32
1504.30	3	—	7.20	—	12106.44
1509.30	3A	0	7.15	—	12107.72
1512.30	3A	8	7.12	2.71	12108.79
—	△ Q	—	—	—	—
1516.30	4	0	7.65	—	12110.06
1519.30	4	6.5	7.77	2.16	12110.93

NO. OF CASINGS FULL PUMPED: —

Depth Sampled: —

SAMPLES TAKEN: —

PRESERVATIVE: —

○ - water level is static

**W** Wahler  
Associates

**STEP DRAWDOWN TEST**  
WELL PUMPING/TESTING DATA SHEET

Page 2 of 2

JOB NO. : JCO-104H WELL NO. : U-4 DATE: 8-28-87 PUMPED/TESTED BY: RGS/D

WELL DIA.: 4" Pumping Method: Grimus Submersible Weather: Sunny & warm

REFERENCE POINT: Pressure Transducer REFERENCE ELEVATION: —

INITIAL DEPTH TO WATER: — INITIAL DEPTH OF OPEN WELL: —

INITIAL HEIGHT OF WATER COLUMN IN WELL: —

VOLUME OF 1 CASING FULL OF WATER: — CU. FEET  
( $\pi \times R^2 \times H$ ), IN FT<sup>3</sup> —  $\times 7.479 =$  — GAL.

CLOCK TIME	Step number	Volume pumped per Q-estimate (gallons)	Depth of water above Probe (ft)	Q (gpm)	Meter reading (ft <sup>3</sup> )
1527.00	5	0	7.82	—	12112.96
1530.00	5	6.2	7.82	2.07	12113.79
1530.30	5	—	7.82	—	12114.75
—	ΔQ	—	—	—	—
1537.30	6	0	7.72	—	12118.23
1540.30	6	18.25	2.51	6.08	12120.67
—	ΔQ	—	—	—	—
1543.15	7	0	6.82	—	12121.04
1546.15	7	13.7	6.90	4.56	12122.87

Conclusion:

PUMP QT 2.0 - 2.2 gpm

During Constant Discharge  
test

NO. OF CASINGS FULL PUMPED: —

Depth Sampled: —

SAMPLES TAKEN: —

PRESERVATIVE: —



Wahler Associates

## CALCULATION SHEET

SHEET 1 OF 2 SHEETSPROJECT Jasco Chemical CorporationPROJECT NO. JCO-104 HSUBJECT Step - Drawdown TestFILE 9/28/87  
DATE 9/28/87CALCULATED BY D.S. CHECKED BY A.C.

## Step - Drawdown Test

Jacob Solution (1946):

$$S = \frac{\text{Av. head loss}}{BQ} + \frac{\text{Well head loss}}{CQ^2}$$

S - drawdown in well, ft

Q - discharge rate,  $\text{ft}^3/\text{min}$ 

B - constant

C - well loss coefficient

By Fierschenk's method of analysis (Driscoll, 1986):

$$\frac{S}{Q} = B + CQ$$

plot  $\frac{S}{Q}$  vs. Q } Two data points chosen:

$$Q_1 = 1.2 \text{ gpm} = 0.16 \text{ ft}^3/\text{min}$$

$$Q_2 = 2.7 \text{ gpm} = 0.36 \text{ ft}^3/\text{min}$$

$Q (\text{ft}^3/\text{min})$	$S (\text{ft.})$	$S/Q (\text{min}/\text{ft}^2)$
$Q_1 = 0.16$	$S_1 = 1.33$	$S_1/Q_1 = 8.31$
$Q_2 = 0.36$	$S_2 = 3.73$	$S_2/Q_2 = 10.36$

From graph:

$$B = 6.6 \text{ min}/\text{ft}^2$$

$$C = 10.25 \text{ min}^2/\text{ft}^5$$



Wahler Associates

## CALCULATION SHEET

SHEET 2 OF 2 SHEETS

PROJECT

SUBJECT

Step - Drawdown Test

PROJECT NO. JCO-104H

FILE

CALCULATED BY

D.S.

CHECKED BY

A.C.

DATE

9/28/87

$$s = 6.6 Q + 10.25 Q^2$$

Check

$$Q_1 = 0.16 \text{ ft}^3/\text{min}$$

$$s = (6.6 \text{ min}/\text{ft}^2)(.16 \text{ ft}^3/\text{min}) + (10.25 \text{ min}^2/\text{ft}^5)(0.0256 \text{ ft}^6/\text{min}^2)$$

$$s_1 = 1.06' + 0.26' = 1.32' \text{ } \parallel \text{ similar to what measured.}$$

$$Q_2 = 0.36 \text{ ft}^3/\text{min}$$


$$s_2 = (6.6 \text{ min}/\text{ft}^2)(.36 \text{ ft}^3/\text{min}) + (10.25 \text{ min}^2/\text{ft}^5)(0.1296 \text{ ft}^6/\text{min}^2)$$

$$s_2 = 2.38' + 1.33' = 3.71' \parallel$$

$$\text{When } Q = 2 \text{ gpm } (0.27 \text{ ft}^3/\text{min})$$

$$s = 6.6 \times 0.27 + (10.25 \times 0.27)^2$$

$$s = 2.53' \text{ desirable drawdown}$$



**APPENDIX C**

## CONSTANT-DISCHARGE TEST DATA AND CALCULATIONS

### Methods of Analysis

#### 1. Hantush-Jacob Method (1955):

General equation for leaky confined aquifer:

$$T = \frac{Q}{4\pi s} W(u, r/B)$$

s - drawdown

Q - discharge rate

T - transmissivity

W(u,r/B) - well function

dimensionless parameter  $r/B = r\sqrt{\frac{K'}{K_1 b_1 b'}}$

K' - hydraulic conductivity of the leaky aquitard

K<sub>1</sub> - hydraulic conductivity of the aquifer being tested

b' - thickness of the leaky aquitard

b<sub>1</sub> - thickness of the aquifer being tested

assumptions

- The aquifer is confined on top and bottom by aquitards. One of the aquitards may be leaky.
- The aquifer is level and infinite in horizontal extent.
- The aquifer is homogeneous and isotropic
- The pumping well fully penetrates the aquifer.
- Discharge from the well is at a constant rate.
- There is no storage within the well itself.
- The storativity of the leaky aquitard is zero.

#### 2. Jacob Straight Line Method (Freeze and Cherry, 1979):

$$T = \frac{2.3 Q}{4\pi \Delta(h_0 - h)} ; \quad S = \frac{2.25 T t_0}{r^2}$$

T - transmissivity ( $\text{ft}^2/\text{min}$ )

S - storativity

Q - discharge rate ( $\text{ft}^3/\text{min}$ )

r - radial distance from pumping to observation well (ft)

$\Delta(h_0-h)$  - drawdown for one log cycle of time

$t_0$  - time intercept on semi-log plot

assumptions and limitations:

- Assumptions are similar to those of Hantush and Jacob method
- this method is well suited to the analysis of bounded confined aquifers and small r, i.e., observation well close to pumping well.

3. Theis non-equilibrium equation modified by Cooper and Jacob (1946) for Recovery Data (Driscoll, 1986):

$$T = \frac{Q}{4\pi(s_1-s_2)} \ln \left( \frac{(t_1/t'_1)}{(t_2/t'_2)} \right)$$

T - transmissivity ( $\text{ft}^2/\text{min}$ )

Q - discharge rate ( $\text{ft}^3/\text{min}$ )

$s_{1,2}$  - residual drawdown (ft)

$t_{1,2}$  - time since pumping began (min)

$t'_{1,2}$  - time since pumping stopped (min)

4. Determining Hydraulic Conductivity:

$$K = T/b$$

K - hydraulic conductivity ( $\text{ft}/\text{min}$ )

T - transmissivity ( $\text{ft}^2/\text{min}$ )

b - aquifer thickness (ft)

5. Determining Seepage Velocity:

By Darcy's Law,

$$v = K \cdot \frac{dh}{dl} \cdot \frac{l}{n}$$

v - seepage velocity (ft/min)

K - hydraulic conductivity

$\frac{dh}{dl}$  - hydraulic gradient

n - effective porosity

## Constant Discharge Pumping Test: V-4

9/29-30, 10/1/87

Q=2.07gpm, 2.40gpm

V-4				V-2				V-4				V-2			
Time	Ch	H(ft)	ch	H(ft)	Time	ch	H(ft)	ch	H(ft)	Time	ch	H(ft)	ch	H(ft)	
12:06:20	7	9.08	8	4.52	12:56:00	7	8.35	8	4.02						
12:06:10	7	9.08	8	4.55	12:55:00	7	8.37	8	4.02						
-12:06:00	7	9.02	8	4.55	12:54:00	7	8.37	8	4.02						
12:05:50	7	9.02	8	4.55	12:53:00	7	8.37	8	4.02						
12:05:40	7	9.02	8	4.57	12:52:00	7	8.37	8	4.02						
12:05:30	7	9.05	8	4.57	12:51:00	7	8.37	8	4.02						
12:05:20	7	9.05	8	4.60	12:50:00	7	8.37	8	4.02						
12:05:10	7	9.07	8	4.60	12:49:00	7	8.40	8	4.02						
-12:05:00	7	9.10	8	4.62	12:48:00	7	8.40	8	4.02						
12:04:50	7	9.10	8	4.62	12:47:00	7	8.40	8	4.05						
12:04:40	7	9.10	8	4.62	12:46:00	7	8.40	8	4.02						
12:04:30	7	9.12	8	4.65	12:45:00	7	8.40	8	4.02						
12:04:20	7	9.15	8	4.67	12:44:00	7	8.42	8	4.05						
12:04:10	7	9.15	8	4.67	12:43:00	7	8.42	8	4.05						
12:04:00	7	9.17	8	4.70	12:42:00	7	8.42	8	4.05						
12:03:50	7	9.17	8	4.70	12:41:00	7	8.42	8	4.05						
12:03:40	7	9.20	8	4.72	-12:40:00	7	8.45	8	4.05						
12:03:30	7	9.22	8	4.75	12:39:00	7	8.45	8	4.05						
12:03:20	7	9.22	8	4.77	12:38:00	7	8.47	8	4.07						
12:03:10	7	9.25	8	4.77	12:37:00	7	8.47	8	4.07						
-12:03:00	7	9.27	8	4.80	12:36:00	7	8.47	8	4.07						
12:02:50	7	9.30	8	4.82	12:35:00	7	8.47	8	4.07						
12:02:40	7	9.32	8	4.85	12:34:00	7	8.50	8	4.07						
12:02:30	7	9.35	8	4.87	12:33:00	7	8.50	8	4.07						
12:02:20	7	9.37	8	4.90	12:32:00	7	8.50	8	4.10						
12:02:10	7	9.40	8	4.92	12:31:00	7	8.52	8	4.10						
-12:02:00	7	9.42	8	4.95	12:30:00	7	8.52	8	4.10						
12:01:50	7	9.45	8	4.97	12:29:00	7	8.52	8	4.10						
12:01:40	7	9.47	8	4.97	12:28:00	7	8.55	8	4.12						
12:01:30	7	9.47	8	5.00	12:27:00	7	8.55	8	4.12						
12:01:20	7	9.50	8	5.00	12:26:00	7	8.55	8	4.15						
12:01:10	7	9.50	8	5.00	12:25:00	7	8.57	8	4.15						
12:01:00	7	9.52	8	5.02	12:24:00	7	8.57	8	4.15						
12:00:50	7	9.55	8	5.05	12:23:00	7	8.60	8	4.17						
12:00:40	7	9.57	8	5.05	12:22:00	7	8.60	8	4.17						
12:00:30	7	9.60	8	5.07	12:21:00	7	8.62	8	4.20						
12:00:20	7	9.62	8	5.10	12:20:00	7	8.65	8	4.20						
12:00:10	7	9.65	8	5.10	12:19:00	7	8.65	8	4.22						
12:00:05	7	9.67	8	5.12	12:18:00	7	8.67	8	4.22						
-12:00:00	7	9.70	8	5.15	12:17:00	7	8.67	8	4.25						
12:00:55	7	9.75	8	5.17	12:16:00	7	8.70	8	4.25						
12:00:50	7	9.80	8	5.17	12:15:00	7	8.72	8	4.27						
12:00:45	7	9.82	8	5.20	12:14:00	7	8.72	8	4.27						
12:00:40	7	9.87	8	5.22	12:13:00	7	8.75	8	4.30						
12:00:35	7	9.95	8	5.25	12:12:00	7	8.77	8	4.32						
-12:00:30	7	10.00	8	5.27	12:11:00	7	8.80	8	4.35						
12:00:25	7	10.07	8	5.27	12:10:00	7	8.82	8	4.37						
12:00:20	7	10.17	8	5.30	12:09:00	7	8.87	8	4.42						
-12:00:15	7	10.27	8	5.32	12:08:00	7	8.90	8	4.45						
12:00:10	7	10.40	8	5.35	12:07:00	7	8.95	8	4.50						
12:00:05	7	10.57	8	5.35	12:06:00	7	8.97	8	4.50						
12:00:00	7	10.30	8	5.35	12:05:00	7	8.97	8	4.50						
12:54:53 87/09/21 4:19					12:04:40	7	8.97	8	4.50						
Begin test					12:03:00	7	8.97	8	4.52						

## Constant Discharge pumping test: V-4 (continued)

9/29-30, 10/1/87

Q=2.07gpm, 2.40gpm

	V-4	V-2		V-4	V-2
Time	ch H(ft)	ch H(ft)	Time	ch H(ft)	ch H(ft)
16:07:00	7 7.82	8 3.85	19:43:00	7 7.47	8 3.75
16:03:00	7 7.80	8 3.85	19:39:00	7 7.50	8 3.77
15:59:00	7 7.82	8 3.85	19:35:00	7 7.50	8 3.77
15:55:00	7 7.82	8 3.85	19:31:00	7 7.50	8 3.77
15:51:00	7 7.82	8 3.85	19:27:00	7 7.50	8 3.75
15:47:00	7 7.82	8 3.85	19:23:00	7 7.50	8 3.77
15:43:00	7 7.82	8 3.85	19:19:00	7 7.52	8 3.77
15:39:00	7 7.85	8 3.85	19:15:00	7 7.52	8 3.77
15:35:00	7 7.85	8 3.85	19:11:00	7 7.52	8 3.75
15:31:00	7 7.87	8 3.85	19:07:00	7 7.47	8 3.77
15:27:00	7 7.87	8 3.85	19:03:00	7 7.55	8 3.77
15:23:00	7 7.90	8 3.87	18:59:00	7 7.55	8 3.77
15:19:00	7 7.90	8 3.87	18:55:00	7 7.55	8 3.77
15:15:00	7 7.90	8 3.87	18:51:00	7 7.55	8 3.77
15:11:00	7 7.92	8 3.87	18:47:00	7 7.57	8 3.89
15:07:00	7 7.92	8 3.87	18:43:00	7 7.57	8 3.77
15:03:00	7 7.95	8 3.87	18:39:00	7 7.57	8 3.77
14:59:00	7 7.95	8 3.87	18:35:00	7 7.57	8 3.77
14:55:00	7 7.97	8 3.87	18:31:00	7 7.57	8 3.77
14:51:00	7 8.00	8 3.90	18:27:00	7 7.60	8 3.89
14:47:00	7 8.05	8 3.92	18:23:00	7 7.60	8 3.89
14:43:00	7 7.97	8 3.90	18:19:00	7 7.60	8 3.89
14:39:00	7 8.00	8 3.90	18:15:00	7 7.60	8 3.89
14:35:00	7 8.00	8 3.90	18:11:00	7 7.62	8 3.89
14:31:00	7 8.00	8 3.90	18:07:00	7 7.62	8 3.89
14:27:00	7 8.02	8 3.90	18:03:00	7 7.62	8 3.89
14:23:00	7 8.02	8 3.90	17:59:00	7 7.62	8 3.89
14:19:00	7 8.05	8 3.90	17:55:00	7 7.65	8 3.89
14:15:00	7 8.05	8 3.90	17:51:00	7 7.65	8 3.89
14:11:00	7 8.07	8 3.92	17:47:00	7 7.65	8 3.89
14:07:00	7 8.07	8 3.92	17:43:00	7 7.65	8 3.89
14:03:00	7 8.10	8 3.92	17:39:00	7 7.65	8 3.89
13:59:00	7 8.10	8 3.92	17:35:00	7 7.67	8 3.82
13:55:00	7 8.12	8 3.92	17:31:00	7 7.67	8 3.82
13:51:00	7 8.12	8 3.92	17:27:00	7 7.67	8 3.82
13:47:00	7 8.15	8 3.95	17:23:00	7 7.67	8 3.82
13:43:00	7 8.15	8 3.95	17:19:00	7 7.70	8 3.82
13:39:00	7 8.15	8 3.95	17:15:00	7 7.70	8 3.82
13:35:00	7 8.17	8 3.95	17:11:00	7 7.70	8 3.82
13:31:00	7 8.20	8 3.97	17:07:00	7 7.70	8 3.82
13:27:00	7 8.20	8 3.97	17:03:00	7 7.72	8 3.82
13:23:00	7 8.22	8 3.97	16:59:00	7 7.72	8 3.82
13:19:00	7 8.25	8 3.97	16:55:00	7 7.75	8 3.82
13:15:00	7 8.27	8 4.00	16:51:00	7 7.72	8 3.82
13:11:00	7 8.27	8 4.00	16:47:00	7 7.72	8 3.82
13:07:00	7 8.30	8 4.00	16:43:00	7 7.72	8 3.82
13:03:00	7 8.30	8 4.00	16:39:00	7 7.72	8 3.82
13:02:00	7 8.32	8 4.00	16:35:00	7 7.75	8 3.85
13:01:00	7 8.32	8 4.00	16:31:00	7 7.77	8 3.85
13:00:00	7 8.32	8 4.00	16:27:00	7 7.77	8 3.85
12:59:00	7 8.32	8 4.00	16:23:00	7 7.77	8 3.85
12:58:00	7 8.35	8 4.02	16:19:00	7 7.77	8 3.85
12:57:00	7 8.35	8 4.02	16:15:00	7 7.80	8 3.85

## Constant Discharge test recovery data: V-4

V-4 V-2 10-1-87 V-4 V-2

Time	ch	H(ft)	ch	H(ft)	Time	ch	H(ft)	ch	H(ft)
00:16:21	7	9.99	8	4.57	01:42:21	7	10.65	8	5.32
00:15:21	7	9.87	8	4.52	01:58:21	7	10.65	8	5.32
00:14:21	7	9.92	8	4.50	01:34:21	7	10.62	8	5.32
00:13:21	7	9.77	8	4.45	01:30:21	7	10.62	8	5.30
00:12:21	7	9.72	8	4.37	01:26:21	7	10.60	8	5.27
00:11:21	7	9.65	8	4.32	01:22:21	7	10.60	8	5.27
00:10:21	7	9.55	8	4.25	01:18:21	7	10.57	8	5.25
00:10:11	7	9.52	8	4.22	01:14:21	7	10.55	8	5.22
00:10:01	7	9.50	8	4.22	01:10:21	7	10.55	8	5.22
00:09:51	7	9.47	8	4.20	01:06:21	7	10.52	8	5.22
00:09:41	7	9.45	8	4.17	01:02:21	7	10.52	8	5.20
00:09:31	7	9.42	8	4.17	01:07:21	7	10.52	8	5.20
00:09:21	7	9.42	8	4.15	01:06:21	7	10.52	8	5.20
00:09:11	7	9.40	8	4.15	01:05:21	7	10.52	8	5.20
00:09:01	7	9.37	8	4.12	01:04:21	7	10.50	8	5.20
00:08:51	7	9.35	8	4.10	01:03:21	7	10.50	8	5.17
00:08:41	7	9.35	8	4.10	01:02:21	7	10.50	8	5.17
00:08:31	7	9.32	8	4.07	01:01:21	7	10.50	8	5.17
00:08:21	7	9.30	8	4.05	01:00:21	7	10.47	8	5.17
00:08:11	7	9.27	8	4.05	00:59:21	7	10.47	8	5.15
00:08:01	7	9.27	8	4.02	00:58:21	7	10.47	8	5.15
00:07:51	7	9.22	8	4.00	00:57:21	7	10.47	8	5.15
00:07:41	7	9.22	8	3.97	00:56:21	7	10.45	8	5.15
00:07:31	7	9.17	8	3.95	00:55:21	7	10.45	8	5.12
00:07:21	7	9.17	8	3.92	00:54:21	7	10.45	8	5.12
00:07:11	7	9.12	8	3.90	00:53:21	7	10.45	8	5.12
00:07:01	7	9.10	8	3.87	00:52:21	7	10.42	8	5.12
00:06:51	7	9.07	8	3.85	00:51:21	7	10.42	8	5.10
00:06:41	7	9.02	8	3.82	00:50:21	7	10.42	8	5.10
00:06:31	7	9.00	8	3.80	00:49:21	7	10.42	8	5.10
00:06:21	7	8.95	8	3.77	00:48:21	7	10.40	8	5.07
00:04:11	7	8.92	8	3.75	00:47:21	7	10.40	8	5.07
00:06:01	7	8.87	8	3.70	00:46:21	7	10.40	8	5.07
00:05:51	7	8.82	8	3.67	00:45:21	7	10.37	8	5.05
00:05:41	7	8.77	8	3.65	00:44:21	7	10.37	8	5.05
00:05:31	7	8.70	8	3.62	00:43:21	7	9.97	8	5.05
00:05:21	7	8.65	8	3.57	00:42:21	7	10.35	8	5.02
00:05:16	7	8.60	8	3.57	00:41:21	7	10.35	8	5.02
00:05:11	7	8.57	8	3.55	00:40:21	7	10.35	8	5.02
00:05:06	7	8.52	8	3.52	00:39:21	7	10.32	8	5.00
00:05:01	7	8.47	8	3.52	00:38:21	7	10.32	8	5.00
00:04:56	7	8.42	8	3.50	00:37:21	7	10.30	8	4.97
00:04:51	7	8.35	8	3.47	00:36:21	7	10.30	8	4.97
00:04:46	7	8.27	8	3.47	00:35:21	7	10.27	8	4.95
00:04:41	7	8.22	8	3.45	00:34:21	7	10.27	8	4.95
00:04:36	7	8.12	8	3.42	00:33:21	7	10.25	8	4.92
00:04:31	7	8.05	8	3.42	00:32:21	7	10.25	8	4.92
00:04:26	7	7.95	8	3.40	00:31:21	7	10.22	8	4.90
00:04:21	7	7.85	8	3.40	00:30:21	7	10.22	8	4.90
00:04:16	7	7.72	8	3.37	00:29:21	7	10.20	8	4.87
00:04:11	7	7.60	8	3.35	00:28:21	7	10.17	8	4.85
00:04:06	7	7.47	8	3.35	00:27:21	7	10.17	8	4.85
00:04:01	7	7.30	8	3.32	00:26:21	7	10.15	8	4.82
00:03:56	7	7.15	8	3.32	00:25:21	7	10.12	8	4.80
00:03:51	7	6.95	8	3.30	00:24:21	7	10.12	8	4.80
00:03:46	7	6.75	8	3.30	00:23:21	7	10.10	8	4.77
00:03:41	7	6.52	8	3.30	00:22:21	7	10.07	8	4.75
00:03:36	7	6.27	8	3.30	00:21:21	7	10.05	8	4.72
00:03:31	7	6.00	8	3.29	00:20:21	7	10.02	8	4.70
00:03:26	7	5.92	8	3.29	00:19:21	7	10.00	8	4.67
00:03:21	7	5.92	8	3.29	00:18:21	7	9.97	8	4.65
00:00 HRS	87/10/01	#19			00:17:21	7	9.92	8	4.60

Begin recovery

## Constant Discharge test Recovery Data: V-4 (continued)

10-1-87

	V-4	V-2
Time	ch H(ft)	ch H(ft)
04:38:21	7 10.85	8 5.55
04:34:21	7 10.85	8 5.55
04:30:21	7 10.85	8 5.55
04:26:21	7 10.85	8 5.55
04:22:21	7 10.85	8 5.55
04:18:21	7 10.85	8 5.52
04:14:21	7 10.85	8 5.55
04:10:21	7 10.82	8 5.52
04:06:21	7 10.85	8 5.52
04:04:21	7 10.85	8 5.52
03:58:21	7 10.82	8 5.52
03:54:21	7 10.82	8 5.52
03:50:21	7 10.82	8 5.52
03:46:21	7 10.82	8 5.52
03:42:21	7 10.82	8 5.52
03:38:21	7 10.82	8 5.52
03:34:21	7 10.82	8 5.50
03:30:21	7 10.82	8 5.50
03:26:21	7 10.80	8 5.50
03:22:21	7 10.80	8 5.50
03:18:21	7 10.80	8 5.50
03:14:21	7 10.80	8 5.50
03:10:21	7 10.80	8 5.47
03:06:21	7 10.80	8 5.47
03:02:21	7 10.80	8 5.47
02:58:21	7 10.80	8 5.47
02:54:21	7 10.77	8 5.47
02:50:21	7 10.77	8 5.45
02:46:21	7 10.77	8 5.45
02:42:21	7 10.77	8 5.45
02:38:21	7 10.77	8 5.45
02:34:21	7 10.75	8 5.42
02:30:21	7 10.75	8 5.42
02:26:21	7 10.75	8 5.42
02:22:21	7 10.75	8 5.42
02:18:21	7 10.72	8 5.40
02:14:21	7 10.72	8 5.40
02:10:21	7 10.72	8 5.40
02:06:21	7 10.72	8 5.40
02:02:21	7 10.70	8 5.37
01:58:21	7 10.70	8 5.37
01:54:21	7 10.67	8 5.35
01:50:21	7 10.67	8 5.35
01:46:21	7 10.67	8 5.35

JOB NO. : JCO-1041+ WELL NO. : V-4 DATE: 9/29, 30, 10/1/82 PUMPED/TESTED BY: RGB/DS

WELL DIA.: 4" Pumping Method: Grimfus Submersible Weather: Sunny + warm  
REFERENCE POINT: TOP OF protective Casing REFERENCE ELEVATION: 58.54'

INITIAL DEPTH TO WATER: 24.40 INITIAL DEPTH OF OPEN WELL: 35'  
INITIAL HEIGHT OF WATER COLUMN IN WELL: 10.6'

$$\text{VOLUME OF 1 CASING FULL OF WATER: } \frac{0.23}{(PI \times R^2 \times H)} \text{ CU. FEET} \\ (PI \times R^2 \times H), \text{ IN FT}^3 \quad \frac{0.23}{\pi \times 7.479} = 1.73 \text{ GAL.}$$

NO. OF CASINGS FULL PUMPED:

Peach Sampled:

SAMPLES TAKEN: \_\_\_\_\_

WILLIAMS THIRKET \_\_\_\_\_  
PRESERVATION

NOTE:  $24.40' = 10.97' = \text{std DC}$

recorded on channel 7

JOB NO. : JCC-1041t WELL NO. : V-4 DATE: 9/29/30, 10/1/02 PUMPED/TESTED BY: RGB/DSWELL DIA.: 4" Pumping Method: Gruntus Submersible Weather: Sunny + warm.REFERENCE POINT: Pressure Transducer REFERENCE ELEVATION: —INITIAL DEPTH TO WATER: 24.40 INITIAL DEPTH OF OPEN WELL: 35'  
INITIAL HEIGHT OF WATER COLUMN IN WELL: 10.6'VOLUME OF 1 CASING FULL OF WATER: 0.23 CU. FEET  
( $\pi \times R^2 \times H$ ), IN FT<sup>3</sup> 0.23  $\times 7.479 = 1.73$  GAL. INITIAL METER READIN  
= 12126.17

CLOCK TIME	TIME ELAPSED	METER READING (FT <sup>3</sup> )	DEPTH OF WATER ABOVE PROBE (FEET)	Q (cfs)	COMMENTS & OBSERVATIONS
1605.30	4 hours	12189.13	7.80	2.04	9/29
1750.45	5	12205.71	7.72	2.02	
1800.30	6	12224.69	7.62	2.07	
1900.30	7	12241.05	7.52	2.02	
2000.45	8	12257.50	7.45	2.04	
2100.45	9	12273.86	7.37	2.02	
2158.30	10	12289.61	7.32	2.02	
2259.30	11	12306.20	7.25	2.07	
2357.30	12	12322.94	7.25	2.09	9/30
NO DATA	13	NO DATA	NO DATA	NO DATA	
0203.30	14	12356.08	7.17	1.99	
NO DATA	15	NO DATA	NO DATA	NO DATA	
0402.30	16	12388.16	7.10	2.02	
NO DATA	17	NO DATA	NO DATA	NO DATA	
0601.30	18	12420.23	7.02	2.02	
0704.00	19	12437.05	6.97	2.02	
0758.00	20	12451.57	6.92	1.99	
0900.00	21	12468.23	6.87	2.02	
0958.00	22	12483.815	6.85	2.01	
1105.00	23	12501.60	6.80	1.98	

NO. OF CASINGS FULL PUMPED: 2648.78 = 1582.40 gal NOTE: 10.97 = 5.92 DCDepth Sampled: —TOTAL Drawdown = 10.97 - 5.92 = 5.05'SAMPLES TAKEN: —PRESERVATIVE: —

Recorded on Channel 7

JOB NO. : JCC-10414 WELL NO. : U-4 DATE: 9/29-30, 10/1/87 PUMPED/TESTED BY: RGB

WELL DIA.: 4" Pumping Method: Günfus Submersible Weather: Sunny & Warm

REFERENCE POINT: Pressure Transducer REFERENCE ELEVATION: \_\_\_\_\_

INITIAL DEPTH TO WATER: 24.40 INITIAL DEPTH OF OPEN WELL: 35'  
INITIAL HEIGHT OF WATER COLUMN IN WELL: 10.6'

$$\text{VOLUME OF 1 CASING FULL OF WATER: } \frac{\pi}{4} R^2 H \text{ CU. FEET}$$

NO. OF CASINGS FULL PUMPED: \_\_\_\_\_ NOTE: 10.17 - 5.92 = 5.05'  
Depth Sampled: \_\_\_\_\_ Total Drawdown = 10.17 - 5.92 = 5.05'  
SAMPLES TAKEN: \_\_\_\_\_ recorded on - Channel 7  
PRESERVATIVE: \_\_\_\_\_

JOB NO. : JCC-10417 WELL NO. : V-2 DATE: 9/29-30, 10/1, 187 PUMPED/TESTED BY RG-B/DS

WELL DIA.: 2" Pumping Method: OBSERVATION WELL Weather: sunny and warm  
pressure transducer ?  
REFERENCE POINT: TOP of Chnsy REFERENCE ELEVATION: 57.38'

INITIAL DEPTH TO WATER: 23.23' INITIAL DEPTH OF OPEN WELL: 35'  
INITIAL HEIGHT OF WATER COLUMN IN WELL: 11.77'

$$\text{VOLUME OF 1 CASING FULL OF WATER: } \frac{0.26}{(PI \times R^2 \times H)} \text{ CU. FEET}$$

$$= \frac{0.26}{\pi \times 0.5^2 \times 7.479} = 1.92 \text{ GAL.}$$

NO. OF CASINGS FULL PUMPED:

Depth Sampled:

### DEEPEN SAMPLING SAMPLES TAKEN:

#### **STRIPES AREN'T PRESERVATIVE;**

PRESERVATIVE:

Note: 23.23 = 5.50 = 550C  
recorded on channel 8

JOB NO. : JCO-1041 WELL NO. : V-2 DATE: 9/29, 30, 10/1/07 PUMPED/TESTED BY: RBB/DSWELL DIA.: " Pumping Method: OBSERVATION WELL Weather: Sunny + Warm.REFERENCE POINT: Pressure Transducer REFERENCE ELEVATION: \_\_\_\_\_INITIAL DEPTH TO WATER: 23.23 INITIAL DEPTH OF OPEN WELL: 35'  
INITIAL HEIGHT OF WATER COLUMN IN WELL: 11.77VOLUME OF 1 CASING FULL OF WATER: 0.26 CU. FEET  
( $\pi \times R^2 \times H$ ), IN FT<sup>3</sup> 0.26  $\times 7.479 = 1.92 GAL. STATIC LEVEL  
= 5.50'$ 

CLOCK TIME	TIME ELAPSED	U-4 METER READING (FT <sup>3</sup> )	DEPTH OF WATER ABOVE PROBE (FEET)	Q (CCFS)	COMMENTS & OBSERVATIONS
1605.30	4 hrs	12189.13	3.85	2.04	9/29
1750.45	5	12205.71	3.82	2.02	
1800.30	6	12224.69	3.80	2.07	
1900.30	7	12241.05	3.77	2.02	
2000.45	8	12257.50	3.75	2.04	
2100.45	9	12273.86	3.72	2.02	
2158.30	10	12289.61	3.70	2.02	
2259.30	11	12306.20	3.70	2.07	
2357.30	12	12322.94	3.72	2.09	9/30
NO DATA	13	NO DATA	NO DATA	NO DATA	
0203.30	14	12356.08	3.75	1.99	
NO DATA	15	NO DATA	NO DATA	NO DATA	
0402.30	16	12388.16	3.72	2.02	
NO DATA	17	NO DATA	NO DATA	NO DATA	
0601.30	18	12420.23	3.72	2.02	
0704.00	19	12437.05	3.70	2.02	
0758.00	20	12451.57	3.70	1.99	
0900.00	21	12468.23	3.67	2.02	
0958.00	22	12483.815	3.65	2.01	
1105.00	23	12501.60	3.65	1.98	

NO. OF CASINGS FULL PUMPED: \_\_\_\_\_

NOTE: recorded on channel 8

Depth Sampled: \_\_\_\_\_

TOTAL Drawdown = 5.50' - 3.30' = 2.20'

SAMPLES TAKEN: \_\_\_\_\_

PRESERVATIVE: \_\_\_\_\_

 Wchler  
Associates

WELL PUMPING/TESTING DATA SHEET Page 3 of 3

Page 3 of 3

JOB NO. : JCC-1041 WELL NO. : U-2 DATE: 9/29-30, 10/1/87 PUMPED/TESTED BY: RG8

WELL DIA.: 2" Pumping Method: OBSERVATION-WELL Weather: Sunny + Warm

REFERENCE POINT: Pressure Transducer REFERENCE ELEVATION: \_\_\_\_\_

INITIAL DEPTH TO WATER: 23.23' INITIAL DEPTH OF OPEN WELL: 35'  
INITIAL HEIGHT OF WATER COLUMN IN WELL: 11.77'

VOLUME OF 1 CASING FULL OF WATER: 0.26 CU. FEET

$$(\text{PI} \times R^2 \times H), \text{ IN FT}^3 \quad \frac{0.26}{\text{x } 7.479} = \underline{1.92 \text{ GAL.}}$$

NO. OF CASTINGS FULL BUMPER:

note: recorded on Channel 8

No. of castings from each sample:

Depth Sampled;  
SAMPLES TAKEN;

SAMPLES TAKEN  
PRESERVATIVE:

$$\text{Total Drawdown} = 5.50 - 3.30 = 2.20'$$


## Hantush - Jacob Method (by GWAP)

## Data for Pump Test

Well Name: V4a Date of Test: 9/29/87  
 Well Number: 1  
 Pumped Well Discharge(Q) = 2.05 gpm  
 Pumped Well Radius(r) = 0.17 feet  
 Distance(d) of Observation Well from Pumped Well = 6.00 feet (V2)

Entry No.	Time(t) (min.)	Drawdown(s) (ft.)	t / d (min./sq.ft.)
1	0.000	0.000	0.00E+00
2	0.250	0.030	3.91E-03
3	0.500	0.060	7.81E-03
4	1.000	0.200	1.56E-02
5	2.000	0.400	3.13E-02
6	3.000	0.550	4.69E-02
7	4.000	0.650	6.25E-02
8	6.000	0.800	9.38E-02
9	10.000	0.980	1.56E-01
10	16.000	1.100	2.50E-01
11	25.000	1.200	3.91E-01
12	40.000	1.300	6.25E-01
13	60.000	1.350	9.38E-01
14	119.000	1.430	1.86E+00
15	179.000	1.480	2.80E+00
16	240.000	1.500	3.75E+00
17	300.000	1.530	4.69E+00
18	360.000	1.550	5.63E+00
19	420.000	1.580	6.56E+00
20	480.000	1.600	7.50E+00
21	540.000	1.630	8.44E+00
22	600.000	1.650	9.38E+00
23	720.000	1.630	1.13E+01
24	960.000	1.630	1.50E+01
25	1140.000	1.650	1.78E+01
26	1260.000	1.680	1.97E+01
27	1320.000	1.680	2.06E+01
28	1440.000	1.680	2.25E+01

PUMP TEST DATA (V4)



SOLUTION

Transmissivity = 6.289E-02 ft.<sup>2</sup>/min.  
Storativity = 1.587E-03



Wahler Associates

## CALCULATION SHEET

SHEET 1 OF 5 SHEETS

PROJECT Jaco Chemical Corporation  
SUBJECT Constant - Discharge Test CalculationsPROJECT NO. JCO-1044CALCULATED BY D.S. CHECKED BY A.C.FILE \_\_\_\_\_  
DATE 10/1/87

Hantush - Jacob Method (by computer program GINMAP)

$$T = 6.29 \times 10^{-2} \text{ ft}^2/\text{min}$$

$$K = 6.29 \times 10^{-2}$$

$$b = 7'$$

$$\begin{aligned} K &= 8.98 \times 10^{-3} \text{ ft}/\text{min} \\ &= 4.56 \times 10^{-3} \text{ cm/sec} \end{aligned}$$

Seepage velocity,  $V$

$$V = K \frac{dh}{dt} \frac{1}{n}$$

From A-aquifer  
potentiometric maps,

$$\frac{dh}{dt} \approx 0.004$$

$$V = 8.98 \times 10^{-3} \times 0.004 \times \frac{1}{0.4}$$

$n$  for A-aquifer material  
is assumed to be 0.4  
(Freeze and Cherry, 1979)

$$V = 8.98 \times 10^{-5} \text{ ft}/\text{min}$$

$$V = 47.2 \text{ ft/yr.}$$



Wahler Associates

## CALCULATION SHEET

SHEET 2 OF 5 SHEETSPROJECT Jasco Chemical Corporation  
SUBJECT Constant - Discharge Test CalculationsPROJECT NO. JCO-104HCALCULATED BY D.S.CHECKED BY A.C.

FILE \_\_\_\_\_

DATE \_\_\_\_\_

## Jacob Straight Line Analysis:

$$T = 2.3 Q \\ 4\pi A(h_0 - h)$$

$$Q = 2.05 \text{ gpm} = 0.274 \text{ ft}^3/\text{min}$$

 $b$  (aquifer thickness) = 7'

$$T = 2.3 (0.274 \text{ ft}^3/\text{min}) \\ 4\pi (0.83 \text{ ft})$$

from graph

$$T = 6.04 \times 10^{-2} \text{ ft}^2/\text{min}$$

$$K = T/b$$

$$K = 6.04 \times 10^{-2} \text{ ft}^2/\text{min} \\ 7 \text{ ft}$$

$$K = 8.63 \times 10^{-3} \text{ ft/min} = 4.23 \times 10^{-3} \text{ cm/sec}$$

$$S = \frac{2.25 T t_0}{r^2}$$

 $r = 8 \text{ ft}$  $t_0 = 0.68 \text{ min}$   
(from graph)

$$S = \frac{2.25 (6.04 \times 10^{-2} \text{ ft}^2/\text{min}) (0.68 \text{ min})}{64 \text{ ft}^2}$$

$$S = 1.44 \times 10^{-3}$$



Wahler Associates

## CALCULATION SHEET

SHEET 3 OF 5 SHEETSPROJECT Jasco Chemical Corporation  
SUBJECT Constant Discharge Test CalculationsPROJECT NO. JCO-104HCALCULATED BY D.S. CHECKED BY A.C.FILE   
DATE 10/1/87Seepage Velocity -  $v$ ,

$$v = K \cdot \frac{dh}{dl} \cdot \frac{1}{n}$$

Based on potentiometric maps,

$$\frac{dh}{dl} \approx 0.004$$

Porosity of A-aquifer  
material is assumed to  
be 0.4 (Freeg & Cherry, 1979).

$$v = 8.63 \times 10^{-3} \times 0.004 \times \frac{1}{0.4}$$

$$v = 8.63 \times 10^{-5} \text{ ft/min}$$

$$v = 45.4 \text{ ft/yr}$$



Wahler Associates

## CALCULATION SHEET

SHEET 4 OF 5 SHEETS

PROJECT

SUBJECT

Constant Discharge Test CalculationsPROJECT NO. JCO-104-H

CALCULATED BY

D.S.

CHECKED BY

A.C.

FILE

DATE

10/1/87

Modified Theis non-equilibrium equation  
for Recovery Data:

$$T = \frac{Q}{4\pi (S_1 - S_2)} \ln \left( \frac{(t_1/t_1')}{(t_2/t_2')} \right)$$

Recovered data from V-4:

$t/t'$	$t'$ time since pumping stopped (min)	$S$ residual drawdown (ft)
$2160/5.5 = 4,321.0$	0.5	4.02
$2161/1.0 = 2161.0$	1.00	3.12
$2162/2.0 = 1081.0$	2.00	2.32
$2164/4.0 = 541.0$	4.00	1.80
$2168/8.0 = 271.0$	8.00	1.32
$2176/16.0 = 136.0$	16.00	0.97
$2185/25.0 = 87.4$	25.00	0.80
$2198/38.0 = 57.8$	38.00	0.62
$2220/60.0 = 37.0$	60.00	0.47
$2259/99.0 = 22.8$	99.00	0.32
$2299/139.0 = 16.5$	139.00	0.22
$2335/175.0 = 13.3$	175.00	0.17

$$t_0 = 36 \text{ hrs.} = 2160 \text{ mins}$$

$$t = 2160 + t'$$



Wahler Associates

## CALCULATION SHEET

SHEET 5 OF 5 SHEETS

PROJECT

SUBJECT

Constant Discharge Test CalculationsPROJECT NO. JCO-104H

CALCULATED BY

D.S.

CHECKED BY

A.C.

FILE

DATE

10/1/87

$$T = \frac{0.31 \text{ ft}^3/\text{min}}{4\pi(2.95) \text{ ft}} \ln \left( \frac{2161}{13.3} \right)$$

$$Q = 2.33 \text{ gpm}$$

$$= 0.31 \text{ ft}^3/\text{min}$$

$$T = 4.26 \times 10^{-2} \text{ ft}^2/\text{min}$$

Select 2 data points  
from graph:

$$(t_1/t_1') = 2161.0$$

$$(t_2/t_2') = 13.3$$

$$S_1 - S_2 = 3.12 - 0.17 \\ = 2.95$$


$$b = 7'$$

$$R = \frac{T}{b} = \frac{4.26 \times 10^{-2}}{7} = 6.09 \times 10^{-3} \text{ ft}/\text{min} \\ = 3.10 \times 10^{-3} \text{ cm/sec}$$


$$\text{Seepage velocity, } v = \frac{R dh}{de} \times \frac{1}{n} ; \frac{dh}{de} = 0.004 \\ n = 0.4$$

$$v = 32 \text{ ft/yr}$$

Drawdown, S (feet)



Tasco  
Graph of VH  
Recovery Test  
JCO-101H



**APPENDIX D**

JOB NO. : JCC-10411 WELL NO. : V-1 DATE: 9/29-30 10/1/87 PUMPED/TESTED BY: R.G.B/DS

WELL DIA.: 2" Pumping Method: OBSERVATION WELL Weather: Sunny and warm

REFERENCE POINT: TOP of Christy REFERENCE ELEVATION: 58.29'

INITIAL DEPTH TO WATER: 23.67 INITIAL DEPTH OF OPEN WELL: 48.00'  
INITIAL HEIGHT OF WATER COLUMN IN WELL: 24.33'

$$\text{VOLUME OF 1 CASING FULL OF WATER: } \frac{0.53}{(PI \times R^2 \times H)} \text{ CU. FEET} \\ (PI \times R^2 \times H) \text{ IN FT}^3 \quad \frac{0.53}{x} \times 7.479 = 3.97 \text{ GAL.}$$

NO. OF CASTINGS FULL PUMPED:

**Perch Sampled:**

**DEPTH SAMPLES  
SAMPLES TAKEN:**

**SAMPLES ;AREN;  
PREFEEVATIVE;**

 Wahler  
Associates

WELL PUMPING/TESTING DATA SHEET Page 1 of 1

JOB NO. : JCO-1041 WELL NO. : V-3 DATE: 9/29, 30, 10/1/07 PUMPED/TESTED BY: RGB/DS

WELL DIA.: 5" Pumping Method: OBSERVATION WELL. Weather: Sunny + warm

REFERENCE POINT: TOC REFERENCE ELEVATION: 57.60

INITIAL DEPTH TO WATER: 22.94' INITIAL DEPTH OF OPEN WELL: 35'  
INITIAL HEIGHT OF WATER COLUMN IN WELL: 12.06

$$\text{VOLUME OF 1 CASING FULL OF WATER: } \frac{0.26}{(PI \times R^2 \times H)} \text{ CU. FEET} \\ (PI \times R^2 \times H), \text{ IN FT}^3 \quad \frac{0.26}{\pi \times 7.479} = \underline{\underline{1.97}} \text{ GAL.}$$

NO. OF CASTINGS FULL PUMPED:

**Perch Sampled:**

SAMPLES TAKEN:

**REPRESENTATIVE:** \_\_\_\_\_

JOB NO. : JCO-1041 WELL NO. : V-5 DATE: 9/29-30, 10/1/82 PUMPED/TESTED BY: R68/DS

WELL DIA.: 2" Pumping Method: OBSERVATION WELL Weather: Sunny + Warm

REFERENCE POINT: top of steel casing REFERENCE ELEVATION: 60.14'

INITIAL DEPTH TO WATER: 25.95' INITIAL DEPTH OF OPEN WELL: 36.5'  
INITIAL HEIGHT OF WATER COLUMN IN WELL: 10.55'

$$\text{VOLUME OF 1 CASING FULL OF WATER: } \frac{0.23}{(PI \times R^2 \times H)} \text{ CU. FEET} \\ (PI \times R^2 \times H), \text{ IN FT}^3 \quad \frac{0.23}{\pi \times 0.25^2 \times 10} \times 7.479 = 1.72 \text{ GAL.}$$

NO. OF CASTINGS FULL PUMPED:

Depth Sampled:

**SAMPLES TAKEN:**

**PRESENTATIVE:** \_\_\_\_\_

 Wahler  
Associates

WELL PUMPING/TESTING DATA SHEET Page 1 of 1

JOB NO. : JCO-104H WELL NO. : U-6 DATE: 9/29-30, 10/1/87 PUMPED/TESTED BY: R68/DS

WELL DIA.: 2" Pumping Method: OBSERVATION WELL Weather: sunny & warm

REFERENCE POINT: Top of metal Casing REFERENCE ELEVATION: 58.59'

INITIAL DEPTH TO WATER: 24.59 INITIAL DEPTH OF OPEN WELL: 42.7'  
INITIAL HEIGHT OF WATER COLUMN IN WELL: 18.11

$$\text{VOLUME OF 1 CASING FULL OF WATER: } \frac{0.40}{(PI \times R^2 \times H), \text{ IN FT}^3} \times 7.479 = 2.96 \text{ GAL.}$$

NO. OF CASINGS FULL PUMPED:

Depth Sampled:

**SAMPLES TAKEN:**

#### PERIODIC PRESERVATIVE:

 Wahler  
Associates

WELL PUMPING/TESTING DATA SHEET Page 1 of 1

JOB NO. : JCO-104 H.WELL NO. : V-7 DATE: 9/29, 30, 10/1/87 PUMPED/TESTED BY: rob/DS

WELL DIA.: 2" Pumping Method: OBSERVATION WELL Weather: Sunny & Warm

REFERENCE POINT: TOP of steel casing REFERENCE ELEVATION: 56.76'

INITIAL DEPTH TO WATER: 23.19' INITIAL DEPTH OF OPEN WELL: 35.5'  
INITIAL HEIGHT OF WATER COLUMN IN WELL: 12.31'

$$\text{VOLUME OF 1 CASING FULL OF WATER: } \frac{0.27}{(PI \times R^2 \times H)} \text{ CU. FEET} \\ (PI \times R^2 \times H), \text{ IN FT}^3 \quad \frac{0.27}{\pi \times 7.479} = \underline{\underline{2.01}} \text{ GAL.}$$

NO. OF CASINGS FULL PUMPED:

Depth Sampled:

**SAMPLES TAKEN:**

**SHIRES HIRE  
PRESERVATIVE:**

JOB NO. : JCO-104 HUELL NO. : I-1 DATE: 9/29/80, 10/1/82 PUMPED/TESTED BY: RGS/DJSWELL DIA.: 2" Pumping Method: OBSERVATION WELL Weather: Sunny + WarmREFERENCE POINT: TOP OF STEEL CASING REFERENCE ELEVATION: 59.22'INITIAL DEPTH TO WATER: 25.13' INITIAL DEPTH OF OPEN WELL: 57.5'  
INITIAL HEIGHT OF WATER COLUMN IN WELL: 32.37'VOLUME OF 1 CASING FULL OF WATER: 0.71 CU. FEET  
( $\pi \times R^2 \times H$ ), IN FT<sup>3</sup> 0.71  $\times 7.479 = 5.28$  GAL.

CLOCK TIME	TIME ELAPSED	TOTAL VOLUME PUMPED (gallons)	DEPTH TO WATER (feet)	$\Delta h$ ( $h_0 - h$ )	COMMENTS & OBSERVATIONS
1111.45	0	0	25.15	$h_0$	9.29 test begins at 1200
1201.00	1min	2.02	25.13	0.02	
1202.00	2	4.04	25.13	0.02	
1203.00	3	6.06	25.14	0.01	
1204.00	4	8.08	25.13	0.02	
1205.00	5	10.10	25.13	0.02	
1210.00	10	22.00	25.14	0.01	
1215.00	15	33.00	25.13	0.02	
1220.05	20	40.57	25.15	0.00	
1246.20	40	93.59	25.13	0.02	
155.25	60	111.95	25.12	0.03	
1450.25	3hr	344.24	25.13	0.02	
1648.09	5	582.06	25.10	0.05	
2051.50	9	1074.34	25.15	0.00	
0627.00	18.5	2236.14	25.14	0.01	9-30
1241.00	25	2991.62	25.09	0.06	
2354.40	36	4553.93	25.25	-0.10	asc 56 drawdown recovery begins at 0000
0100.00	37	4566.38	25.15	0.00	10/1
0307.00	39	4566.38	25.13	0.02	
1149.05	48	4566.38	25.14	0.01	

NO. OF CASINGS FULL PUMPED: \_\_\_\_\_

Depth Sampled: \_\_\_\_\_

SAMPLES TAKEN: \_\_\_\_\_

PRESERVATIVE: \_\_\_\_\_

JOB NO. : JCO-104 HUELL NO. : I-2 DATE: 9/29, 30, 10/1/87 PUMPED/TESTED BY: RGS/DS

WELL DIA.: 2" Pumping Method: OBSERVATION WELL Weather: Sunny & Warm

REFERENCE POINT: Top of Steel Casing REFERENCE ELEVATION: 57.66

INITIAL DEPTH TO WATER: 24.00 INITIAL DEPTH OF OPEN WELL: 54.50  
INITIAL HEIGHT OF WATER COLUMN IN WELL: .30.50

$$\text{VOLUME OF 1 CASING FULL OF WATER: } \underline{0.67} \text{ CU. FEET}$$

$$(\pi \times R^2 \times H), \text{ IN FT}^3 \quad \underline{0.67} \times 7.479 = \underline{4.98} \text{ GAL.}$$

NO. OF CASTINGS FULL PUMPED:

Depth Sampled:

SAMPLES TAKEN: \_\_\_\_\_

**PRESERVATIVE:**

JOB NO. : JCO-104 H WELL NO. : I-3 DATE: 9/29, 30, 10/1/87 PUMPED/TESTED BY: RCB/OS

WELL DIA.: 2" Pumping Method: OBSERVATION WELL Weather: Sunny + Warm

REFERENCE POINT: Top of Steel Casing REFERENCE ELEVATION: 57.29

INITIAL DEPTH TO WATER: 23.70 INITIAL DEPTH OF OPEN WELL: 55.0  
INITIAL HEIGHT OF WATER COLUMN IN WELL: 30.3

$$\text{VOLUME OF 1 CASING FULL OF WATER: } \frac{0.66}{(PI \times R^2 \times H)} \text{ CU. FEET} \\ (PI \times R^2 \times H), \text{ IN FT}^3 \quad \frac{0.66}{\pi \times 7.479} = 4.94 \text{ GAL.}$$

NO. OF CASINGS FULL PUMPED:

Depth Sampled:

SAMPLES TAKEN: \_\_\_\_\_

PRESERVATIVE: \_\_\_\_\_

**APPENDIX E**

SLUG Test: Well V-1  
9-28-87

Time	ch	H(ft)	Time	ch	H(ft)	Time	ch	H(ft)
10:22:42	7	7.18	10:27:08	7	6.95			
10:22:37	7	7.19	10:27:07	7	6.90			
10:22:32	7	7.12	10:27:06	7	5.97			
10:22:27	7	7.12	10:27:05	7	5.95			
10:22:22	7	7.15	10:27:04	7	5.90			
10:22:17	7	7.15	10:27:03	7	5.87			
10:22:12	7	7.17	10:27:02	7	5.85			
10:22:07	7	7.20	10:27:01	7	5.82			
10:22:02	7	7.22	10:27:00	7	5.77			
10:21:57	7	7.27	10:26:59	7	5.75			
10:21:52	7	7.33	10:26:58	7	5.70			
10:21:50	7	7.32	10:26:57	7	5.65			
10:21:48	7	7.35	10:26:56	7	5.60			
10:21:46	7	7.33	10:26:55	7	5.55			
10:21:44	7	7.37	10:26:54	7	5.50			
10:21:42	7	7.40	10:26:53	7	5.42			
10:21:40	7	7.42	10:26:52	7	5.32			
10:21:38	7	7.45	10:26:51	7	5.25			
10:21:36	7	7.47	10:26:50	7	5.12			
10:21:34	7	7.50	10:26:49	7	5.00			
10:21:32	7	7.52	10:25 HR3 87/09/15 #10			10:28:39	7	6.95
10:21:30	7	7.57	Begin reverse slug test			10:28:34	7	6.92
10:21:28	7	7.60	STATION ID = 91			10:28:29	7	6.92
10:21:26	7	7.62	10:25:52	7	7.02	10:28:24	7	6.99
10:21:24	7	7.67	10:25:42	7	7.02	10:28:19	7	6.98
10:21:22	7	7.72	10:25:32	7	7.02	10:28:14	7	6.97
10:21:20	7	7.73	10:25:22	7	7.02	10:28:09	7	6.95
10:21:18	7	7.80	10:25:12	7	7.02	10:28:04	7	6.92
10:21:16	7	7.85	10:25:02	7	7.02	10:27:59	7	6.89
10:21:14	7	7.90	10:24:52	7	7.02	10:27:54	7	6.77
10:21:12	7	7.95	10:24:42	7	7.02	10:27:49	7	6.72
10:21:11	7	7.97	10:24:32	7	7.02	10:27:47	7	6.72
10:21:10	7	8.02	10:24:22	7	7.02	10:27:45	7	6.70
10:21:09	7	8.05	10:24:17	7	7.05	10:27:43	7	6.67
10:21:08	7	8.07	10:24:12	7	7.05	10:27:41	7	6.65
10:21:07	7	8.10	10:24:07	7	7.05	10:27:39	7	6.62
10:21:06	7	8.15	10:24:02	7	7.05	10:27:37	7	6.60
10:21:05	7	8.17	10:23:57	7	7.05	10:27:35	7	6.57
10:21:04	7	8.20	10:23:52	7	7.05	10:27:33	7	6.55
10:21:03	7	8.25	10:23:47	7	7.05	10:27:31	7	6.52
10:21:02	7	8.27	10:23:42	7	7.05	10:27:29	7	6.50
10:21:01	7	8.32	10:23:37	7	7.05	10:27:27	7	6.47
10:21:00	7	8.37	10:23:32	7	7.05	10:27:25	7	6.42
10:20:59	7	8.42	10:23:27	7	7.05	10:27:23	7	6.40
10:20:58	7	8.47	10:23:22	7	7.05	10:27:21	7	6.35
10:20:57	7	8.52	10:23:17	7	7.05	10:27:19	7	6.32
10:20:56	7	8.57	10:23:12	7	7.05	10:27:17	7	6.27
10:20:55	7	8.65	10:23:07	7	7.07	10:27:15	7	6.22
10:20:54	7	8.72	10:23:02	7	7.07	10:27:13	7	6.17
10:20:53	7	9.22	10:22:57	7	7.07	10:27:11	7	6.12
10:20:52	7	9.32	10:22:52	7	7.07	10:27:09	7	6.07
10:06 428 87/09/15 #10			10:22:47	7	7.10			

Begin slug test

			11:01:05	7	6.77
10:57:48	7	6.97	11:01:03	7	6.77
10:57:43	7	6.97	11:01:02	7	6.75
10:57:38	7	6.97	11:01:01	7	6.75
10:57:33	7	6.97	11:01:00	7	6.75
10:57:28	7	6.97	11:00:59	7	6.75
10:57:23	7	6.97-	11:00:58	7	6.72
10:57:18	7	7.00	11:00:57	7	6.72
10:57:13	7	7.00	11:00:56	7	6.70
10:57:08	7	7.00	11:00:55	7	6.70
10:57:06	7	7.00	11:00:54	7	6.67
10:57:04	7	7.00	11:00:53	7	6.65
10:57:02	7	7.00-	11:00:52	7	6.62
10:57:00	7	7.02	11:00:51	7	6.60
10:56:58	7	7.02	11:00:50	7	6.57
10:56:56	7	7.02	11:00:49	7	6.52
10:56:54	7	7.02	11:00:48	7	6.45
10:56:52	7	7.02	11:00:47	7	6.32
10:56:50	7	7.02	11:00:46	7	6.17
10:56:48	7	7.02	11:00:45	7	6.02
10:56:46	7	7.02	11:00:44	7	5.87
10:56:44	7	7.05	11:00:43	7	5.82
10:56:42	7	7.05	11:00 HRS 87/09/15 #10		6.90
10:56:40	7	7.05			6.90
10:56:38	7	7.05	Begin reverse		6.90
10:56:36	7	7.05			6.90
10:56:34	7	7.07	STATION ID = 02		6.90
10:56:32	7	7.07	11:00:18	7	6.95
10:56:30	7	7.07	11:00:08	7	6.95
10:56:28	7	7.10	10:59:58	7	6.95
10:56:27	7	7.10	10:59:48	7	6.95
10:56:26	7	7.10	10:59:38	7	6.95
10:56:25	7	7.10	10:59:33	7	6.95
10:56:24	7	7.10-	10:59:28	7	6.95
10:56:23	7	7.12	10:59:23	7	6.95
10:56:22	7	7.12	10:59:18	7	6.95
10:56:21	7	7.12	10:59:13	7	6.95
10:56:20	7	7.12	10:59:08	7	6.95
10:56:19	7	7.15	10:58:58	7	6.95
10:56:18	7	7.15	10:58:53	7	6.95
10:56:17	7	7.15	10:58:48	7	6.95
10:56:16	7	7.17	10:58:43	7	6.95
10:56:15	7	7.17	10:58:38	7	6.95
10:56:14	7	7.17	10:58:33	7	6.95
10:56:13	7	7.20	10:58:28	7	6.95
10:56:12	7	7.20	10:58:23	7	6.95
10:56:11	7	7.25	10:58:18	7	6.97
10:56:10	7	7.12	10:58:13	7	6.97
10:56:09	7	7.15	10:58:08	7	6.97
10:56:08	7	9.35	10:58:03	7	6.97
10:46 HRS 87/09/15 #10			10:57:58	7	6.97
			10:57:53	7	6.97
			10:57:48	7	6.97
			10:57:43	7	6.97
			10:57:38	7	6.97
			10:57:33	7	6.97
			10:57:28	7	6.97
			10:57:23	7	6.97
			10:57:18	7	6.97
			10:57:13	7	6.97
			10:57:08	7	6.97
			10:57:06	7	6.97
			10:57:04	7	6.97
			10:57:02	7	6.97
			10:57:00	7	6.97
			10:56:58	7	6.97
			10:56:56	7	6.97
			10:56:54	7	6.97
			10:56:52	7	6.97
			10:56:50	7	6.97
			10:56:48	7	6.97
			10:56:46	7	6.97
			10:56:44	7	6.97
			10:56:42	7	6.97
			10:56:40	7	6.97
			10:56:38	7	6.97
			10:56:36	7	6.97
			10:56:34	7	6.97
			10:56:32	7	6.97
			10:56:30	7	6.97
			10:56:28	7	6.97
			10:56:27	7	6.97
			10:56:26	7	6.97
			10:56:25	7	6.97
			10:56:24	7	6.97
			10:56:23	7	6.97
			10:56:22	7	6.97
			10:56:21	7	6.97
			10:56:20	7	6.97
			10:56:19	7	6.97
			10:56:18	7	6.97
			10:56:17	7	6.97
			10:56:16	7	6.97
			10:56:15	7	6.97
			10:56:14	7	6.97
			10:56:13	7	6.97
			10:56:12	7	6.97
			10:56:11	7	6.97
			10:56:10	7	6.97
			10:56:09	7	6.97
			10:56:08	7	6.97
			10:56:07	7	6.97
			10:56:06	7	6.97
			10:56:05	7	6.97
			10:56:04	7	6.97
			10:56:03	7	6.97
			10:56:02	7	6.97
			10:56:01	7	6.97
			10:56:00	7	6.97
			10:55:59	7	6.97
			10:55:58	7	6.97
			10:55:57	7	6.97
			10:55:56	7	6.97
			10:55:55	7	6.97
			10:55:54	7	6.97
			10:55:53	7	6.97
			10:55:52	7	6.97
			10:55:51	7	6.97
			10:55:50	7	6.97
			10:55:49	7	6.97
			10:55:48	7	6.97
			10:55:47	7	6.97
			10:55:46	7	6.97
			10:55:45	7	6.97
			10:55:44	7	6.97
			10:55:43	7	6.97
			10:55:42	7	6.97
			10:55:41	7	6.97
			10:55:40	7	6.97
			10:55:39	7	6.97
			10:55:38	7	6.97
			10:55:37	7	6.97
			10:55:36	7	6.97
			10:55:35	7	6.97
			10:55:34	7	6.97
			10:55:33	7	6.97
			10:55:32	7	6.97
			10:55:31	7	6.97
			10:55:30	7	6.97
			10:55:29	7	6.97
			10:55:28	7	6.97
			10:55:27	7	6.97
			10:55:26	7	6.97
			10:55:25	7	6.97
			10:55:24	7	6.97
			10:55:23	7	6.97
			10:55:22	7	6.97
			10:55:21	7	6.97
			10:55:20	7	6.97
			10:55:19	7	6.97
			10:55:18	7	6.97
			10:55:17	7	6.97
			10:55:16	7	6.97
			10:55:15	7	6.97
			10:55:14	7	6.97
			10:55:13	7	6.97
			10:55:12	7	6.97
			10:55:11	7	6.97
			10:55:10	7	6.97
			10:55:09	7	6.97
			10:55:08	7	6.97
			10:55:07	7	6.97
			10:55:06	7	6.97
			10:55:05	7	6.97
			10:55:04	7	6.97
			10:55:03	7	6.97
			10:55:02	7	6.97
			10:55:01	7	6.97
			10:55:00	7	6.97
			10:54:59	7	6.97
			10:54:58	7	6.97
			10:54:57	7	6.97
			10:54:56	7	6.97
			10:54:55	7	6.97
			10:54:54	7	6.97
			10:54:53	7	6.97
			10:54:52	7	6.97
			10:54:51	7	6.97
			10:54:50	7	6.97
			10:54:49	7	6.97
			10:54:48	7	6.97
			10:54:47	7	6.97
			10:54:46	7	6.97
			10:54:45	7	6.97
			10:54:44	7	6.97
			10:54:43	7	6.97
			10:54:42	7	6.97
			10:54:41	7	6.97
			10:54:40	7	6.97
			10:54:39	7	6.97
			10:54:38	7	6.97
			10:54:37	7	6.97
			10:54:36	7	6.97
			10:54:35	7	6.97
			10:54:34	7	6.97
			10:54:33	7	6.97
			10:54:32	7	6.97
			10:54:31	7	6.97
			10:54:30	7	6.97
			10:54:29	7	6.97
			10:54:28	7	6.97
			10:54:27	7	6.97
			10:54:26	7	6.97
			10:54:25	7	6.97
			10:54:24	7	6.97
			10:54:23	7	6.97
			10:54:22	7	6.97
			10:54:21	7	6.97
			10:54:20	7	6.97
			10:54:19	7	6.97
			10:54:18	7	6.97
			10:54:17	7	6.97
			10:54:16	7	6.97
			10:54:15	7	6.97
			10:54:14	7	6.97
			10:54:13	7	6.97
			10:54:12	7	6.97
			10:54:11	7	6.97
			10:54:10	7	6.97
			10:54:09	7	6.97
			10:54:08	7	6.97
			10:54:07	7	6.97
			10:54:06	7	6.97
			10:54:05	7	6.97
			10:54:04	7	6.97
			10:54:03	7	6.97
			10:54:02	7	6.97
			10:54:01	7	6.97
			10:54:00	7	6.97
			10:53:59	7	6.97
			10:53:58	7	6.97
			10:53:57	7	6.97
			10:53:56	7	6.97
			10:53:55	7	6.97
			10:53:54	7	6.97
			10:53:53	7	6.97
			10:53:52	7	6.97
			10:53:51	7	6.97
			1		

09:54:04	7	6.20	10:02:09	7	6.00
09:53:59	7	6.20	10:01:39	7	6.00
09:53:54	7	6.20	10:01:09	7	6.00
09:53:49	7	6.20	10:00:39	7	6.02
09:53:44	7	6.20	10:00:29	7	6.02
09:53:39	7	6.20	10:00:19	7	6.02
09:53:34	7	6.22	10:00:09	7	6.02
09:53:29	7	6.22	09:59:59	7	6.02
09:53:24	7	6.22	09:59:49	7	6.02
09:53:19	7	6.22	09:59:39	7	6.02
09:53:14	7	6.22	09:59:29	7	6.05
09:53:09	7	6.25	09:59:19	7	6.05
09:53:07	7	6.25	09:59:09	7	6.05
09:53:05	7	6.25	09:58:59	7	6.05
09:53:03	7	6.25	09:58:49	7	6.05
09:53:01	7	6.25	09:58:39	7	6.05
09:52:59	7	6.25	09:58:29	7	6.05
09:52:57	7	6.25	09:58:19	7	6.05
09:52:55	7	6.25	09:58:09	7	6.07
09:52:53	7	6.25	09:57:59	7	6.07
09:52:51	7	6.25	09:57:49	7	6.07
09:52:49	7	6.25	09:57:39	7	6.07
09:52:47	7	6.27	09:57:29	7	6.07
09:52:45	7	6.27	09:57:19	7	6.07
09:52:43	7	6.27	09:57:09	7	6.10
09:52:41	7	6.27	09:56:59	7	6.10
09:52:39	7	6.27	09:56:49	7	6.10
09:52:37	7	6.27	09:56:39	7	6.10
09:52:35	7	6.27	09:56:29	7	6.10
09:52:33	7	6.27	09:56:19	7	6.12
09:52:31	7	6.27	09:56:09	7	6.12
09:52:29	7	6.27	09:55:59	7	6.12
09:52:28	7	6.30	09:55:49	7	6.12
09:52:27	7	6.30	09:55:39	7	6.12
09:52:26	7	6.30	09:55:34	7	6.12
09:52:25	7	6.30	09:55:29	7	6.15
09:52:24	7	6.30	09:55:24	7	6.15
09:52:23	7	6.30	09:55:19	7	6.15
09:52:22	7	6.30	09:55:14	7	6.15
09:52:21	7	6.30	09:55:09	7	6.15
09:52:20	7	6.30	09:55:04	7	6.15
09:52:19	7	6.30	09:54:59	7	6.15
09:52:18	7	6.30	09:54:54	7	6.15
09:52:17	7	6.30	09:54:49	7	6.15
09:52:16	7	6.30	09:54:44	7	6.17
09:52:15	7	6.30	09:54:39	7	6.17
09:52:14	7	6.30	09:54:34	7	6.17
09:52:13	7	6.27	09:54:29	7	6.17
09:52:12	7	6.27	09:54:24	7	6.17
09:52:11	7	6.92	09:54:19	7	6.17
09:52:10	7	6.93	09:54:14	7	6.17
09:52:09	7	6.11	09:54:09	7	6.17
					STATION ID = 03
			10:06:39	7	5.95
			10:06:09	7	5.95
			10:05:39	7	5.95
			10:05:09	7	5.95
			10:04:39	7	5.95
			10:04:09	7	5.97
			10:03:39	7	5.97
			10:03:09	7	5.97
			10:02:39	7	5.97

11:11:41	7	9.17	11:15:17	7	8.45	11:18:20	7	9.00
11:11:36	7	9.29	11:15:16	7	8.42	11:18:15	7	9.00
11:11:31	7	9.29	11:15:15	7	8.40	11:18:10	7	9.00
11:11:26	7	9.28	11:15:14	7	8.37	11:18:05	7	9.00
11:11:21	7	9.22	11:15:13	7	8.32	11:18:00	7	9.00
11:11:16	7	9.22	11:15:12	7	8.30	11:17:55	7	9.00
11:11:11	7	9.25	11:15:11	7	8.27	11:17:50	7	9.00
11:11:06	7	9.25	11:15:10	7	8.25	11:17:45	7	9.00
11:11:01	7	9.27	11:15:09	7	8.20	11:17:40	7	9.00
11:10:59	7	9.27	11:15:08	7	8.15	11:17:35	7	9.00
11:10:57	7	9.27	11:15:07	7	8.12	11:17:30	7	9.00
11:10:55	7	9.30	11:15:06	7	8.07	11:17:25	7	8.97
11:10:53	7	9.38	11:15:05	7	8.02	11:17:20	7	8.97
11:10:51	7	9.38	11:15:04	7	7.97	11:17:15	7	8.97
11:10:49	7	9.32	11:15:03	7	7.93	11:17:10	7	8.97
11:10:47	7	9.32	11:15:02	7	7.82	11:17:05	7	8.97
11:10:45	7	9.35	11:15:01	7	8.00	11:17:00	7	8.97
11:10:43	7	9.35	11:15:00	7	8.92	11:16:55	7	8.97
11:10:41	7	9.37	11:14 HRS 87/09/15 #10			11:16:50	7	8.95
11:10:39	7	9.37	Begin reverse slug			11:16:45	7	8.95
11:10:37	7	9.40	STATION ID = 04			11:16:40	7	8.95
11:10:35	7	9.42	11:14:41	7	9.10	11:16:35	7	8.95
11:10:33	7	9.42	11:14:31	7	9.10	11:16:30	7	8.92
11:10:31	7	9.45	11:14:21	7	9.10	11:16:25	7	8.92
11:10:29	7	9.47	11:14:11	7	9.10	11:16:20	7	8.90
11:10:27	7	9.50	11:14:01	7	9.10	11:16:15	7	8.90
11:10:25	7	9.52	11:13:51	7	9.10	11:16:10	7	8.90
11:10:23	7	9.55	11:13:41	7	9.10	11:16:05	7	8.87
11:10:21	7	9.60	11:13:31	7	9.12	11:16:00	7	8.85
11:10:20	7	9.60	11:13:26	7	9.12	11:15:56	7	8.85
11:10:19	7	9.62	11:13:21	7	9.12	11:15:54	7	8.82
11:10:18	7	9.65	11:13:16	7	9.12	11:15:52	7	8.82
11:10:17	7	9.67	11:13:11	7	9.12	11:15:50	7	8.80
11:10:16	7	9.70	11:13:06	7	9.12	11:15:48	7	8.80
11:10:15	7	9.70	11:13:01	7	9.12	11:15:46	7	8.80
11:10:14	7	9.72	11:12:56	7	9.12	11:15:44	7	8.77
11:10:13	7	9.77	11:12:51	7	9.12	11:15:42	7	8.77
11:10:12	7	9.80	11:12:46	7	9.12	11:15:40	7	8.75
11:10:11	7	9.82	11:12:41	7	9.12	11:15:38	7	8.72
11:10:10	7	9.85	11:12:36	7	9.12	11:15:36	7	8.72
11:10:09	7	9.90	11:12:31	7	9.15	11:15:34	7	8.70
11:10:08	7	9.92	11:12:26	7	9.15	11:15:32	7	8.67
11:10:07	7	9.97	11:12:21	7	9.15	11:15:30	7	8.65
11:10:06	7	10.00	11:12:16	7	9.15	11:15:28	7	8.62
11:10:05	7	10.05	11:12:11	7	9.15	11:15:26	7	8.60
11:10:04	7	10.12	11:12:06	7	9.15	11:15:24	7	8.57
11:10:03	7	10.27	11:12:01	7	9.15	11:15:22	7	8.52
11:10:02	7	11.22	11:11:56	7	9.17	11:15:20	7	8.50
11:10:01	7	12.45	11:11:51	7	9.17	11:15:19	7	8.47
11:03 HRS 87/09/15 #10			11:11:46	7	9.17	11:15:18	7	8.45
Begin slug								

11:44:32	7	8.55	11:54:02	7	7.65		
11:44:27	7	8.57	11:53:32	7	7.67		
11:44:22	7	8.57	11:53:02	7	7.67		
11:44:17	7	8.60	11:52:32	7	7.70		
11:44:12	7	8.62	11:52:02	7	7.72		
11:44:07	7	8.65	11:51:32	7	7.75		
11:44:02	7	8.67	11:51:02	7	7.80		
11:43:57	7	8.70	11:50:52	7	7.80		
11:43:52	7	8.72	11:50:42	7	7.80		
11:43:47	7	8.75	11:50:32	7	7.82		
11:43:42	7	8.77	11:50:22	7	7.82		
11:43:37	7	8.80	11:50:12	7	7.85		
11:43:32	7	8.85	11:50:02	7	7.85		
11:43:30	7	8.85	11:49:52	7	7.85		
11:43:28	7	8.85	11:49:42	7	7.87		
11:43:26	7	8.87	11:49:32	7	7.87		
11:43:24	7	8.87	11:49:22	7	7.90		
11:43:22	7	8.90	11:49:12	7	7.92		
11:43:20	7	8.90	11:49:02	7	7.92		
11:43:18	7	8.92	11:48:52	7	7.95		
11:43:16	7	8.92	11:48:42	7	7.95		
11:43:14	7	8.95	11:48:32	7	7.97		
11:43:12	7	8.97	11:48:22	7	7.97		
11:43:10	7	8.97	11:48:12	7	8.00		
11:43:08	7	9.00	11:48:02	7	8.02		
11:43:06	7	9.02	11:47:52	7	8.02		
11:43:04	7	9.02	11:47:42	7	8.03		
11:43:02	7	9.05	11:47:32	7	8.07		
11:43:00	7	9.05	11:47:22	7	8.10		
11:42:58	7	9.07	11:47:12	7	8.10		
11:42:56	7	9.10	11:47:02	7	8.12		
11:42:54	7	9.12	11:46:52	7	8.15		
11:42:52	7	9.12	11:46:42	7	8.17		
11:42:51	7	9.15	11:46:32	7	8.20		
11:42:50	7	9.15	11:46:22	7	8.22		
11:42:49	7	9.17	11:46:12	7	8.25		
11:42:48	7	9.17	11:46:02	7	8.27		
11:42:47	7	9.20	11:45:57	7	8.27		
11:42:46	7	9.20	11:45:52	7	8.27		
11:42:45	7	9.22	11:45:47	7	8.30		
11:42:44	7	9.22	11:45:42	7	8.32		
11:42:43	7	9.25	11:45:37	7	8.32		
11:42:42	7	9.25	11:45:32	7	8.35		
11:42:41	7	9.27	11:45:27	7	8.35		
11:42:40	7	9.27	11:45:22	7	8.37		
11:42:39	7	9.30	11:45:17	7	8.40		
11:42:38	7	9.32	11:45:12	7	8.40		
11:42:37	7	9.35	11:45:07	7	8.42		
11:42:36	7	9.37	11:45:02	7	8.42		
11:42:35	7	9.35	11:44:57	7	8.45		
11:42:34	7	9.22	11:44:52	7	8.47		
11:42:33	7	10.47	11:44:47	7	8.50		
11:42:32	7	9.55	11:44:42	7	8.50		
11:00 HRS 87/09/15 #10			11:44:37	7	8.52		
					STATION ID = 05		
					12:02:32	7	7.45
					12:02:02	7	7.45
					12:01:32	7	7.45
					12:01:02	7	7.47
					12:00:32	7	7.47
					12:00:02	7	7.47
					11:59:32	7	7.50
					11:59:02	7	7.50
					11:58:32	7	7.52
					11:58:02	7	7.52
					11:57:32	7	7.52
					11:57:02	7	7.52
					11:56:32	7	7.55
					11:56:02	7	7.55
					11:55:32	7	7.60
					11:55:02	7	7.60
					11:54:32	7	7.62

Begin slug

STATION ID = 96

11:29:04 7 8.62  
 11:28:59 7 8.62  
 11:28:57 7 8.62  
 11:28:55 7 8.62  
 11:28:53 7 8.62  
 11:28:51 7 8.62  
 11:28:49 7 8.62  
 11:28:47 7 8.62  
 11:28:45 7 8.62  
 11:28:43 7 8.62  
 11:28:41 7 8.62  
 11:28:39 7 8.62  
 11:28:37 7 8.62  
 11:28:35 7 8.62  
 11:28:33 7 8.62  
 11:28:31 7 8.62  
 11:28:29 7 8.62  
 11:28:27 7 8.62  
 11:28:25 7 8.62  
 11:28:23 7 8.62  
 11:28:21 7 8.62  
 11:28:19 7 8.65  
 11:28:18 7 8.62  
11:28:17 7 8.62  
 11:28:16 7 8.62  
 11:28:15 7 8.65  
 11:28:14 7 8.65  
 11:28:13 7 8.65  
 11:28:12 7 8.65  
 11:28:11 7 8.65  
 11:28:10 7 8.65  
 11:28:09 7 8.65  
 11:28:08 7 8.67  
 11:28:07 7 8.65  
 11:28:06 7 8.70  
 11:28:05 7 8.75  
 11:28:04 7 8.77  
 11:28:03 7 8.77  
 11:28:02 7 8.87  
 11:28:01 7 9.07  
11:28:00 7 9.27  
 11:27:59 7 10.62  
 11:29 HRS 87/09/15 #10

Begin reverse slug

Begin slug test

STATION ID = 07

12:38:15 7 8.58  
 12:38:18 7 8.52  
 12:38:05 7 8.58  
 12:38:00 7 8.58  
 12:29:55 7 8.58  
 12:29:50 7 8.58  
 12:29:45 7 8.58  
 12:29:40 7 8.58  
 12:29:35 7 8.58  
 12:29:30 7 8.58  
 12:29:25 7 8.58  
 12:29:20 7 8.58  
 12:29:15 7 8.58  
 12:29:10 7 8.58  
 12:29:05 7 8.58  
 12:29:00 7 8.58  
 12:28:58 7 8.58  
 12:28:56 7 8.58  
 12:28:54 7 8.58  
 12:28:52 7 8.47  
 12:28:50 7 8.47  
 12:28:48 7 8.47  
 12:28:46 7 8.47  
 12:28:44 7 8.47  
 12:28:42 7 8.47  
 12:28:40 7 8.47  
 12:28:38 7 8.47  
 12:28:36 7 8.47  
 12:28:34 7 8.47  
 12:28:32 7 8.45  
 12:28:30 7 8.45  
 12:28:28 7 8.45  
 12:28:26 7 8.45  
 12:28:24 7 8.42  
 12:28:22 7 8.42  
 12:28:20 7 8.42  
 12:28:19 7 8.40  
 12:28:18 7 8.40  
 12:28:17 7 8.40  
 12:28:16 7 8.37  
 12:28:15 7 8.37  
 12:28:14 7 8.35  
 12:28:13 7 8.35  
 12:28:12 7 8.32  
 12:28:11 7 8.30  
 12:28:10 7 8.27  
 12:28:09 7 8.22  
 12:28:08 7 8.17  
 12:28:07 7 8.12  
 12:28:06 7 8.05  
 12:28:05 7 7.97  
 12:28:04 7 7.85  
 12:28:03 7 7.72  
 12:28:02 7 7.55  
 12:28:01 7 7.49  
 12:28:00 7 6.67  
 12:27 HRS 87/09/15 #10

Begin slug test

12:27 HRS 87/09/15 #10  
Begin reverse slug

10:42:53	7	6.55	10:45:45	7	6.52
10:42:53	7	6.55	10:45:49	7	6.52
10:42:48	7	6.55	10:45:35	7	6.52
10:42:43	7	6.55	10:45:30	7	6.52
10:42:38	7	6.55	10:45:25	7	6.52
10:42:33	7	6.55	10:45:20	7	6.52
10:42:28	7	6.55	10:45:18	7	6.52
10:42:23	7	6.55	10:45:16	7	6.52
10:42:18	7	6.55	10:45:14	7	6.52
10:42:13	7	6.55	10:45:12	7	6.52
10:42:08	7	6.55	10:45:10	7	6.52
10:42:03	7	6.55	10:45:08	7	6.52
10:41:58	7	6.55	10:45:06	7	6.52
10:41:53	7	6.55	10:45:04	7	6.52
10:41:48	7	6.55	10:45:02	7	6.52
10:41:43	7	6.55	10:45:00	7	6.52
10:41:38	7	6.55	10:44:58	7	6.52
10:41:33	7	6.55	10:44:56	7	6.52
10:41:34	7	6.55	10:44:54	7	6.52
10:41:32	7	6.55	10:44:52	7	6.52
10:41:30	7	6.55	10:44:50	7	6.52
10:41:28	7	6.55	10:44:48	7	6.52
10:41:26	7	6.55	10:44:46	7	6.52
10:41:24	7	6.55	10:44:44	7	6.52
10:41:22	7	6.55	10:44:42	7	6.52
10:41:20	7	6.55	10:44:40	7	6.55
10:41:18	7	6.55	10:44:38	7	6.55
10:41:16	7	6.55	10:44:37	7	6.52
10:41:14	7	6.55	10:44:36	7	6.55
10:41:12	7	6.55	10:44:35	7	6.55
10:41:10	7	6.55	10:44:34	7	6.57
10:41:08	7	6.55	10:44:33	7	6.55
10:41:06	7	6.55	10:44:32	7	6.52
10:41:04	7	6.55	10:44:31	7	6.59
10:41:02	7	6.55	10:44:30	7	6.52
10:41:00	7	6.55	10:44:29	7	6.58
10:40:58	7	6.55	10:44:28	7	6.55
10:40:57	7	6.55	10:44:27	7	6.57
10:40:56	7	6.55	10:44:26	7	6.42
10:40:55	7	6.55	10:44:25	7	6.32
10:40:54	7	6.55	10:44:24	7	6.45
10:40:53	7	6.55	10:44:23	7	6.32
10:40:52	7	6.55	10:44:22	7	7.05
10:40:51	7	6.57	10:44:21	7	6.75
10:40:50	7	6.57	10:44:20	7	5.70
10:40:49	7	6.55	10:43:53	87/09/15 #10	
10:40:48	7	6.52	Begin reverse slug		
10:40:47	7	6.50	STATION ID = 98	STATION ID = 98	
10:40:46	7	6.55	10:43:48	7	6.55
10:40:45	7	6.60	10:43:43	7	6.55
10:40:44	7	6.67	10:43:38	7	6.55
10:40:43	7	6.67	10:43:33	7	6.55
10:40:42	7	6.52	10:43:28	7	6.55
10:40:41	7	6.27	10:43:23	7	6.55
10:40:40	7	6.11	10:43:18	7	6.55
10:40:39	7	6.10	10:43:13	7	6.55
10:40:38	7	6.15	10:43:08	7	6.55
10:40:34	87/09/15 #10		10:43:03	7	6.55
Begin slug test			10:45:52	7	6.52

STATION ID = 09

12:18:49 7 9.32  
12:18:38 7 9.32  
12:18:36 7 9.32  
12:18:34 7 9.32  
12:18:32 7 9.32  
12:18:30 7 9.32  
12:18:28 7 9.32  
12:18:26 7 9.32  
12:18:24 7 9.32  
12:18:22 7 9.32  
12:18:21 7 9.32  
12:18:20 7 9.32  
12:18:19 7 9.32  
12:18:18 7 9.32  
12:18:17 7 9.32  
12:18:16 7 9.32  
12:18:15 7 9.32  
12:18:14 7 9.32  
12:18:13 7 9.32  
12:18:12 7 9.32  
12:18:11 7 9.32  
12:18:10 7 9.32  
12:18:09 7 9.32  
12:18:08 7 9.32  
12:18:07 7 9.32  
12:18:06 7 9.32  
12:18:05 7 9.29  
12:18:04 7 9.17  
12:18:03 7 9.15  
12:18:02 7 11.00  
12:02 HRS 87/09/15 #10

Begin slug test

STATION ID = 09

12:20:09 7 9.32  
12:20:07 7 9.32  
12:20:05 7 9.32  
12:20:03 7 9.32  
12:20:02 7 9.32  
12:20:01 7 9.32  
12:20:00 7 9.32  
12:19:59 7 9.32  
12:19:58 7 9.32  
12:19:57 7 9.32  
12:19:56 7 9.32  
12:19:55 7 9.32  
12:19:54 7 9.32  
12:19:53 7 9.32  
12:19:52 7 9.32  
12:19:51 7 9.32  
12:19:50 7 9.32  
12:19:49 7 9.29  
12:19:48 7 9.17  
12:19:47 7 9.32  
12:19:46 7 9.57  
12:19:45 7 9.65  
12:19:44 7 9.22  
12:19:43 7 8.85  
12:18 HRS 87/09/15 #10

Begin reverse slug test

12:39 HRS 07/09/15 #10

STATION ID = 10

12:39:33 7 9.65  
12:39:31 7 9.65  
12:39:29 7 9.65  
12:39:27 7 9.65  
12:39:25 7 9.65  
12:39:23 7 9.65  
12:39:21 7 9.65  
12:39:19 7 9.65  
12:39:17 7 9.65  
12:39:15 7 9.65  
12:39:13 7 9.65  
12:39:11 7 9.65  
12:39:09 7 9.65  
12:39:07 7 9.65  
12:39:05 7 9.65  
12:39:03 7 9.65  
12:39:01 7 9.65  
12:38:59 7 9.65  
12:38:57 7 9.62  
12:38:55 7 9.67  
12:38:53 7 9.67  
12:38:52 7 9.62  
12:38:51 7 9.60  
12:38:50 7 9.62  
12:38:49 7 9.70  
12:38:48 7 9.75  
12:38:47 7 9.72  
12:38:46 7 9.62  
12:38:45 7 9.50  
12:38:44 7 9.52  
12:38:43 7 9.70  
12:38:42 7 9.90  
12:38:41 7 9.87  
12:38:40 7 9.60  
12:38:39 7 9.25  
12:38:38 7 9.25  
12:38:37 7 9.72  
12:38:36 7 10.30  
12:38:35 7 10.32  
12:38:34 7 9.52  
12:38:33 7 8.60  
12:38 HRS 07/09/15 #10

STATION ID = 10

12:38:04 7 9.65  
12:38:02 7 9.65  
12:38:00 7 9.65  
12:37:58 7 9.65  
12:37:56 7 9.65  
12:37:54 7 9.65  
12:37:52 7 9.65  
12:37:50 7 9.65  
12:37:48 7 9.65  
12:37:46 7 9.67  
12:37:45 7 9.67  
12:37:44 7 9.65  
12:37:43 7 9.62  
12:37:42 7 9.62  
12:37:41 7 9.65  
12:37:40 7 9.70  
12:37:39 7 9.72  
12:37:38 7 9.70  
12:37:37 7 9.62  
12:37:36 7 9.55  
12:37:35 7 9.55  
12:37:34 7 9.67  
12:37:33 7 9.85  
12:37:32 7 9.90  
12:37:31 7 9.75  
12:37:30 7 9.47  
12:37:29 7 9.12  
12:37:28 7 9.30  
12:37:27 7 11.12  
12:37:26 7 9.65  
12:38 HRS 07/09/15 #10

Begin slug test


Begin reverse slug test

Data for Slug Injection/Withdrawal Test

Well Name: V1 Date of Test: 9/15/87  
Well Number: 1  
Change in Vol. of Water = 0.04 cu.ft.  
Effective Radius of Well = 0.33 feet  
Radius of Casing( $r_c$ ) over Water Level Decline = 0.08 feet

Entry No.	Time(t) (min.)	Head (ft.)	H (ft.)	H/H0
1		7.000		
2	0.000	8.720	1.720	1.000
3	0.083	8.420	1.420	0.826
4	0.200	8.150	1.150	0.669
5	0.367	7.900	0.900	0.523
6	0.537	7.600	0.600	0.349
7	0.800	7.400	0.400	0.233
8	1.000	7.300	0.300	0.174
9	1.250	7.200	0.200	0.116
10	1.750	7.100	0.100	0.058
11	2.300	7.050	0.050	0.029

SLUG TEST DATA (V1)



o - Data

+ - Type Curve

Slug Test:  $\alpha = -8.0$

SOLUTION

Transmissivity =  $6.112E-02$  ft.<sup>2</sup>/min.


Storativity =  $5.877E-10$

Data for Slug Injection/Withdrawal Test

Well Name: V2 Date of Test: 9/15/87  
Well Number: 1  
Change in Vol.of Water = 0.04 cu.ft.  
Effective Radius of Well = 0.33 feet  
Radius of Casing( $r_c$ ) over Water Level Decline = 0.20 feet

Entry No.	Time(t) (min.)	Head (ft.)	H (ft.)	H/H <sub>0</sub>
1		6.920		
2	0.000	7.250	0.330	1.000
3	0.017	7.200	0.280	0.848
4	0.050	7.170	0.250	0.758
5	0.150	7.120	0.200	0.606
6	0.220	7.100	0.180	0.545
7	0.320	7.070	0.150	0.455
8	0.580	7.020	0.100	0.303
9	0.850	7.000	0.080	0.242
10	1.200	6.970	0.050	0.152
11	2.200	6.950	0.030	0.091

SLUG TEST DATA (V2)



SOLUTION


Transmissivity = 6.951E-02 ft.<sup>2</sup>/min.  
Storativity = 3.673E-02

Data for Slug Injection/Withdrawal Test

Well Name: U3 Date of Test: 9/15/87  
Well Number: 1  
Change in Vol. of Water = 0.09 cu.ft.  
Effective Radius of Well = 0.42 feet  
Radius of Casing( $r_c$ ) over Water Level Decline = 0.29 feet

Entry No.	Time(t) (min.)	Head (ft.)	H (ft.)	H/H <sub>0</sub>
1		5.850		
2	0.000	6.300	0.450	1.000
3	0.250	6.270	0.420	0.933
4	0.500	6.250	0.400	0.889
5	1.420	6.200	0.350	0.778
6	1.920	6.170	0.320	0.711
7	2.580	6.150	0.300	0.667
8	3.330	6.120	0.270	0.600
9	4.250	6.100	0.250	0.556
10	6.080	6.050	0.200	0.444
11	8.580	6.000	0.150	0.333
12	12.060	5.950	0.100	0.222

SLUG TEST DATA (V3)



o - Data

+ - Type Curve  
Slug Test: alpha = -4.0

SOLUTION


Transmissivity = 2.984E-02 ft.<sup>2</sup>/min.  
Storativity = 4.768E-05

Data for Slug Injection/Withdrawal Test

Well Name: V4 Date of Test: 9/15/87  
Well Number: 1  
Change in Vol. of Water = 0.10 cu.ft.  
Effective Radius of Well = 0.42 feet  
Radius of Casing( $r_c$ ) over Water Level Decline = 0.17 feet

Entry No.	Time(t) (min.)	Head (ft.)	H (ft.)	H/H <sub>0</sub>
1		9.050		
2	0.000	10.270	1.220	1.000
3	0.017	10.120	1.070	0.877
4	0.050	10.000	0.950	0.779
5	0.083	9.920	0.870	0.713
6	0.130	9.820	0.770	0.631
7	0.200	9.700	0.650	0.533
8	0.270	9.620	0.570	0.467
9	0.400	9.500	0.450	0.369
10	0.500	9.420	0.370	0.303
11	0.670	9.350	0.300	0.246
12	0.900	9.270	0.220	0.180
13	1.360	9.200	0.150	0.123
14	1.970	9.150	0.100	0.082
15	3.630	9.100	0.050	0.041

SLUG TEST DATA (V4)



o - Data

+ - Type Curve

Slug Test: alpha = -2.0

SOLUTION


Transmissivity = 1.049E-01 ft.<sup>2</sup>/min.  
Storativity = 1.638E-03

Data for Slug Injection/Withdrawal Test

Well Name: VS Date of Test: 9/15/87  
 Well Number: 1  
 Change in Vol. of Water = 0.04 cu.ft.  
 Effective Radius of Well = 0.33 feet  
 Radius of Casing( $r_c$ ) over Water Level Decline = 0.08 feet

Entry No.	Time(t) (min.)	Head (ft.)	H (ft.)	H/H0
1		7.370		
2	0.000	9.370	2.000	1.000
3	0.067	9.270	1.900	0.950
4	0.167	9.200	1.830	0.915
5	0.333	9.100	1.730	0.865
6	0.567	8.970	1.600	0.800
7	0.867	8.850	1.480	0.740
8	1.350	8.700	1.330	0.665
9	1.930	8.550	1.180	0.590
10	2.770	8.370	1.000	0.500
11	3.600	8.250	0.880	0.440
12	4.930	8.070	0.700	0.350
13	6.770	7.900	0.530	0.265
14	8.930	7.750	0.360	0.190
15	13.430	7.570	0.200	0.100
16	18.933	7.450	0.080	0.040

SLUG TEST DATA (V5)



o - Data

+ - Type Curve  
Slug Test:  $\alpha = -2.0$

SOLUTION


Transmissivity = 1.978E-03 ft.<sup>2</sup>/min.  
Storativity = 5.877E-04

Data for Slug Injection/Withdrawal Test

Well Name: V6 Date of Test: 9/15/87  
 Well Number: 1  
 Change in Vol. of Water = 0.01 cu.ft.  
 Effective Radius of Well = 0.33 feet  
 Radius of Casing( $r_c$ ) over Water Level Decline = 0.08 feet

Entry No.	Time(t) (min.)	Head (ft.)	H (ft.)	H/H <sub>0</sub>
1		8.600		
2	0.000	9.270	0.670	1.000
3	0.017	9.070	0.470	0.701
4	0.033	8.870	0.270	0.403
5	0.050	8.770	0.170	0.254
6	0.067	8.750	0.150	0.224
7	0.083	8.700	0.100	0.149
8	0.117	8.670	0.070	0.104
9	0.150	8.650	0.050	0.075
10	0.267	8.620	0.020	0.030

SLUG TEST DATA (V6)



o - Data

+ - Type Curve  
Slug Test:  $\alpha = -7.0$

SOLUTION


Transmissivity = 7.181E-01 ft.<sup>2</sup>/min.  
Storativity = 5.877E-09

Data for Slug Injection/Withdrawal Test

Well Name: V7 Date of Test: 9/15/87  
Well Number: 1  
Change in Vol. of Water = 0.02 cu.ft.  
Effective Radius of Well = 0.33 feet  
Radius of Casing( $r_c$ ) over Water Level Decline = 0.08 feet

Entry No.	Time(t) (min.)	Head (ft.)	H (ft.)	H/H <sub>0</sub>
1		8.520		
2	0.000	9.670	1.150	1.000
3	0.017	9.450	0.930	0.809
4	0.033	9.300	0.780	0.678
5	0.050	9.170	0.650	0.565
6	0.083	8.970	0.450	0.371
7	0.133	8.820	0.300	0.261
8	0.183	8.720	0.200	0.174
9	0.233	8.670	0.150	0.130
10	0.317	8.620	0.100	0.087
11	0.483	8.570	0.050	0.043
12	0.750	8.550	0.030	0.026

SLUG TEST DATA (V7)



o - Data

+ - Type Curve  
Slug Test: alpha = -4.0

SOLUTION

Transmissivity = 1.804E-01 ft.<sup>2</sup>/min.  
Storativity = 5.877E-06



Wahler Associates

## CALCULATION SHEET

SHEET 1 OF 3 SHEETS

PROJECT

Tasco Chemical Corporation

PROJECT NO. JCO-104H

SUBJECT

Slug Test Calculation

CALCULATED BY

D.S.

CHECKED BY

A.C.

FILE

DATE

9/15/87

## Hydraulic Conductivity Calculations

$$K = \frac{T}{b}$$

Well no:

$$V-1 : K = 6.11 \times 10^{-2} / 22 = 2.78 \times 10^{-3} \text{ ft/min} = 1.42 \times 10^{-3} \text{ cm/sec}$$

$$V-2 : K = 6.95 \times 10^{-2} / 12 = 5.79 \times 10^{-3} \text{ ft/min} = 2.95 \times 10^{-3} \text{ cm/sec}$$

$$V-3 : K = 2.98 \times 10^{-2} / 12 = 2.48 \times 10^{-3} \text{ ft/min} = 1.27 \times 10^{-3} \text{ cm/sec}$$

$$V-4 : K = 1.05 \times 10^1 / 7 = 1.5 \times 10^{-2} \text{ ft/min} = 7.65 \times 10^{-3} \text{ cm/sec}$$

$$V-5^* : K = 1.98 \times 10^{-3} / 3 = 6.6 \times 10^{-4} \text{ ft/min} = 3.37 \times 10^{-4} \text{ cm/sec}$$

(low)

$$V-6^* : K = 7.18 \times 10^{-1} / 7 = 1.03 \times 10^{-1} \text{ ft/min} = 5.23 \times 10^{-2} \text{ cm/sec}$$

(high)

$$V-7 : K = 1.8 \times 10^1 / 13.5 = 1.33 \times 10^{-2} \text{ ft/min} = 6.80 \times 10^{-3} \text{ cm/sec}$$

\* Conductivity values used to determine velocity ranges.



Wahler Associates

## CALCULATION SHEET

SHEET 2 OF 3 SHEETSPROJECT Jasco Chemical CorporationPROJECT NO. JCO-104-11SUBJECT Slurry Test CalculationFILE 9/15/87  
DATE CALCULATED BY D.S. CHECKED BY A.C.

Seepage Velocity:

$$V = K \frac{dh}{dl} \frac{1}{n}$$

$$\frac{dh}{dl} = 0.004$$

$$n = 0.4$$

$K$  ranges from  $6.6 \times 10^{-4}$  ft/min to  $1.03 \times 10^1$  ft/min.

Average  $K = 2.04 \times 10^{-2}$  ft/min

Lowest V

$$(V-5) \quad V = 6.6 \times 10^{-4} \times 0.004 \times \frac{1}{0.4}$$

$$V = 6.6 \times 10^{-6} \text{ ft/min}$$

$$\text{Low } V = 3.5 \text{ ft/yr}$$

Highest V

$$(V-6) \quad V = 1.03 \times 10^1 \times 0.004 \times \frac{1}{0.4}$$

$$= 1.03 \times 10^3 \text{ ft/min}$$

$$\text{High } V = 541.4 \text{ ft/yr}$$

Average V

$$V = 2.04 \times 10^{-2} \times 0.004 \times \frac{1}{0.4}$$

$$\text{Average } V = 107.2 \text{ ft/yr}$$



Wahler Associates

## CALCULATION SHEET

SHEET 3 OF 3 SHEETS

PROJECT

SUBJECT

Slug Test CalculationsPROJECT NO. JCO-104 H

CALCULATED BY

D.S.

CHECKED BY

A.C.

FILE

DATE

9/15/87

Other Seepage Velocities:

$$V-1: V = (2.73 \times 10^{-3} \times 0.004 \times \frac{1}{0.4}) \text{ ft/min} = 14.6 \text{ ft/yr}$$

$$V-2: V = (5.79 \times 10^{-3} \times 0.004 \times \frac{1}{0.4}) \text{ ft/min} = 30.4 \text{ ft/yr}$$

$$V-3: V = (2.48 \times 10^{-3} \times 0.004 \times \frac{1}{0.4}) \text{ ft/min} = 13.0 \text{ ft/yr}$$

$$V-4: V = (1.5 \times 10^{-2} \times 0.004 \times \frac{1}{0.4}) \text{ ft/min} = 78.8 \text{ ft/yr}$$

$$V-7: V = (1.33 \times 10^{-2} \times 0.004 \times \frac{1}{0.4}) \text{ ft/min} = 70.0 \text{ ft/yr}$$